

## **1.0 - FLARE Materials Test Station and TPC Cryogenic Safety Report**

- 1.1 Materials Test Station System Description
- 1.2 Flow Schematic
- 1.3 Instrument and Valve Summary
- 1.4 System Control Loops, Interlocks, and Electrical Schematics
- 2.1a Procedure for Filling “Luke”
- 2.1b Procedure for Emptying “Luke”
- 2.1c Procedure for Operating “Air Lock” During Material Insertion
- 2.1d Procedure for Operating “Air Lock” During Material Removal
- 2.1e Procedure for Filling the LN2 dewar
- 2.1f Normal Nitrogen Circuit Valve Positions During Operation
- 2.1g Procedure for Connecting Stockroom Liquid Argon Dewars to the System
- 2.1h Procedure for Removing Stockroom Liquid Argon Dewars from the System
- 2.1i Procedure for Molecular Sieve Regeneration
- 2.1j Procedure for O2 Filter Regeneration
- 2.1k Procedure for filling “Bo”
- 2.1l Procedure for emptying “Bo”
- 2.2a Startup Check List for Filling the Material Test Station (“Luke”)
- 2.2b Startup Check List for Filling the TPC Cryostat (“Bo”)
- 2.3 Training List for Operators of the FLARE Material Test Station (“Luke”) and the TPC cryostat (“Bo”)
- 3.1 FMEA
- 3.2 WHAT-IF WORKSHEET
- 3.5a1 ODH Analysis of the Proton Assembly Building for the FLARE Materials Test Station and the TPC Cryostat.
- 3.5a2 ODH Fan Manufacturer Info
- 3.5b1 Pressure Vessel Engineering Note for “Luke” Including Relief Valve Certification and U-1A Manufacturers Data Report for Pressure Vessels
- 3.5b2 Updated Pressure Vessel Engineering Note for PAB (Formally PS1) Liquid Nitrogen Dewar Including Relief Valve Certifications.
- 3.5b3 Old Pressure Vessel Engineering Note for PS1 Liquid Nitrogen Dewar
- 3.5b4 Vacuum Vessel Engineering Note for PS1 Liquid Nitrogen Dewar

- 3.5b5 Pressure Vessel Engineering Note for “Bo” Including Relief Valve Certification and U-1A Manufacturers Data Report for Pressure Vessels
- 3.5c PAB LN2 Dewar Compliance with Fermilab ES&H 5032.1TA
- 3.5d LN2 Dewar Fill Line Pressure Test Documentation
- 3.5e LN2 Transfer Line Pressure Test Documentation
- 3.5f LAr Transfer Line Pressure Test Documentation (up to “Luke”)
- 3.5g “Luke” Materials Lock Bellows and Gate Valve Pressure Test
- 3.5h LN2 Dewar Piping Pressure Test
- 3.5i “Bo” High Voltage Feed Thru Pressure Test
- 3.5j “Bo” Signal Feed Thru Pressure Test
- 3.5k “Bo” LAr Piping Pressure Test
- 4.1a Relief Valve Sizing for the FLARE Materials Test Station and TPC Cryostats With Supporting Documentation
- 4.1aa Supporting Documentation for Relief Valve Calculations
- 4.1b Relief Valve Sizing for Piping Associated with the FLARE Materials Test Station and TPC Cryostats
- 4.1c Relief Valve Sizing for the PAB LN2 Dewar
- 4.2 Material Stress Levels
- 4.3 Correspondence Related to Operational Readiness Clearance

## **1.1 - System Description**

The Liquid Argon R&D effort at Fermilab has fabricated a materials test station and a time projection chamber (TPC) at the Proton Assembly Building (PAB). Liquid argon time projection chambers (LArTPCs) are the future of long-baseline neutrino oscillation physics and present several engineering challenges.

When a high energy charged particle passes through a medium, the particle leaves a path of ionization electrons which can be detected, tagging the path of the incoming particle. In a LArTPC, the medium is liquid argon (LAr) and the paths of ionization electrons are detected by drifting the electrons over meters to wire planes. These wire planes are oriented in such a way that the magnitude and position of each path can be reconstructed. Thus a data acquisition system records many snapshots of the appearance of ionization electrons each second [at 2-3 MHz]. Put in sequence, physicists can reconstruct each particle's path, which results in gorgeous bubble-chamber-like images. From the topology and energy deposited along each track, specific interactions can be reconstructed.

The materials test station will help determine what materials can be used to construct a detector without polluting the argon. Purity is an issue because polar molecules and atoms without full outer electron shells (which every element has except for noble gases, which argon is) attract electrons. These contaminants - predominantly water and oxygen - will absorb the ionization electrons to make themselves happy, at the expense of the evidence of the particle interaction. Liquid argon calorimeters have been successfully operated at Fermilab with electro-negative contaminants at the level of  $10^{-7}$ . The liquid argon TPC requires electronegative contaminants not to exceed  $10^{-11}$  or 10 parts per trillion.

To measure such contamination levels, a purity monitor is used. The purity monitor measures purity by firing a light pulse from a xenon lamp at a photocathode and then drifting the ejected electrons to the anode with an electric field. The fraction of electrons surviving the transit from the cathode to the anode gives a measure of the argon.

Fermilab print 3942.510-ME-435365 documents the cryogenic system piping.

The materials test station (Luke) is a 250 liter liquid argon ASME coded cryostat. The cryostat has several key features.

- An “air lock” for introducing materials into the liquid argon. Materials are placed into a basket above a gate valve. The space above the valve can either be evacuated or purged with argon to remove the atmospheric contaminants. This basket can then be lowered into cryostat and positioned in the argon vapor or the argon liquid to study the contamination effects of the test material.

- A vapor pump with oxygen and water removing filter material. The pump uses a heater to create vapor which pushes the liquid argon out the bottom of the filter housing. When the heater is turned off, a valve opens at the top of the filter which equalizes the pressure in the filter and cryostat vapor spaces and allows liquid to flow back into the filter housing. All tubing used to construct the filter assembly is less than 6 inches in diameter such that no part of it is a pressure vessel.
- A condenser that uses liquid nitrogen to condense the liquid argon boil off vapor so that the system may remain closed. All tubing used to construct the condenser LAr and LN2 spaces is less than or equal to 6 inches in diameter such that it is not a pressure vessel. The argon vapor condensation rate is controlled by adjusting the level of liquid nitrogen in the condenser.
- The use of metal seals on all flanges to prevent the diffusion of oxygen that occurs with o-rings. The only o-rings in the system are on relief valves and the large top flange. The down stream side of the relief valves are purged with argon to prevent oxygen diffusion. The space between the two concentric o-rings on the top flange is evacuated to prevent oxygen diffusion.
- Ports on the cryostat allow the introduction of contamination gas to study the effects of nitrogen, carbon dioxide, etc.
- An internal heater to build vapor pressure for quick control response.

Liquid argon is supplied by up to four FNAL stockroom high pressure dewars. These supply dewars have their reliefs set at 350 psig. The trapped volume reliefs on the liquid argon transfer line are set at 400 psig. Thus all components between the source dewars and the cryostat are rated for at least 400 psig.

The “P-bar Molecular Sieve Filtering Dewar” contains a molecular sieve intended to remove water from the liquid argon. The dewar is a vacuum jacketed ASME vessel originally used to store liquid helium with an internal MAWP of 35 psig. In this implementation it is just a convenient method to support and insulate a filter housing. Both the vacuum jacket and inner vessel are evacuated during operation. The liquid argon is contained in the piping and filter housing. The liquid does not reside in the inner vessel. This system is not considered a pressure vessel because it is relieved at atmospheric pressure. The molecular sieve is regenerated by isolating the filter housing and heating the filter material while vacuum pumping. With an internal volume of 160 liters, the dewar is too small to fall under the FESHM 5033 Vacuum Vessel Safety Guidelines.

The “P-bar Oxygen Filtering Dewar” contains an oxygen filter that removes oxygen by oxidation to a high surface area copper alumina catalyst. The dewar is a vacuum jacketed ASME vessel identical to the “P-bar Molecular Sieve Filtering Dewar.” Both the vacuum jacket and inner vessel are

evacuated during normal operation and the inner vessel shares a common vacuum with much of the liquid argon transfer line. The liquid argon is contained in the piping and filter housing. The liquid does not reside in the inner vessel. In this system it is not considered a pressure vessel because it is relieved at near atmospheric pressure. The oxygen filter is regenerated by heating the filter to 250 °C and flowing a mixture of 5% hydrogen and 95% argon thru the filter while the filter is isolated from the rest of the system. The gas mix is considered flammable and the system was previously reviewed by Jim Priest.

Liquid nitrogen is supplied to Luke's condenser from an 1875 gallon liquid nitrogen tank located outside PAB. The liquid nitrogen flows thru a vacuum jacketed line into PAB where solenoid valves control the flow. A cool down valve bypasses the condenser so that warm vapor is not added to the condenser. All nitrogen gas vents outside PAB. The liquid nitrogen tank is equipped with a fill shut off valve to prevent overfilling of the tank by the tanker truck.

A cryostat identical to Luke (known as "cousin Bo") contains the small TPC wire chamber. The chamber is a vertical cylinder about 22 inches high and 12 inches in diameter. Electrons drift upward thru the chamber. The TPC has 150 wires total, which are contained in 3 planes. The wire spacing is 4.7 mm. The materials involved in the TPC construction are copper-clad G-10, G-10, copper-beryllium wire, solder, HDPE pipe, and some stainless tube. Figure 1.1.9 shows the size of the chamber relative to the cryostat. A photo of the wire chamber being lowered into the cryostat is shown in Figure 1.1.10.

Purified argon reaches Bo using the same filling manifold and filters that are used to charge Luke. Figure 1.1.11 shows the path of liquid argon takes to reach Bo. In the future, it is likely a nitrogen powered condenser identical to the one on Luke will be added to Bo.




Figure 1.1.1: Drawing of the transfer line, filters, and material test station cryostat (“Luke”).




Figure 1.1.2: Photo of the transfer line, filters, and material test station cryostat.

# AirLock




Figure 1.1.3: Schematic of the air lock used for material testing.



Figure 1.1.4: Photo of the air lock used for material testing.




Figure 1.1.5: Schematic of the internal filter found in the material test station cryostat (“Luke”).




Figure 1.1.6: Drawing of the condenser.

REV	DESCRIPTION	DATE	BY	CHECKED
43	166-301109	1/10/08	MM	MM
42	166-301109	1/10/08	MM	MM
41	166-301109	1/10/08	MM	MM
40	166-301109	1/10/08	MM	MM
39	166-301109	1/10/08	MM	MM
38	166-301109	1/10/08	MM	MM
37	166-301109	1/10/08	MM	MM
36	166-301109	1/10/08	MM	MM
35	166-301109	1/10/08	MM	MM
34	166-301109	1/10/08	MM	MM
33	166-301109	1/10/08	MM	MM
32	166-301109	1/10/08	MM	MM
31	166-301109	1/10/08	MM	MM
30	166-301109	1/10/08	MM	MM
29	166-301109	1/10/08	MM	MM
28	166-301109	1/10/08	MM	MM
27	166-301109	1/10/08	MM	MM
26	166-301109	1/10/08	MM	MM
25	166-301109	1/10/08	MM	MM
24	166-301109	1/10/08	MM	MM
23	166-301109	1/10/08	MM	MM
22	166-301109	1/10/08	MM	MM
21	166-301109	1/10/08	MM	MM
20	166-301109	1/10/08	MM	MM
19	166-301109	1/10/08	MM	MM
18	166-301109	1/10/08	MM	MM
17	166-301109	1/10/08	MM	MM
16	166-301109	1/10/08	MM	MM
15	166-301109	1/10/08	MM	MM
14	166-301109	1/10/08	MM	MM
13	166-301109	1/10/08	MM	MM
12	166-301109	1/10/08	MM	MM
11	166-301109	1/10/08	MM	MM
10	166-301109	1/10/08	MM	MM
9	166-301109	1/10/08	MM	MM
8	166-301109	1/10/08	MM	MM
7	166-301109	1/10/08	MM	MM
6	166-301109	1/10/08	MM	MM
5	166-301109	1/10/08	MM	MM
4	166-301109	1/10/08	MM	MM
3	166-301109	1/10/08	MM	MM
2	166-301109	1/10/08	MM	MM
1	166-301109	1/10/08	MM	MM

1650-ME-381151

REduced COPY - DO NOT SCALE

1650-ME-381151



Figure 1.1.7: Photo of a purity monitor (that's the big one).






Figure 1.1.9: Schematic of TPC in Bo.



Figure 1.1.10: Insertion of the TPC into Bo.



## **1.2 – Flow Schematic**

Drawing number 3942.510-ME-435365 details the piping and instrumentation associated with the material test station and the TPC cryostat.

NOTE: 1. ALL SYMBOLS CONFORM TO ANSI/ISA S5.1-1984(R1992) STANDARDS UNLESS OTHERWISE SPECIFIED.


2. LINE DEFINITIONS:

- GAr LINES
- VACUUM LINES
- LAr LINES
- LN2 LINES
- GN2 LINES
- WALLS, BOUNDARYS, ECT.

3. BLUE PLASTIC TUBING-ARGON  
 YELLOW PLASTIC TUBING-SHOP AIR  
 RED PLASTIC TUBING-HELIUM  
 WHITE PLASTIC TUBING-NITROGEN

4. LEGEND:

- AE-ANALYZING ELEMENT
- CV-CHECK VALVE
- CVI-VACUUM PUMP/RELIEF
- DPT-DIFFERENTIAL PRESSURE TRANSMITTER
- EP-PNEUMATIC VALVE
- EV-ELECTRIC VALVE
- FI-FLOW INDICATOR
- FO-FLOW ORIFICE
- HTR-HEATER
- LT-LEVEL TRANSMITTER
- MV-MANUAL VALVE
- PCV-PRESSURE CONTROL VALVE
- PE-PRESSURE ELEMENT (VACUUM)
- PI-PRESSURE INDICATOR
- PT-PRESSURE TRANSMITTER
- PRV OR RV-PRESSURE REGULATING VALVE
- PSV OR SV-PRESSURE SAFETY VALVE
- TE-TEMPERATURE ELEMENT



UNLESS OTHERWISE SPECIFIED	ORIGINATOR	T.TOPE	09-JUN-2005
±	DRAWN	N.CADENA	17-JUN-2005
±	CHECKED	T.TOPE	15-MAY-2008
±	APPROVED	T.TOPE	15-MAY-2008
±	USED ON		
	MATERIAL		

1. BREAK ALL SHARP EDGES  
 2. DO NOT SCALE DRAWING.  
 3. DIMENSIONS BASED UPON  
 4. MAX. ALL MACH. SURFACES  
 5. DRAWING UNITS:

**FERMI NATIONAL ACCELERATOR LABORATORY**  
 UNITED STATES DEPARTMENT OF ENERGY

**FLARE-P942  
 GAS SYSTEM  
 ARGON PURIFICATION SYSTEM**

SCALE	DRAWING NUMBER	SHEET	REV
NONE	3942.510-ME-435365	1 OF 1	

CREATED WITH: IDeas12NXSeries GROUP: PPD/MECHANICAL DEPARTMENT

### 1.3 - Instrument and Valve Summary

Type	Tag	Tag	Loc	Service	Range or Set point	Manufacturer	Model or Part #	Signal Out	Maximum Pressure
<b>Analyzing elements</b>									
AE	311	Ar	G2	Oxygen Analyzer	0 - 100 ppm	Delta F	DF-150	0 - 10 VDC	20 psig
AE	52	HAr	E7	Filter regeneration moisture monitoring (close to exhaust)	-80 to + 20 C	Vaisala	DMT242A	4-20 mA	290 psig
AE	151	HAr	D4	Filter regeneration moisture monitoring (close to filter)	-60 to + 60 C	Vaisala	DMT242B	4-20 mA	290 psig
AE	321	Ar	***	Oxygen Analyzer	0 - 20 ppm	Delta F	DF-560	4-20 mA	20 psig
AE	322	Ar	***	Nitrogen Arc Cell	0 - 100 PPM	FNAL	-----	0 -10 VDC	~ atm
<b>Check valves</b>									
CV	90	N	F8	LN2 dewar fill line check valve	no spring	Check-All Valve	UN-3-150-SS	-----	3000 psig
CV	150	Ar	F4	LAr vent line	1 psid	Circle Seal	249B-8PP	-----	3000 psig
CV	100	N	F6	LN2 dewar liquid use line	no spring	Fermlab	1/2" cryogenic check valve	-----	>> 100 psig
CV	257	Ar	D2	"Air lock" vent line backflow prevention	3 psid	Nupro	SS-4CA-VCR	-----	3000 psig
CV	266	N2	B5	Insulating vacuum bleed up check valve	0.8 psid	Circle Seal	2598-2PP	-----	3000 psig
CV	309	HAr	D5	O2 filter regeneration check valve	< 1 psid	Parker - Veriflo Division	36FW-442VMM-V	-----	3000 psig
CV	415	HAr	E7	Regeneration gas ventline back flow prevention	1/3 psid	Parker	4Z(A)-C4L 1/3-SS	-----	6000 psig
<b>Pump out ports</b>									
CVI	138	V	B3	Luke insulating vacuum pumpout and relief	~ 1 atm (spring removed)	CVI	V-1046-31	-----	~ atm
CVI	187	V	C7	Molecular sieve pbar dewar insulating vacuum pumpout/relief	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	207	V	B8	Liquid argon source manifold insulating vacuum pumpout and relief	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	220	V	C7	Pbar molecular sieve dewar inner vessel pumpout/relief	~ 1 atm (spring removed)	CVI	V-1046-31	-----	~ atm
CVI	259	V	D1	Luke LN2-LAr condenser insulating vacuum pumpout/relief	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	260	V	D2	LN2 transfer line vacuum pumpout/relief near Luke	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	285	V	E6	LN2 transfer line vacuum pumpout/relief dewar side	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	286	V	E6	LN2 transfer line vacuum pumpout/PAB side	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	289	V	B4	O2 filter pbar dewar insulating vacuum pumpout/relief	~20 psig	CVI	V-1046-31	-----	~ atm
CVI	382	V	A6	Bo insulating vacuum pumpout and relief	~ 1 atm (spring removed)	CVI	V-1046-31	-----	~ atm
<b>Differential pressure transmitters</b>									
DPT	67	Ar	C3	Luke Vapor Pump filter liquid level	0 - 5 psid	Setra	C239	4-20 mA	75 psig
DPT	100	N	G7	Liquid Nitrogen Dewar	0 - 80" wc	Barton	ITI3	4-20 mA	500 psig
<b>Pneumatic valves</b>									
EP	78	Ar	C2	Luke vapor pump equalization valve	Normally Closed - 100 psig actuation pressure	Swagelok	SS-6UW-V19-TF-6C	-----	2500 psig
EP	155	V	C5	Oxygen filter vacuum isolation	normally closed	VAT	F29615-17	-----	~ atm
EP	205	Ar	C1	Luke Ar vent	Normally Closed - 100 psig actuation pressure	Swagelok	SS-6UW-V19-TF-6C	-----	2500 psig
EP	222	V	C5	Molecular sieve insulating vacuum isolation	normally closed	MDC	KAV-150-P	-----	~ atm
EP	236	V	A4	Cryostat pump cart inter-stage isolation (turbo protection)	normally closed	Varian	VPI251205060	-----	~ atm
EP	308	Ar	B2	Luke vapor pump liquid inlet	10 psig to close, vacuum to fully open	Fermlab	H2 target cold valve - print# 2726.4-MB-58267	-----	45 psig
EP	347	V	A3	Seal monitor pump cart anti-suck back valve	normally closed	Norcal	3870-01455	-----	~ atm
EP	362	V	C5	LAr transfer line insulating vacuum isolation	normally closed	Temascal	45130	-----	~ atm
EP	383	V	A5	Bo vacuum pump cart turbo protection valve	normally closed	VAT	108-UE44-0006/0175	-----	~ atm
<b>Electric valves</b>									
EV	79	Air	C2	EP-78-Ar actuation	normally closed	Asco	8320G132 (24 VDC)	24 VDC	200 psig
EV	105	N2	D2	LN2 transfer line into Luke condenser	normally closed	Asco	8263G209LT (120 VAC)	120 VAC	100 psig
EV	106	N2	E5	LN2 transfer line vent	normally closed	Asco	8263G209LT (120 VAC)	120 VAC	100 psig
EV	223	Air	C5	EP-222-V actuation	normally closed	Humphrey	31039 RC	120 VAC	125 psig
EV	232	Air	C6	EP-155-V actuation	normally closed	Huba	???	120 VAC	> 100 psig
EV	233	Air	C6	EP-362-V actuation	normally closed	Humphrey	T125 4E136	120 VAC	125 psig
EV	258	Air	D2	Material basket catch/release mechanism actuation	normally closed	Humphrey	062-4E1-36	120 VAC	125 psig
EV	270	N2	D1	EP-205-Ar actuation	normally closed	Asco	8320G132 (24 VDC)	24 VDC	200 psig
EV	287	V	A4	EP-236-V actuation	normally open	Peter Paul Electronics	51X0011CD	120 VAC	~ atm
EV	346	AIR	A3	Seal monitor pump cart anti-suck back valve actuation	normally closed	ARD Fluid Power	A2155-120-A-G	120 VAC	100 psig
EV	384	V	B5	EP-383-V actuation	normally closed	MAC	N-7557-019	120 VAC	100 psig
<b>Filters</b>									
F	395	Ar	F3	Removal of O2, H2O, and HCs from Luke contamination gas	-----	Airgas	Y40-RES0010K	-----	160 psig

**Flowmeters**

FI	278	Ar	F2	Luke vapor pump trapped volume relief (PSV-156-Ar)	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	279	Ar	F2	Luke vapor pump electronic purge	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	280	Ar	F1	Luke ASME relief purge (PSV-210-Ar)	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	281	Ar	F1	Molecular sieve trapped volume relief purge (PSV-219-Ar)	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	282	Ar	F1	O2 filter inlet side trapped volume relief (PSV-249-Ar)	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	283	Ar	F1	O2 filter outlet side trapped volume relief (PSV-250-Ar)	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	284	Ar	F1	Material lock release mechanism argon purge	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	312	Ar	G2	Oxygen monitor inlet flowrate	0 - 5 SCFH SP is 2 SCFH N2 equiv	Dwyer	VFA-3	-----	150 psig
FI	315	Ar	F1	Air lock argon purge flowmeter	0 - 10 SCFH	Dwyer	RMB-50-SSV	-----	100 psig
FI	390	Ar	E2	Bo ASME relief purge (PSV-378-Ar)	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	391	Ar	E2	Not in use	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	392	Ar	E2	Not in use	0 - 50 sccm	Dwyer	RMA-151-SSV	-----	100 psig
FI	406	Har	D6	Oxygen filter regeneration gas flow rate (metering valve limits to 5 SCFH)	0 - 50 SCFH	Dwyer	RMB-52-SSV	-----	100 psig

**Flow restricting orifices**

FO	212	Ar	C7	Liquid argon source manifold argon flow restriction	0.122" dia.	Fermlab	-----	-----	-----
----	-----	----	----	---	-------------	---------	-------	-------	-------

**Heating elements**

HTR	8	Har	B4	Oxygen filter regeneration heater	1000W / 240 VAC	Omega	heating tape compressed by a clamshell	-----	-----
HTR	21	Ar	B1	Luke vapor pressure building heater	250 W /120 VAC	Watlow	Firerod	-----	-----
HTR	22	Ar	A6	Bo vapor pressure building heater	250 W /120 VAC	Watlow	Firerod	-----	-----
HTR	55	Har	B4	Oxygen filter gas pre-heater	150 W / 120 VAC	Watlow	Firerod	-----	-----
HTR	72	Har	C1	Luke vapor pump filter regeneration heater	1500 W / 120 VAC	Watlow	Firerod	-----	-----
HTR	75	Ar	C1	Luke vapor pump cup heater	250 W / 120 VAC	Watlow	Firerod	-----	-----
HTR	215	Ar	C7	Molecular sieve regeneration heater	1000W / 240 VAC	Omega	heating tape compressed by a clamshell	-----	-----

**Output to DAQ**

INTL	325	Ar	*	24 VDC output to purity monitor for liquid level interlock	-----	-----	-----	-----	-----
------	-----	----	---	--	-------	-------	-------	-------	-------

**Liquid level transmitters**

LT	10	N2	D1	Luke condenser LN2 level	0-20.5 inches	American Magnetics	Model 286 Controller	4-20 mA	> 35 psig
LT	13	Ar	C3	Luke cryostat LAr level	0-39.62 inches	American Magnetics	Model 286 Controller	4-20 mA	> 35 psig
LT	372	Ar	B7	Bo cryostat LAr level	0-39.62 inches	American Magnetics	Model 286 Controller	4-20 mA	> 35 psig

**Manual valves**

MV	80	N	G6	LN2 dewar pressure gauge isolation	-----	Swagelok	SS-4BK-VCO	-----	1000 psig
MV	85	N	F6	LN2 dewar vapor line pressure sensing isolation	-----	Anderson Greenwood	MM1VS 2-8174-3	-----	6000 psig
MV	86	N	F7	LN2 dewar level gauge equalization	-----	Anderson Greenwood	MM1VS 2-8174-3	-----	6000 psig
MV	87	N	F7	LN2 dewar liquid line pressure sensing isolation	-----	Anderson Greenwood	MM1VS 2-8174-3	-----	6000 psig
MV	88	N	G6	LN2 dewar pressure building regulator isolation	-----	Nibco	???	-----	600 psig
MV	89	N	H6	LN2 dewar pressure building loop isolation	-----	Nibco	???	-----	600 psig
MV	90	V	F8	LN2 dewar vacuum pump out	-----	Vacua	FO-100	-----	~ atm
MV	90	N	H7	LN2 dewar pressure relieving regulator isolation	-----	Nibco	???	-----	600 psig
MV	91	V	F7	LN2 dewar vacuum readout isolation	-----	Nupro	SS-4BK-VCO	-----	1000 psig
MV	91	N	E7	LN2 dewar fill line drain valve	-----	Worcester	1/2 C4416P	-----	870 psig
MV	92	N	F7	LN2 dewar fill line isolation	-----	Worcester	1 1/2 C4416P	-----	870 psig
MV	93	N	H7	LN2 dewar vapor vent	-----	Nibco	???	-----	600 psig
MV	94	N	G8	LN2 dewar full trycock	-----	Nibco	???	-----	600 psig
MV	95	N	F6	LN2 dewar pressure building loop bypass	-----	Nibco	???	-----	600 psig
MV	96	N	F6	LN2 dewar pressure building regulator isolation	-----	Nibco	???	-----	600 psig
MV	97	N	F6	LN2 dewar liquid withdrawal	-----	Cryolab	EST-86-2TPC2	-----	???
MV	98	N	H7	LN2 dewar relief valve selector	-----	Anderson Greenwood	SVS-0600T-BSTC	-----	1200 psig
MV	99	N	H7	LN2 dewar vapor vent valve	-----	Anderson Greenwood	HSVB 22	-----	> 75 psig
MV	100	N	F6	LN2 dewar liquid into PAB isolation	-----	Cryolab	CV8-086-SWPY22-ED	-----	150 psig
MV	101	N	H7	LN2 dewar vapor vent valve	-----	Anderson Greenwood	HSVB 22	-----	> 75 psig
MV	107	N	F6	LN2 dewar isolation for future gas use	-----	Nibco	???	-----	600 psig
MV	119	N	F6	LN2 liquid transfer line branch isolation	-----	Cryolab	CV8-084-SWTG2	-----	100 psig
MV	120	N	E6	LN2 liquid transfer line Luke/Bo branch isolation	-----	Cryolab	CV8-086-SWPG2	-----	150 psig
MV	124	Ar	E3	Ar with O2 contamination source bottle regulator outlet isolation	-----	Scientific Gas Products	5939	-----	3000 psig
MV	127	Ar	E3	Ar with O2 contamination source line regulator outlet isolation	-----	Nupro	B-4HK2	-----	1000 psig
MV	128	Ar	E3	Gas contamination introduction isolation	-----	Swagelok	SS-4BK-TW	-----	1000 psig
MV	131	N2	F3	N2 contamination source regulator outlet isolation	-----	Swagelok	SS-4BK-TW	-----	1000 psig
MV	132	N2	G3	Contamination manifold vacuum isolation	-----	Swagelok	SS-4BK-VCO	-----	1000 psig
MV	202	Ar	C4	Filter assembly inlet isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	204	Ar	B8	Liquid argon source manifold argon line isolation/pumpout	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	208	Ar	C4	Filter assembly outlet isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	213	Ar	C7	Liquid argon source manifold isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	217	Ar	C7	Molecular sieve isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	218	Ar	C7	Molecular sieve isolation/pumpout	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	224	V	A5	Transfer line insulating vacuum pump cart roughing pump port isolation	-----	Leybold	281 53B1	-----	~ atm

MV	227	V	A5	Insulating vacuum pump cart port isolation	-----	MKS	22406	-----	~ atm
MV	228	V	A5	Insulating vacuum pump cart port isolation	-----	Leybold	281 53B1	-----	~ atm
MV	229	V	A4	Cryostat pump cart port isolation	-----	Unknown model	Unknown brand	-----	~ atm
MV	237	V	A3	Seal monitor pump cart isolation	-----	Norcal	3879-01455	-----	~ atm
MV	239	Ar	B6	Liquid argon bypass for both Luke and Bo	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	241	Ar	C3	Gas contamination introduction isolation	-----	Parker/Veriflo	930 series	-----	250 psig
MV	242	Ar	C3	Gas contamination introduction isolation	-----	Swagelok	6LV-DLBW4	-----	3500 psig
MV	244	Ar	C3	Luke cryo isolation valve	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	246	Ar	D3	Gas contamination introduction isolation	-----	Swagelok	6LV-DLBW4	-----	3500 psig
MV	247	Ar	C3	Luke vapor pump filter regeneration gas outlet isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	248	Ar	C2	Luke vapor pump filter regeneration gas inlet isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	251	V	C2	"Air lock" vacuum isolation	-----	MDC	AV-150	-----	~ atm
MV	252	Ar	C2	"Air lock" argon bottle purge isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	253	Ar	C2	"Air lock" cryostat vapor purge isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	254	V	C2	Luke materials test station air lock pass thru	-----	Norcal	GVM-6002-CF	-----	> 35 psig
MV	255	Ar	C1	Luke manual vapor vent	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	256	Ar	C2	"Air lock" purge vent isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	261	V	B1	Luke insulating vacuum isolation/pumpout	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	265	N2	B5	Bleed up cylinder regulator outlet isolation	-----	Parker	???	-----	~ 1000 psig
MV	267	V	C5	Transfer line insulating vacuum nitrogen bleed up isolation	-----	Swagelok	SS-4BK-VCO	-----	1000 psig
MV	268	Air	E1	Shop air isolation	-----	Worcester	1/2" 416N SE	-----	250 psig
MV	277	Ar	F2	Argon purge regulator outlet isolation	-----	Legris	Appears to be a 4812 10 17	-----	2030 psig
MV	290	Ar	C2	Air lock purge inlet isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	291	Ar	D2	Air lock purge oxygen monitor isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	294	Ar	G1	Oxygen monitor manifold inlet isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	295	V	G1	Oxygen monitor vacuum pump isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	296	Ar	F1	Oxygen monitor open port isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	300	Ar	G2	Oxygen monitor metering valve	-----	Swagelok	SS-4MG-XX	-----	700 psig
MV	310	Ar	G2	Oxygen monitor inlet isolation	-----	Nupro	SS-DLXX	-----	3500 psig
MV	316	Ar	F2	Argon purge flowmeter manifold inlet isolation	-----	Unknown Brand	Unknown Model	-----	~ 1000 psig
MV	327	Ar	D1	Luke condenser argon space vent	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	328	Ar	C2	Luke vapor pump equalization isolation	-----	Swagelok	SS-8BG-TW	-----	1000 psig
MV	329	Ar	C2	Luke vapor pump vent isolation	-----	Swagelok	SS-8BG-TW	-----	1000 psig
MV	333	CO2	D3	Vapor pump transport CO2 bottle regulator outlet isolation	-----	Parker	4FM-PR4-VT-B	-----	3000 psig
MV	336	V	C3	Vapor pump cold valve vacuum isolation	-----	Swagelok	SS-4BK-TW	-----	1000 psig
MV	337	He	C3	Vapor pump cold valve isolation at vapor pump top flange	-----	Nupro	SS-4P4T4	-----	3000 psig
MV	338	He	C3	Vapor pump cold valve He supply isolation	-----	Nupro	SS-4BK-VCO	-----	1000 psig
MV	342	He	D4	He bottle regulator outlet isolation	-----	Unknown Brand	Unknown Model	-----	~ 3000 psig
MV	354	Ar	C3	Luke liquid space tap isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	360	V	B3	Luke vacuum pumpout isolation valve	-----	MDC	AV-250	-----	~ atm
MV	365	V	C5	O2 filter vacuum isolation (downstream tap)	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	366	V	C5	O2 filter vacuum isolation (upstream tap)	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	368	V	A7	Bo insulating vacuum isolation	-----	Swagelok	SS-4BG-V51	-----	1000 psig
MV	369	V	A7	Bo insulating vacuum isolation/pumpout	-----	Balzars	EVA 016H	-----	~ atm
MV	370	Ar	C3	Luke drain valve	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	375	N2	D5	PT-27-N2 isolation	-----	Parker	4F-PR4-VT-B	-----	3000 psig
MV	379	Ar	B6	Bo LAr fill isolation valve	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	380	Ar	B6	Bo venting isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	381	V	B6	Bo inner vessel vacuum pumpout	-----	MDC	AV250	-----	~ atm
MV	386	V	A5	Bo vacuum pump cart rough pump isolation	-----	Leybold	2870282	-----	~ atm
MV	387	V	B5	Bo vacuum pump cart bleed up valve	-----	Rial	Unknown Model	-----	~ atm
MV	393	Ar	F2	Luke contamination gas filter isolation	-----	Carten	MD250-05-LV	-----	375 psig
MV	394	Ar	F3	Luke contamination gas filter isolation	-----	Carten	MD250-05-LV	-----	375 psig
MV	401	HAr	E8	5% H2 95% Ar O2 filter regeneration gas metering valve	-----	Swagelok	SS-SS4-VH	-----	2000 psig
MV	418	HAr	E7	Regeneration vacuum pump isolation	-----	Whitey	B-42S4	-----	2500 psig
MV	419	HAr	E7	Regeneration vacuum pump isolation	-----	Whitey	B-42S4	-----	2500 psig
MV	420	HAr	E7	Regeneration vacuum pump bleed up	-----	Nupro	B-4JN	-----	600 psig
MV	461	HAr	C4	One pass fill filter regeneration isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	480	HAr	C5	One pass fill filter regeneration isolation	-----	Swagelok	SS-8BG-V47	-----	1000 psig
MV	V2	Air	D8	Regulator isolation	-----	Swagelok	SS-4P4T4	-----	3000 psig
MV	V4	Air	D8	Regulator isolation	-----	Swagelok	SS-4P4T4	-----	3000 psig
MV	V7	Ar	D7	Line pressure regulator outlet isolation	-----	Concoa	Unknown Model	-----	~ 1000 psig
MV	V8	HAr	E7	Regeneration vacuum pump isolation	-----	Swagelok	B-4HK	-----	1000 psig
MV	V9	HAr	D6	Bench top oxygen filter regeneration isolation	-----	Swagelok	SS-4P4T4	-----	3000 psig
MV	V10	HAr	D7	Regeneration gas isolation	-----	Swagelok	SS-4P4T4	-----	3000 psig
MV	V12	HAr	D7	Regeneration gas isolation	-----	Swagelok	SS-4P4T4	-----	3000 psig
MV	V14	HAr	E8	5% H2 95% Ar O2 filter regeneration gas bottle regulator outlet isolation	-----	Matheson	LMF4373	-----	3500 psig
MV	V17	HAr	E7	Regeneration gas isolation	-----	Swagelok	SS-4P4T4	-----	3000 psig

**Pressure regulators and pressure control valves**

PCV	70	N	F8	Fill shut off valve (Sensitive to vibration)	75 psig (MAWP)	Messer / Chart	MG-97 P	-----	600 psig
PCV	121	Ar	E3	Ar with O2 contamination source bottle regulator	30 psig	Scientific Gas Products	R35D 350	-----	3000 psig
PCV	125	Ar	E3	Ar with O2 contamination source line regulator	10 psig (25 psig max outlet)	Air Products	E11-B-N141A	-----	400 psig
PCV	129	N2	F3	Nitrogen contamination source bottle regulator	30 psig	Parker / Veriflo	735 series	-----	3500 psig
PCV	262	N2	B5	LA transfer line insulating vacuum bleed up regulator	10 psig	Victor	VTS 450B	-----	3000 psig
PCV	269	Air	E1	Shop air point of use regulator	100 psig (0-125 psig range)	Norgren	B12-496-M3LA	-----	250 psig
PCV	273	Ar	F2	Argon purge bottle regulator	15 psig	Victor	VTS 450B	-----	3000 psig
PCV	292	Air	D2	Materials basket catch/release mechanism line pressure regulation	40 psig	Humphrey	062-4E1-36	-----	125 psig
PCV	297	Ar	G1	Oxygen monitor inlet pressure regulation	5 psig	Matheson	9463-4-V4FM	-----	3000 psig
PCV	330	CO2	D3	Vapor pump transport CO2 bottle regulator	30 psig	IMI Cornelius Inc	857-A Style PL-160	-----	2400 psig
PCV	339	He	D4	Vapor pump cold valve He supply bottle regulator	30 psig	Victor	VTS 450B	-----	3000 psig
PCV	388	N2	E2	Luke condenser back pressure regulator	30 psig	Cash Acme	123-5 1 in. x 1 in.	-----	????
PCV	396	HAr	E8	O2 filter regeneration gas bottle regulator (located outside PAB)	20 psig	Airco	400 Series	-----	4000 psig
PCV	402	Ar	D7	Line pressure regulation	Not in use	Concoa	400 Series	-----	4000 psig

**Vacuum pressure elements**

PE	91	V	F7	LN2 dewar insulating vacuum	10 <sup>-4</sup> . 1000 Torr	Hastings	gauge tube	-----	~ atm
PE	225	V	B8	Liquid argon source manifold insulating vacuum	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	226	V	A5	Insulating vacuum pump cart inter stage pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	230	V	A5	Insulating vacuum pump cart pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	231	V	A5	Insulating vacuum pump cart pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	234	V	C5	Transfer line insulating vacuum pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	235	V	C4	Oxygen filter insulating vacuum	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	239	V	A2	Seal monitor pump cart pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	288	V	A4	Cryostat pump cart vacuum pressure	10 <sup>-4</sup> . 1000 Torr	Hastings	gauge tube	-----	~ atm
PE	312	V	G1	Oxygen monitor manifold vacuum pump inlet pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	348	V	D2	LN2 transfer insulating vacuum near Luke	10 <sup>-4</sup> . 1000 Torr	Hastings	gauge tube	-----	~ atm
PE	371	V	A7	Bo insulating vacuum gauge tube	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	408	V	E6	LN2 transfer insulating vacuum dewar side	10 <sup>-4</sup> . 1000 Torr	Hastings	gauge tube	-----	~ atm
PE	409	V	E6	LN2 transfer insulating vacuum highbay side	10 <sup>-4</sup> . 1000 Torr	Hastings	gauge tube	-----	~ atm
PE	416	HAr	E7	Regeneration gas vent line pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm
PE	417	HAr	E7	Regeneration gas vacuum pump inlet pressure	10 <sup>-4</sup> . 1000 Torr	Granville-Phillips	275 series gauge tube	-----	~ atm

**Pressure indicating gauges**

PI	12	Ar	C1	Luke cryostat Ar pressure	30-0-60 psig	AMETEK	1535-V-0-60-PSI/KPA-CBM-FVCR-FR	-----	60 psig
PI	44	N2	D5	LN2 transfer line pressure	0 - 150 psig	US Gauge	Unknown model	-----	150 psig
PI	100	N	G6	LN2 dewar pressure	0 - 100 psig	US Gauge	150025X	-----	100 psig
PI	122	Ar	F3	Ar with O2 contamination source bottle pressure	0 - 3000 psig	Scientific Gas Products	Unknown model	-----	3000 psig
PI	123	Ar	F3	Ar with O2 contamination source regulated bottle pressure	30 - 0 - 30 psig	US Gauge	Unknown model	-----	30 psig
PI	126	Ar	F3	Ar with O2 contamination source regulated line pressure	30 - 0 - 30 psig	Unknown brand	Unknown model	-----	30 psig
PI	130	N2	G3	N2 contamination source bottle pressure	0 - 3000 psig	Wika	Unknown model	-----	3000 psig
PI	133	N2	D1	LN2 vent back pressure	30 - 0 - 150 psig	US gauge	Unknown model	-----	30 psig
PI	134	N2	G3	N2 contamination regulated pressure	0 - 60 psig	Wika	Unknown model	-----	60 psig
PI	243	Ar	C3	Gas contamination sample bottle isolation	30-0-150 psig	AMETEK	160552	-----	150 psig
PI	263	N2	B5	Bleed up cylinder bottle pressure	0 - 4000 psig	US Gauge	BU-2581-AQ	-----	4000 psig
PI	264	N2	B5	Bleed up cylinder regulated pressure	0 - 60 psig	US Gauge	CU-2581-HY	-----	60 psig
PI	272	Air	E1	Shop air regulated pressure	0 - 160 psig	Unknown brand	Unknown model	-----	160 psig
PI	274	Ar	F2	Argon purge cylinder pressure	0 - 4000 psig	US Gauge	BU-2581-AQ	-----	4000 psig
PI	275	Ar	F2	Argon purge cylinder regulated pressure	0 - 60 psig	US Gauge	CU-2581-HY	-----	60 psig
PI	293	Air	D2	Materials basket catch/release mechanism line pressure regulator outlet	0 - 200 psig	???	???	-----	200 psig
PI	298	Ar	G1	Oxygen monitor line pressure regulator inlet pressure	0 - 3000 psig	Matheson	63 - 2233V	-----	3000 psig
PI	299	Ar	G1	Oxygen monitor line pressure regulator outlet pressure	30 - 0 - 60 psig	Matheson	63 - 2206V	-----	60 psig
PI	326	Ar	C1	Material lock pressure	30 - 0 - 60 psig	US Gauge	Unknown model	-----	60 psig
PI	331	CO2	D3	Vapor pump transport CO2 bottle regulator inlet pressure	0 - 2000 psig	Unknown brand	Unknown model	-----	2000 psig
PI	332	CO2	D3	Vapor pump transport CO2 bottle regulator outlet pressure	0 - 200 psig	US Gauge	Unknown model	-----	200 psig
PI	334	CO2	D3	Vapor pump cold valve pressure	30 - 0 - 30 psig	US Gauge	Unknown model	-----	30 psig
PI	340	He	D4	He bottle regulator inlet	0 - 4000 psig	US Gauge	Unknown model	-----	4000 psig
PI	341	He	D4	He bottle regulator outlet	0 - 60 psig	US Gauge	Unknown model	-----	60 psig
PI	345	Ar	B7	LA supply manifold line pressure	30 - 0 - 400 psig	Ashcroft	25-1009SWXVKLL	-----	400 psig
PI	363	Ar	B7	Bo cryostat Ar pressure	30-0-60 psig	Ashcroft	25-1009SWXVKLL	-----	60 psig
PI	397	HAr	E8	5% H2 95% Ar O2 filter regeneration gas bottle regulator inlet pressure	0 - 3000 psig	Marsh	Unknown model	-----	3000 psig
PI	398	HAr	E8	5% H2 95% Ar O2 filter regeneration gas bottle regulator outlet pressure	0 - 30 psig	Marsh	Unknown model	-----	30 psig
PI	403	Ar	D7	Line pressure	0 - 2000 psig	Wika	Unknown model	-----	2000 psig
PI	404	Ar	D7	Line pressure regulator inlet pressure	0 - 4000 psig	Concoa	0550-0208	-----	4000 psig
PI	405	Ar	D7	Line pressure regulator outlet pressure	30 - 0 - 100 psig	Concoa	0550-0202	-----	100 psig

**Pressure relief valves**

PSV	101	N2	D5	LN2 transfer line trapped volume relief	100 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	117	N2	F6	LN2 transfer line trapped volume relief	100 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	118	N2	E6	LN2 transfer line trapped volume relief	100 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	136	Ar	F3	Contamination gas supply line relief	100 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	137	N2	B5	Bleed up gas supply line relief	100 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	156	Ar	C2	Luke vapor pump trapped volume relief	45 psig	Circle Seal	5100-4MP	----	2400 psig
PSV	203	Ar	G8	Liquid argon source manifold trapped volume relief	400	Circle Seal	5100-4MP	----	2400 psig
PSV	210	Ar	C1	Luke LAr volume pressure relief (ASME coded)	35 psig	Anderson Greenwood	83SF1216F	----	2000 psig
PSV	211	Ar	C7	Pbar molecular sieve filter dewar inner vessel relief	35 psig	Circle Seal	5100-8MP	----	2400 psig
PSV	219	Ar	C7	Molecular sieve trapped volume relief	400	Circle Seal	5100-2MP	----	2400 psig
PSV	249	Ar	C4	LAr transfer line trapped volume relief	400 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	250	Ar	C4	LAr transfer line trapped volume relief	400 psig	Circle Seal	5100-2MP	----	2400 psig
PSV	276	Ar	F2	Argon purge pressure relief	30 psig	Circle Seal	5200-2MP	----	2400 psig
PSV	313	Ar	C2	Materials lock pressure relief for bellows protection	~10 psig	Circle Seal	500-8MP	----	2400 psig
PSV	335	CO2	D3	Vapor pump transport CO2 supply relief (also relieves He when in Luke)	30 psig	Circle Seal	500-2MP	----	200 psig
PSV	343	He	D4	He bottle supply relief valve	42 psig	Circle Seal	5120B-2MP	----	2400 psig
PSV	344	V	D4	LAr transfer line vacuum relief	~3 psig	Fermlab	4 inch parallel plate relief	----	~ atm
PSV	377	Ar	B6	Bo LAr volume pressure relief (ASME coded)	35 psig	Anderson Greenwood	83SF1216F	----	2000 psig
PSV	378	Ar	B6	Bo LAr volume operational relief	10 psig	Circle Seal	5200-10MP	----	2400 psig
PSV	389	N2	E2	Luke condenser trapped volume relief	61 psig	Circle Seal	5120T-2MP	----	2400 psig
PSV	399	HAr	E8	5% H2 95% Ar O2 filter regeneration gas supply relief	350 psig	Nupro	B-4CP2	----	3000 psig
PSV	400	HAr	E8	5% H2 95% Ar O2 filter regeneration gas supply relief	27 psig	Circle Seal	5159B-4MP	----	2400 psig
PSV	407	Ar	D7	Gas supply relief valve	1500 psig	Anderson Greenwood	83MC68-4	----	2000 psig

**Pressure transmitters**

PT	1	N2	D1	Luke condenser LN2 back pressure	0-50 psig	Setra	C206	4-20 mA	150 psig
PT	11	Ar	C1	Luke Ar vapor pressure	0-50 psia	Setra	GCT-225 (2251-050P-A-D4-11-B1)	4-20 mA	75 psig
PT	15	V	C5	LAr transfer line insulating vacuum	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	17	V	A7	Bo cryostat insulating vacuum	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	19	V	C1	Luke Argon volume rough vacuum	10 <sup>-4</sup> -760 Torr	Varian (Controller Part# L8350301)	ConvecTorr gauge board (Part# L9887301)	0 - 7 VDC, 1 V per decade log-linear	~ atm
PT	27	N2	D5	Nitrogen transfer line pressure	0-100 psig	Setra	205-2	0-5 DC	100 psig
PT	33	V	C1	Luke Argon volume high vacuum	10 <sup>-11</sup> Torr to 10 <sup>-3</sup> Torr	Varian (Controller Part# L8350301)	UHV Bayard-Alpert gauge board (Part# L8321301)	0-10 VDC, 1 V per decade log-linear	~ atm
PT	51	N	G5	LN2 dewar pressure transmitter	0-100 psig	Setra	205-2	0-5 DC	~ atm
PT	68	V	B1	Luke dewar insulating vacuum	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	69	V	A3	Luke seal monitoring at vacuum pump	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	180	V	C7	P-bar mole sieve filter dewar - filter insulating vacuum	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	181	V	C7	P-bar mole sieve filter dewar - dewar insulating vacuum	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	185	V	C2	Materials lock rough vacuum	10 <sup>-4</sup> -760 Torr	Varian (Controller Part# L8350301)	ConvecTorr gauge board (Part# L9887301)	0 - 7 VDC, 1 V per decade log-linear	~ atm
PT	186	V	C2	Materials lock high vacuum	10 <sup>-11</sup> Torr to 10 <sup>-3</sup> Torr	Varian (Controller Part# L8350301)	UHV Bayard-Alpert gauge board (Part# L8321301)	0-10 VDC, 1 V per decade log-linear	~ atm
PT	154	V	B4	Pbar oxygen filtering dewar filter insulating vacuum	10 <sup>-4</sup> -1 Torr linear & 10 <sup>-4</sup> -1000 Torr non-linear	Granville-Phillips	275857-EU	0-10 VDC	~ atm
PT	320	Air	D1	Shop Air Pressure Transmitter	0-500 psig	Setra	C206	4-20 mA	500 psig
PT	323	Ar	F2	Argon purge pressure transmitter	0-50 psig	Setra	C206	4-20 mA	100 psig
PT	373	Ar	B7	Bo Ar vapor pressure	0-50 psia	Setra	GCT-225 (2251-050P-A-D4-11-B1)	4-20 mA	75 psig
PT	374	V	B7	Bo Argon volume rough vacuum	10 <sup>-4</sup> -760 Torr	Varian (Controller Part# L8350301)	ConvecTorr gauge board (Part# L9887301)	0 - 7 VDC, 1 V per decade log-linear	~ atm
PT	382	V	B5	Bo vacuum pump cart inlet full range pressure transmitter	5 x 10 <sup>-10</sup> to 1000 mbar	Leybold	ITR-90	0 - 10 VDC	~ atm
PT	385	V	A5	Bo vacuum pump cart rough pump inlet pressure transmitter	5 x 10 <sup>-4</sup> to 1000 mbar	Leybold	TTR-91 S	2 - 10 VDC	~ atm

**Rupture disks**

RD	99	N	H6	LN2 dewar rupture disk	105 psig	Fike	CPU BT	----	> 105 psig
RD	100	N	H7	LN2 dewar rupture disk	105 psig	Fike	CPU BT	----	> 105 psig
RD	209	Ar	C7	Pbar molecular sieve filter dewar inner vessel relief	40 psig	Fike	CPV BT (1 inch)	----	275 psig
RD	301	V	B4	Pbar oxygen filtering dewar filter insulating volume pressure relief	40 psig	Fike	CPV BT (1 inch)	----	275 psig
RD	302	Ar	B1	Luke cryostat LAr volume pressure relief	55 psig	BS&B	JRS	----	> 55 psig
RD	376	Ar	B6	Luke cryostat LAr volume pressure relief	55 psig	BS&B	JRS	----	> 55 psig

**Pressure regulators**

RV	36	N	G6	LN2 dewar pressure building regulator	30 psig	Cash Acme	B	----	400 psig
RV	90	N	H6	LN2 dewar pressure relieving regulator	35 psig	Cash Acme	FR	----	400 psig

**Strainers**

S	91	N	E7	LN2 dewar fill line strainer	-----	Mueller	1715 Class 300	----	500 psig @ 150 °F
---	----	---	----	------------------------------	-------	---------	----------------	------	-------------------

**Relief valves**

SV	90	N	F7	LN2 dewar fill line trapped volume relief	200 psig	Circle Seal	5120B-4MP-200	-----	2400 psig
SV	90	V	G8	LN2 dewar vacuum jacket relief	~ 0 psig, no spring	Circle Seal	Parallel Plate - 3.5"	-----	~ atm
SV	96	N	F6	LN2 dewar pressure building loop trapped volume relief	80 psig	Circle Seal	5159B-4MP-80	-----	2400 psig
SV	97	N	G6	LN2 dewar pressure building loop trapped volume relief	80 psig	Circle Seal	5159B-4MP-80	-----	2400 psig
SV	98	N	G6	LN2 dewar pressure building loop trapped volume relief	80 psig	Circle Seal	5159B-4MP-80	-----	2400 psig
SV	99	N	H6	LN2 dewar relief valve	75 psig	Anderson Greenwood	81S12166	-----	> 75 psig
SV	100	N	H7	LN2 dewar relief valve	75 psig	Anderson Greenwood	81S12166	-----	> 75 psig

**Temperature elements**

TE	6	N2	E5	LN2 transfer line cool down temperature (control)	70-400K	Omega	Platinum RTD (PR-19-2-100-1/8-6-E)	-----	-----
TE	7	Ar	B4	O2 filter internal temperature (hard wired interlock)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	23	Ar	B1	HTR-21-Ar internal temperature (read out)	-200 to 1300 C	Watlow	Type K thermocouple	-----	-----
TE	24	Ar	B1	HTR-21-Ar internal temperature (hard wired interlock)	-200 to 1300 C	Watlow	Type K thermocouple	-----	-----
TE	25	Ar	A6	HTR-22-Ar internal temperature (read out)	-200 to 1300 C	Watlow	Type K thermocouple	-----	-----
TE	26	Ar	A6	HTR-22-Ar internal temperature (hard wired interlock)	-200 to 1300 C	Watlow	Type K thermocouple	-----	-----
TE	54	Ar	B4	O2 filter internal temperature (read out)	70-400K	Minco	100 ohm platinum RTD (Part # S201PD)	-----	-----
TE	56	Ar	B4	O2 filter regeneration gas pre-heater temperature (control)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	57	Ar	B4	O2 filter regeneration gas pre-heater temperature (hard wired interlock)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	73	HAr	C1	Luke Vapor pump filter regeneration heater (control)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	74	HAr	C1	Luke Vapor pump filter regeneration heater (hard wired interlock)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	76	Ar	C1	Luke Vapor pump "cup" heater (control)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	77	Ar	C1	Luke Vapor pump "cup" heater (hard wired interlock)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	81	HAr	B3	Luke Vapor pump filter bed (ID)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	82	HAr	B3	Luke Vapor pump filter bed (OD)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	83	HAr	B2	Luke Vapor pump filter bed (middle)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	214	Ar	C7	Molecular sieve regeneration temperature (hard wired interlock)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	216	Ar	C7	Molecular sieve regeneration temperature (controls)	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	324	Ar	B1	Material lock elevator temperature probe	70-400K	Minco - cryogenic	100 ohm platinum RTD (Part # S270PD12(E))	-----	-----
TE	410	Air	E1	PAB high bay ambient air temperature	70-400K	Minco	100 ohm platinum RTD (Part # S201PD)	-----	-----
TE	411	CS	C3	Luke top flange temperature	-200 to 1300 C	Omega	Type K thermocouple	-----	-----
TE	412	CS	***	Luke top flange temperature	-200 to 1300 C	Omega	Type K thermocouple	-----	-----

\* Found on EE-435364

\*\*\* Currently not in use






## **1.4 - System Control Loops and Interlocks**

The safety of the cryogenic system does NOT depend upon the proper execution of any control loop or interlock. The system does include a Beckhoff programmable logic controller (PLC) and an iFix computer terminal. The controller has a loop that controls the flow of liquid nitrogen into Luke's condenser based upon the desired pressure in the cryostat. The PLC also contains a control loop for each of the 6 heaters in the system including the vapor pump. The relief valves are sized to handle the maximum output of each heater. Each heater installation includes two temperature sensors. One sensor is read out by the PLC and the other is hardwired to an interlock that drops the AC power if the sensor temperature is too high. All heaters are contained within stainless steel vessels making it extremely unlikely a malfunction can start a fire.

The only active element associated with Bo is the pressure building heater HTR-22-Ar.

Drawing 3942.520-EE-435364 contains the control system electrical schematics.





29	COM'L	POTTER AND BRUMFIELD PRO-740-120	2
28	COM'L	RFI FILTER NEWARK 52K4261	1
27	COM'L	ALOMEGA MALE THERMOCOUPLE PINS OMEGA P/N SMC-AL-5 (-)	6
26	COM'L	ALOMEGA FEMALE THERMOCOUPLE PINS OMEGA P/N SMC-CH-5 (+)	6
25	COM'L	CHROMEGA MALE THERMOCOUPLE PINS OMEGA P/N SMC-CH-5 (+)	6
24	COM'L	CHROMEGA FEMALE THERMOCOUPLE PINS OMEGA P/N SMC-CH-5 (-)	6
23	COM'L	OMEGA LIMIT CONTROLLER P/N CN3261-KF	1
22	COM'L	MALE THERMOCOUPLE CONNECTOR OMEGA P/N SMC-15M	2
21	COM'L	THERMOCOUPLE SNAP IN PANEL JACK OMEGA P/N SMC-15M	2
20	COM'L	15 PIN D CONNECTOR (MALE) OMEGA P/N SMC-15M	1
19	COM'L	15 PIN D CONNECTOR (FEMALE) OMEGA P/N SMC-15M	1
18	COM'L	MALE THERMOCOUPLE CONNECTOR OMEGA P/N SMC-15M	4
17	COM'L	THERMOCOUPLE SNAP IN PANEL JACK OMEGA P/N SMC-15M	4
16	COM'L	TWIST-LOCK VALISE CONNECTOR BODY (FEMALE) P/N HBL 7593V	2
15	COM'L	TWIST-LOCK VALISE CONNECTOR (MALE) P/N HBL 7594V	1
14	COM'L	19 PIN CONNECTOR (FEMALE) AMPHENOL P/N DTZH-14-19S	1
13	COM'L	19 PIN CONNECTOR (MALE) DETRONICS P/N MS120F16-80	1
12	COM'L	8 PIN CONNECTOR (FEMALE) AMPHENOL P/N SMC-15M	3
11	COM'L	8 PIN CONNECTOR (MALE) SEALTRON P/N SMC-15M	3
10	COM'L	MAGNETIC CONTACTOR OMEGA #MC1-2-30-120	1
9	COM'L	SOLID STATE RELAY OMEGA #SSR330C10	1
8	COM'L	MAGNETIC CONTACTOR OMEGA #MC1-2-30-240	3
7	COM'L	OMEGA RTD ALARM LIMIT MODULE PART #BSC-AR-RTD	0
6	COM'L	HAMMOND ENCLOSURE 16"x16"x7" STOCK # 91F2192	4
5	COM'L	OMEGA PDI MODULE	8
4	COM'L	RATLOW HEATER	8
3	COM'L	RFI FILTER-C11 TECHNOLOGY NEWARK #81F4557	7
2	COM'L	OMEGA LIMIT CONTROLLER #CN3261-KF	7
1	COM'L	SOLID STATE RELAY DC INPUT 16 AC OMEGA #SSR330C10	7

UNLESS OTHERWISE SPECIFIED	ORIGINATOR	D. MARKLEY	15-MAY-2006
±	DRAWN	N. CADENA	15-MAY-2006
±	CHECKED	T. TOPE	16-MAY-2008
±	APPROVED	T. TOPE	16-MAY-2008

1. BREAK ALL SHARP EDGES  
 2. DO NOT SCALE DRAWING.  
 3. DIMENSIONS BASED UPON USED ON MATERIAL  
 4. MAX. ALL MACH. SURFACES  
 5. DRAWING UNITS:

**FERMI NATIONAL ACCELERATOR LABORATORY**  
 UNITED STATES DEPARTMENT OF ENERGY

**FLARE-P942**  
 ELECTRICAL SYSTEMS-DIAGRAMS  
 LAR PURIFICATION SLOW CONTROL

SCALE	DRAWING NUMBER	SHEET	REV
	3942.520-EE-435364	2 OF 2	

CREATED WITH: Ideas12NXSeries GROUP: PPD/MECHANICAL DEPARTMENT  
 Page 26 of 300

## **2.1a – Procedure for Filling “Luke”**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be performed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. Start the argon purges. MV-316-Ar, MV-277-Ar, and the argon bottle isolation valve should be open. PCV-273-Ar outlet should be adjusted to 10 psig as indicated by PI-275-Ar. FI-278-Ar, FI-279-Ar, FI-280-Ar, FI-281-Ar, FI-282-Ar, FI-283-Ar, FI-390-Ar, and FI-284-Ar should be set to 20 sccm. FI-315-Ar should be closed unless the material lock is being purged. All Flowmeters except for FI-315-Ar should flow continuously to prevent oxygen from migrating into the bulk of the o-rings.
2. The cryostat must be evacuated. MV-345-Ar, MV-244-Ar, MV-370-Ar, MV-241-Ar, MV-247-Ar, MV-248-Ar, MV-253-Ar, MV-254-V, MV-255-Ar, MV-360-V, MV-329-Ar, MV-327-Ar, and EP-205-Ar must all be closed. EP-78-Ar and EP-308-Ar should be open.
3. Although the cryostat is rated for 15 psi external pressure, the insulating vacuum pressure should be checked on PT-68-V. The insulating vacuum should be less than 100 microns. If the insulating vacuum has spoiled, a vacuum pump should be connected to MV-261-V or CVI-138-V and improved before pumping out the cryostat. CVI-138-V does not have a spring, so it must be closed carefully when done pumping.
4. The rough pump on the cryostat pump cart should be started. A gauge read out should be connected to PE-288-V. When the vacuum is less than 100 microns, MV-360-V can be slowly opened to begin pumping out the cryostat. When PT-19-V indicates the cryostat pressure is below 1 Torr, the turbo pump may be started. The cryostat should be pumped on until the pressure reported by PT-33-V is less than  $10^{-5}$  Torr. Typically the cryostat reaches a pressure in the  $5 \times 10^{-6}$  Torr range after several days of vacuum pumping prior to the fill.
5. The oxygen filter cryostat insulating vacuum should be checked on PT-154-V. If the vacuum is worse than 100 microns, a vacuum pump should be connected to CVI-289-V and the vacuum improved until it is less than 100 microns. The purpose of this is to ensure the inner vessel is not evacuated with pressure in the insulating vacuum space.
6. The transfer line insulating vacuum should be checked on PT-15-V. If it is not less than 100 microns, then it should be pumped down. To do this, MV-224-V, MV-227-V, MV-228-V, EP-222-V, EP-155-V, MV-267-V, and EP-362-V should all be closed. The rough pump on the insulating vacuum pump cart should be started. When a readout connected to gauge tube PE-226-V indicates a vacuum less than 100 microns, EP-362-V should be opened. When the pressure reported by PE-226-V is less than 1 Torr, the turbo pump should be started. When the pressure reported by PT-15-V (or PE-234-V) is less than 10 microns, EP-362-V may be closed and the turbo pump turned off.
7. The molecular sieve insulating vacuum should be checked on PT-181-V. If the vacuum is worse than 100 microns, a vacuum pump should be connected to CVI-187-V and the vacuum improved until its less than 100 microns. The purpose of this is to ensure the inner vessel is not evacuated with pressure in the insulating vacuum space.
8. The inner vessel vacuum surrounding the molecular sieve should be checked on PT-180-V. If it is not less than 100 microns, the space should be pumped out. To do this, MV-224-V, MV-227-V, MV-228-V, EP-222-V, EP-362-V, and EP-155-V should all be closed. The rough pump on the insulating vacuum pump cart should be started. When the

- pressure reported by PE-226-V is less than 100 microns, EP-222-V should be opened. Once the pressure reported by PE-226-V is less than 1 Torr, the turbo pump should be started. The inner vessel should be pumped on until PT-180-V reads 10 microns or less. Then EP-222-V should be closed. The turbo pump should then be turned off and allowed to spin down.
9. The piping between MV-213-Ar and MV-244-Ar must be pumped out before introducing argon. MV-213-Ar, MV-218-Ar, EP-222-V, MV-228-V, MV-227-V, MV-224-V, EP-362-V, MV-480-HAr, MV-461-HAr, MV-239-Ar, MV-244-Ar, MV-365-V, MV-267-V, MV-379-Ar, and MV-366-V should all be closed. EP-155-V, MV-202-Ar (must be left open during assembly), MV-208-Ar, and MV-217-Ar should be open.
  10. The rough pump on the insulating vacuum pump cart should be started. When a gauge readout connected to PE-226-V indicates a vacuum less than 100 microns, the LN2 cold trap should be filled.
  11. MV-365-V and MV-366-V should be slowly opened. When PE-226-V indicates a vacuum of less than 1 Torr, the turbo pump should be turned on. The piping should be pumped on for at least 4 hours.
  12. Close MV-365-V and MV-366-V. Turn off the turbo pump. Allow rough pump to run until LN2 trap is warm.
  13. The argon filling manifold insulating vacuum should be checked using PE-225-V. If the vacuum is not less than 100 microns, a vacuum pump should be connected to CVI-207-V and the insulating space pumped until the vacuum is less than 100 microns. CVI-207-V should then be closed and the vacuum pump disconnected.
  14. Empty liquid dewars should be removed using 2.1h – Procedure for Removing Stockroom Liquid Argon Dewars from the System.
  15. MV-213-Ar and MV-204-Ar should be verified as closed. Follow procedure 2.1g - Procedure for Connecting Stockroom Liquid Argon Dewars to the System to connect four high pressure liquid argon dewars from the Fermilab stockroom to the manifold.
  16. MV-360-V should be closed and the turbo pump on the cryostat pump cart turned off and allowed to spin down.
  17. MV-204-Ar, MV-218-Ar, MV-480-HAr, MV-461-HAr, MV-365-V, MV-366-V, MV-239-Ar, MV-370-Ar, MV-241-Ar, MV-247-Ar, MV-248-Ar, MV-254-V, MV-255-Ar, EP-205-Ar, MV-253-Ar, MV-379-Ar, MV-380-Ar, MV-327-Ar, and MV-244-Ar should be verified as closed.
  18. MV-213-Ar, MV-217-Ar, and MV-208-Ar should be open.
  19. Slowly open the liquid withdrawal isolation valve on one of the stock room dewars and charge the system with argon. Open the liquid withdrawal valve on the rest of the connected dewars.
  20. Slowly open MV-239-Ar to allow argon to flow out the vent and cool down the transfer line. This should be done at least until TE-56-Ar reaches a stable minimum temperature and it appears that liquid is flowing out the vent piping.
  21. Close MV-239-Ar.
  22. Very slowly open MV-244-Ar and bring the cryostat to positive pressure as indicated by PI-12-Ar.

23. Once the cryostat is at positive pressure and the pressure is slowly rising, fully open MV-255-Ar. EP-205-Ar may also be opened to increase vent flow.
24. Adjust MV-244-Ar to balance the flow such that the cryostat remains below 20 psig during the fill.
25. Liquid level will be indicated by LT-13-Ar. Fill the cryostat to the desired level, but not beyond 32 inches. About 12 inches of liquid depth is required to submerge the purity monitor.
26. Close MV-244-Ar.
27. Turn on automatic pressure control at computer. Close MV-255-Ar. Computer will use HTR-21-Ar to build pressure, the LN2 condenser to reduce pressure, and if needed EP-205-Ar to vent excess pressure. If there is a problem with the computer terminal or PLC, leave MV-255-Ar open. The boil off vapor will vent thru the vaporizer and the liquid purity will be maintained.
28. The high pressure stockroom dewars may remain open and connected to the system for future charging if desired.

### **2.1b – Procedure for Emptying “Luke”**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be preformed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. MV-360-V, MV-244-Ar, MV-370-Ar, MV-241-Ar, MV-247-Ar, MV-248-Ar, MV-254-V, MV-255-Ar, MV-253-Ar, and EP-205-Ar should be closed. EP-308-Ar and EP-78-Ar should be open.
2. Turn off the nitrogen control loop at the computer. Leave the pressure venting control loop on. Open MV-370-Ar. Cryostat vapor pressure will push the liquid out of the cryostat.
3. Last bit of liquid at cryostat bottom will slowly evaporate. EP-205-Ar will automatically vent remaining liquid as vapor.

### **2.1c – Procedure for Operating “Air Lock” during Material Insertion**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be preformed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. Cryostat should be in a stable operating condition with the appropriate liquid argon level for the material test. The nitrogen pressure control loop set point should be 5 psig. MV-360-V, MV-244-Ar, MV-370-Ar, MV-241-Ar, MV-247-Ar, MV-248-Ar, MV-253-Ar, MV-254-V, MV-345-Ar, MV-329-Ar, MV-327-Ar, and MV-255-Ar should all be closed under normal operating conditions. Automatic vent control of EP-205-Ar should be enabled at a set point of 10 psig or greater.

2. The surface area of the material test sample must be measured. ***The surface area must be less than 162.5 square inches.*** Two people must measure the surface area independently. Their calculations and signatures must be entered into the material lock log book. Their signature indicates that they understand how to measure surface area and that they are responsible for the safety of the system during the insertion of the test sample. ***The sample also must not be in a shape that will retain liquid argon when the sample is withdrawn from the system.***
3. Place sample into air lock basket and install 8 inch conflat flange to close the air lock.
4. The air lock must be purged with argon gas to remove the oxygen and water contamination. MV-253-Ar, MV-296-Ar, MV-295-V, MV-300-Ar, and MV-310-Ar should be closed. MV-316-Ar, MV-277-Ar, MV-252-Ar, MV-290-Ar, MV-256-AR, MV-291-Ar, MV-294-Ar should be open.
5. FI-315-Ar should be adjusted to 8 SCFH.
6. MV-310-Ar should be opened and MV-300-Ar adjusted until FI-312-Ar indicates 2 SCFH.
7. Purge should continue until AE-311-Ar indicates an oxygen concentration below 10 ppm.
8. When purge has achieved desired oxygen level, close MV-252-Ar.
9. Open MV-253-Ar. Allow the cryostat boil off to purge the airlock until AE-311-Ar indicates an oxygen level below 1 ppm. Because of the change of the purge gas source, MV-300-Ar may have to be re-adjusted for FI-312-Ar to again indicate 2 SCFH.
10. Close MV-253-Ar, MV-290-Ar, and MV-310-Ar.
11. Open the large vacuum gate valve MV-245-V.
12. Using the rack mounted stepper motor controller, lower the basket onto the elevator below the gate valve.
13. Release the material test basket from its catch mechanism by cycling EV-258-Air.
14. Entered desired material depth for cryostat insertion into the stepper motor rack mounted controller. The controller will then slowly lower the elevator and material into cryostat. Excess vapor generated by the warm material reaching liquid will continuously vent thru MV-256-AR or PSV-313-Ar.
15. Once desired depth is reached, the controller will stop.
16. Use the rack mounted stepper motor controller to raise the basket catch/release mechanism above the gate valve.
17. Once the material basket catch/release mechanism has retreated above the vacuum gate valve as indicated by the controller and verified visually thru the window, close MV-254-V.

#### **2.1d – Procedure for Operating “Air Lock” during material removal**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be preformed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. Cryostat should be in a stable operating condition with the appropriate liquid argon level for the material test. The nitrogen pressure control loop set point should be 5 psig. MV-360-V, MV-244-Ar, MV-370-Ar, MV-241-Ar, MV-247-Ar, MV-248-Ar, MV-253-Ar, MV-254-V, MV-345-Ar, MV-329-Ar, MV-327-Ar, and MV-255-Ar should all be closed under normal operating conditions. Automatic vent control of EP-205-Ar should be enabled at a set point of 10 psig or greater.
2. The air lock must be purged with argon gas to remove the oxygen and water contamination. MV-253-Ar, MV-296-Ar, MV-295-V, MV-300-Ar, and MV-310-Ar should be closed. MV-316-Ar, MV-277-Ar, MV-252-Ar, MV-290-Ar, MV-256-Ar, MV-291-Ar, MV-294-Ar should be open.
3. FI-315-Ar should be adjusted to 8 SCFH.
4. MV-310-Ar should be opened and MV-300-Ar adjusted until FI-312-Ar indicates 2 SCFH.
5. Purge should continue until AE-311-Ar indicates an oxygen concentration below 10 ppm.
6. When purge has achieved desired oxygen level, close MV-252-Ar.
7. Open MV-253-Ar. Allow the cryostat boil off to purge the airlock until AE-311-Ar indicates an oxygen level below 1 ppm. Because of the change of the purge gas source, MV-300-Ar may have to be re-adjusted for FI-312-Ar to again indicate 2 SCFH.
8. Close MV-253-Ar, MV-290-Ar, and MV-310-Ar.
9. Open MV-254-V.
10. Using the rack mounted stepper motor controller raise the elevator to its highest position.
11. Lower the basket catch/release mechanism until it reaches the top of the basket.
12. By cycling EV-258-Air, attach the catch/release mechanism to the basket.
13. Using the rack mounted stepper motor controller, raise the basket into the air lock.
14. Visually verify that the basket is in the material lock and then close MV-254-V.
15. Verify that MV-290-Ar is closed. Verify that MV-256-Ar and MV-294-Ar are open. Open MV-296-Ar to vent any pressure inside the material lock. Verify that the pressure is 0 psig on PI-326-Ar. The eight inch conflat flange may now be removed to access and remove material in test basket. Use cryogenic gloves to remove material that is still cold.

### **2.1e – Procedure for filling the LN2 dewar**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be preformed while wearing a face shield and cryogenic gloves.**

1. Remove the inlet cover on the fill connection and connect the tanker transfer hose. Do not hammer the fill connection tight. Use the supplied wrench to tighten the fill connection.
2. Open the blow-down valve, MV-93-N, to maintain the dewar pressure at 30 psig.

3. Open the bottom fill valve MV-92-N.
4. Open the full trycock valve, MV-94-N.
5. Open the liquid discharge valve on the trailer to start filling the dewar.
6. Read the quantity gauge, DPI-100-N, during filling and observe the full trycock valve MV-94-N.
7. Close the liquid discharge valve on the trailer when the quantity gauge DPI-100-N reads 50 inches or when liquid discharges from the full trycock valve MV-94-N.
8. Close the bottom fill valve, MV-92-N.
9. Close the dewar blow down valve MV-93-N.
10. Vent the contents of the fill line using MV-91-N.
11. Disconnect the transfer hose.
12. Replace the inlet cover on the fill connection.

#### **2.1f – Normal Nitrogen Circuit Valve Positions During Operation**

**All operators must meet the training requirements specified in section 2.3.**

1. Valves that are closed during normal operation: MV-91-N, MV-92-N, MV-90-V, MV-94-N, MV-91-V, MV-86-N, MV-95-N, MV-107-N, MV-97-N, MV-119-N, MV-101-N, MV-99-N, and MV-93-N.
2. Valves that are open during normal operation: MV-90-N, MV-89-N, MV-88-N, MV-96-N, MV-100-N, MV-120-N, MV-87-N, MV-85-N, and MV-80-N.

#### **2.1g – Procedure for Connecting Stockroom Liquid Argon Dewars to the System**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be preformed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. Verify that the dewar label indicates the contents are liquid argon. Connecting a liquid nitrogen dewar to the system will cause a violent reaction with any liquid argon in the system as the nitrogen will freeze the argon. Also verify that the dewar contains liquid by looking at the liquid level gauge.
2. Using the metallic green and black Valley Craft brand lifting cart, move the liquid argon dewar from outside PAB into an open spot by one of the four flexible hoses that extend from the liquid argon manifold.
3. Close MV-213-Ar. The argon manifold must be isolated from the rest of the system anytime a dewar is added to the system to prevent contamination.
4. Connect the flexible stainless steel pigtail to the liquid withdrawal port on the dewar. The stainless steel pigtail has a VCR to flare adaptor to mate with the dewar liquid withdrawal

port. A new copper gasket should be used with the flare fitting each time the connection is made up.

5. Repeat steps 1-4 to connect up to four dewars to the manifold.
6. Any pigtail not in use should be plugged by removing the VCR to flare adaptor and plugging the VCR fitting.
7. Anytime a dewar is connected to the manifold, the connection must be helium leak checked. A helium leak detector should be connected to MV-204-Ar. MV-204-Ar should be opened and the flare fitting at the liquid withdrawal port and the isolation valve supplied on the dewar should be sprayed externally with helium gas. Once the system is reasonably leak tight, MV-204-Ar should be closed and the leak detector disconnected.
8. The liquid withdrawal isolation valve supplied on each dewar should be opened to pressurize the manifold.

### **2.1h – Procedure for Removing Stockroom Liquid Argon Dewars from the System**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be performed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. Close MV-213-Ar. The argon manifold must be isolated from the rest of the system anytime a dewar is removed from the system to prevent contamination of the upstream filters.
2. Close the liquid withdrawal port isolation valve on each liquid argon dewar connected to the system.
3. Slowly open MV-204-Ar to vent any pressure contained in the argon manifold.
4. When the pressure in the manifold has been vented, the flare connection at the liquid argon dewar may be disconnected. If a new dewar is not being attached, the stainless steel pigtail should be plugged by removing the VCR to flare adaptor and plugging the VCR fitting.
5. MV-204-Ar should be closed after the desired dewars are disconnected.
6. Empty dewars should be removed from the PAB highbay using the metallic green and black Valley Craft brand lifting cart and placed outside by the gas shed. The full/empty tag should be flipped so that the empty side faces upward.

### **2.1i – Procedure for Molecular Sieve Regeneration**

**All operators must meet the training requirements specified in section 2.3.**

1. MV-213-Ar, MV-218-Ar, and MV-217-Ar should be closed.
2. The molecular sieve insulating vacuum should be checked on PT-181-V. If the vacuum is worse than 100 microns, a vacuum pump should be connected to CVI-187-V and the vacuum improved until its less than 100 microns. The purpose of this is to ensure the inner vessel is not evacuated with pressure in the insulating vacuum space.

3. The inner vessel vacuum surrounding the molecular sieve should be checked on PT-180-V. If it is not less than 100 microns, the space should be pumped out. To do this, MV-224-V, MV-227-V, MV-228-V, EP-222-V, EP-362-V, and EP-155-V should all be closed. The rough pump on the insulating vacuum pump cart should be started. When the pressure reported by PE-226-V is less than 100 microns, EP-222-V should be opened. Once the pressure reported by PE-226-V is less than 1 Torr, the turbo pump should be started. The inner vessel should be pumped on until PT-180-V reads 10 microns or less. Then EP-222-V should be closed. The turbo pump should then be turned off and allowed to spin down.
4. A vacuum pump should be connected to MV-218-Ar with a cold trap between the pump and MV-218-Ar.
5. Once the vacuum is below 1 Torr as indicated by a vacuum gauge at the pump, the cold trap can be filled.
6. MV-218-Ar should be slowly opened. Avoid sending a surge of high pressure argon gas to the vacuum pump.
7. Once the gauge at the pump reads less than 10 Torr, turn on the heater in iFix. Set point should be 275 °C and duration 8 hours. Monitoring the vacuum gauge at the pump will give some idea of the regeneration progress as water is removed and the pressure drops.
8. After regeneration is complete, turn off the heater in iFix.
9. Close MV-218-Ar. Disconnect the vacuum pump.

### **2.1j – Procedure for O2 Filter Regeneration**

**All operators must meet the training requirements specified in section 2.3.**

1. MV-217-Ar, MV-239-Ar, MV-244-Ar, MV-365-V, and MV-366-V must be closed.
2. MV-208-Ar, MV-480-HAr, and MV-461-HAr must be open. MV-202-Ar must also be open, although it is inaccessible when the vacuum jacket is closed and should be in the open position.
3. The oxygen filter cryostat insulating vacuum should be checked on PT-154-V. If the vacuum is worse than 100 microns, a vacuum pump should be connected to CVI-289-V and the vacuum improved until its less than 100 microns. The purpose of this is to ensure the inner vessel is not evacuated with pressure in the insulating vacuum space.
4. The transfer line insulating vacuum should be checked on PT-15-V. If it is not less than 100 microns, then it should be pumped down. To do this, MV-224-V, MV-227-V, MV-228-V, EP-222-V, EP-155-V, MV-267-V, and EP-362-V should all be closed. The rough pump on the insulating vacuum pump cart should be started. When a readout connected to gauge tube PE-226-V indicates a vacuum less than 100 microns, EP-362-V should be opened. When the pressure reported by PE-226-V is less than 1 Torr, the turbo pump should be started. When the pressure reported by PT-15-V (or PE-234-V) is less than 10 microns, EP-362-V may be closed and the turbo pump turned off.
5. From the regeneration station, supply a 5 SCFH flow of argon gas.

6. In iFix, turn on the oxygen filter regeneration heaters HTR-8-Ar and HTR-55-Ar. Make the set point for both heaters 270 °C.
7. Once the temperatures reported by TE-56-Ar and TE-54-Ar are stable, supply the 5% H<sub>2</sub> – 95% Ar mixture from the regeneration station for 8 hours.
8. Turn off HTR-8-Ar and HTR-55-Ar in iFix.
9. Supply a flow of argon gas from the regeneration station for 15 minutes to purge the hydrogen from the system.
10. Close MV-461-HAr first and then close MV-480-HAr to isolate the filter with a positive internal pressure.

### **2.1k – Procedure for Filling “Bo”**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be performed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. Start the argon purges. MV-316-Ar, MV-277-Ar, and the argon bottle isolation valve should be open. PCV-273-Ar outlet should be adjusted to 10 psig as indicated by PI-275-Ar. FI-278-Ar, FI-279-Ar, FI-280-Ar, FI-281-Ar, FI-282-Ar, FI-283-Ar, FI-390-Ar, and FI-284-Ar should be set to 20 sccm. FI-315-Ar should be closed unless the material lock is being purged. All Flowmeters except for FI-315-Ar should flow continuously to prevent oxygen from migrating into the bulk of the o-rings.
2. The cryostat must be evacuated. MV-379-Ar, MV-380-Ar, and MV-381-V must all be closed.
3. Although the cryostat is rated for 15 psi external pressure, the insulating vacuum pressure should be checked on PT-17-V. The insulating vacuum should be less than 100 microns. If the insulating vacuum has spoiled, a vacuum pump should be connected to MV-369-V or CVI-382-V, and the vacuum improved before pumping out the cryostat. CVI-382-V does not have a spring, so it must be closed carefully when done pumping.
4. The rough pump on the cryostat pump cart should be started and MV-386-V opened. When the vacuum is less than 100 microns as indicated by the pump controller, MV-381-V can be slowly opened to begin pumping out the cryostat. When PT-374-V indicates the cryostat pressure is below 1 Torr, the turbo pump may be started. The cryostat should be pumped on until the pressure reported by PT-382-V is less than 10<sup>-5</sup> Torr. Typically the cryostat reaches a pressure in the 5 x 10<sup>-6</sup> Torr range after several days of vacuum pumping prior to the fill.
5. The oxygen filter cryostat insulating vacuum should be checked on PT-154-V. If the vacuum is worse than 100 microns, a vacuum pump should be connected to CVI-289-V and the vacuum improved until it is less than 100 microns. The purpose of this is to ensure the inner vessel is not evacuated with pressure in the insulating vacuum space.
6. The transfer line insulating vacuum should be checked on PT-15-V. If it is not less than 100 microns, then it should be pumped down. To do this, MV-224-V, MV-227-V, MV-228-V, EP-222-V, EP-155-V, MV-267-V, and EP-362-V should all be closed. The rough pump on the insulating vacuum pump cart should be started. When a readout connected

- to gauge tube PE-226-V indicates a vacuum less than 100 microns, EP-362-V should be opened. When the pressure reported by PE-226-V is less than 1 Torr, the turbo pump should be started. When the pressure reported by PT-15-V (or PE-234-V) is less than 10 microns, EP-362-V may be closed and the turbo pump turned off.
7. The molecular sieve insulating vacuum should be checked on PT-181-V. If the vacuum is worse than 100 microns, a vacuum pump should be connected to CVI-187-V and the vacuum improved until its less than 100 microns. The purpose of this is to ensure the inner vessel is not evacuated with pressure in the insulating vacuum space.
  8. The inner vessel vacuum surrounding the molecular sieve should be checked on PT-180-V. If it is not less than 100 microns, the space should be pumped out. To do this, MV-224-V, MV-227-V, MV-228-V, EP-222-V, EP-362-V, and EP-155-V should all be closed. The rough pump on the insulating vacuum pump cart should be started. When the pressure reported by PE-226-V is less than 100 microns, EP-222-V should be opened. Once the pressure reported by PE-226-V is less than 1 Torr, the turbo pump should be started. The inner vessel should be pumped on until PT-180-V reads 10 microns or less. Then EP-222-V should be closed. The turbo pump should then be turned off and allowed to spin down.
  9. The piping between MV-213-Ar and MV-379-Ar must be pumped out before introducing argon. MV-213-Ar, MV-218-Ar, EP-222-V, MV-228-V, MV-227-V, MV-224-V, EP-362-V, MV-480-HAr, MV-461-HAr, MV-239-Ar, MV-244-Ar, MV-365-V, MV-267-V, and MV-366-V should all be closed. EP-155-V, MV-202-Ar (must be left open during assembly), MV-208-Ar, and MV-217-Ar should be open.
  10. The rough pump on the insulating vacuum pump cart should be started. When a gauge readout connected to PE-226-V indicates a vacuum less than 100 microns, the LN2 cold trap should be filled.
  11. MV-365-V and MV-366-V should be slowly opened. When PE-226-V indicates a vacuum of less than 1 Torr, the turbo pump should be turned on. The piping should be pumped on for at least 4 hours.
  12. Close MV-365-V and MV-366-V. Turn off the turbo pump. Allow rough pump to run until LN2 trap is warm.
  13. The argon filling manifold insulating vacuum should be checked using PE-225-V. If the vacuum is not less than 100 microns, a vacuum pump should be connected to CVI-207-V and the insulating space pumped until the vacuum is less than 100 microns. CVI-207-V should then be closed and the vacuum pump disconnected.
  14. Empty liquid dewars should be removed using 2.1h – Procedure for Removing Stockroom Liquid Argon Dewars from the System.
  15. MV-213-Ar and MV-204-Ar should be verified as closed. Follow procedure 2.1g - Procedure for Connecting Stockroom Liquid Argon Dewars to the System to connect four high pressure liquid argon dewars from the Fermilab stockroom to the manifold.
  16. MV-381-V should be closed and the turbo pump on the cryostat pump cart turned off and allowed to spin down.
  17. MV-204-Ar, MV-218-Ar, MV-480-HAr, MV-461-HAr, MV-365-V, MV-366-V, MV-239-Ar, MV-379-Ar, MV-380-Ar, and MV-244-Ar should be verified as closed.

18. MV-213-Ar, MV-217-Ar, and MV-208-Ar should be open. (MV-202-Ar should have been left open during assembly).
19. Slowly open the liquid withdrawal isolation valve on one of the stock room dewars and charge the system with argon. Open the liquid withdrawal valve on the rest of the connected dewars.
20. Slowly open MV-239-Ar to allow argon to flow out the vent and cool down the transfer line. This should be done at least until TE-56-Ar reaches a stable minimum temperature and it appears that liquid is flowing out the vent piping.
21. Close MV-239-Ar.
22. Very slowly open MV-379-Ar and bring the cryostat to positive pressure as indicated by PI-375-Ar.
23. Once the cryostat is at positive pressure and the pressure is slowly rising, fully open MV-380-Ar.
24. Adjust MV-379-Ar to balance the flow such that the cryostat remains below 10 psig during the fill.
25. Liquid level will be indicated by LT-372-Ar. Fill the cryostat to the desired level, but not beyond 32 inches.
26. Close MV-379-Ar.
27. Leave MV-380-Ar open. This will allow the cryostat boil off to vent and the pressure to remain near atmospheric.
28. The high pressure stockroom dewars may remain open and connected to the system for future charging if desired.

### **2.11 – Procedure for Emptying “Bo”**

**All operators must meet the training requirements specified in section 2.3.**

**All steps of this procedure should be performed while wearing eye protection. Cryogenic gloves and a face shield must be available in the immediate work area in case a leak must be addressed or a cold component handled.**

1. MV-379-Ar, MV-381-V, MV-239-Ar, MV-244-Ar, MV-208-Ar, and MV-380-Ar should be closed.
2. Open MV-379-Ar and MV-239-Ar. Liquid will vent thru the vaporizer.
3. Last bit of liquid at cryostat bottom will slowly evaporate. HTR-22-Ar can be used to speed up this evaporation.

### **2.2a - Startup Check List for Filling the Material Test Station**

1. Ensure the liquid nitrogen dewar has at least 15 inches of liquid in it as indicated by DPI-100-N. If not, request a fill from Air Products by contacting Don Brown (610-481-1343 or BROWNDE@airproducts.com).
2. Check that the LN2 dewar vapor pressure is around 45 psig as indicated by PI-100-N and PT-51-N. If not, adjust RV-036-N or RV-090-N as needed.
3. Check that the Beckhoff PLC and the iFix GUI are operating properly.
4. Check that the argon purge cylinder has at least 500 psig left. If not, connect a new cylinder of argon gas.
5. Ensure that at least 3 full stockroom high pressure argon dewars are available to fill the cryostat.
6. Check the availability of shop air on PI-272-Air which should indicate at least 60 psig.
7. Check the log book (<http://www-lartpc-crl.fnal.gov/lartpc/Index.jsp>) to see if the molecular sieve and oxygen filter require regeneration. If so, regenerate per 2.1i and 2.1j.

### **2.2b - Startup Check List for Filling the TPC cryostat**

1. Check that the Beckhoff PLC and the iFix GUI are operating properly.
2. Check that the argon purge cylinder has at least 500 psig left. If not, connect a new cylinder of argon gas.
3. Ensure that at least 3 full stockroom high pressure argon dewars are available to fill the cryostat.
4. Check the availability of shop air on PI-272-Air which should indicate at least 60 psig.
5. Check the log book (<http://www-lartpc-crl.fnal.gov/lartpc/Index.jsp>) to see if the molecular sieve and oxygen filter require regeneration. If so, regenerate per 2.1i and 2.1j.

### **2.3 - Training List for Operators of the FLARE Material Test Station and the TPC Cryostat**

All operators of the FLARE material test station and TPC cryostat must meet the following training requirements.

1. Successful completion of Cryogenic Safety (General) [FN000115 / CR.](#)
2. O.D.H Training [FN000029 / CR.](#)
3. Successful completion of Pressure Safety Orientation [FN000271 / CR.](#)
4. Successful completion of Compressed Gas Cylinder Safety [FN000213 / CR.](#)
5. Must review system description, flow schematic, and operating procedures with a designated system expert.

Designated system experts: Terry Tope, Cary Kendziora.

Table 2.3.1: Date required training for FLARE material test station has been completed.

Person	ID #	Cryogenic Safety (General)	O.D.H Training Completed	O.D.H Training Due	Pressure Safety Orientation	Compressed Gas Cylinder Safety	Review System Documents
Terry Tope	13329N	12/6/2002	2/5/2008	2/28/2009	1/10/2003	1/16/2002	Expert
Cary Kendziora	4446N	1/23/1984	8/16/2007	Inactive	2/27/2003	3/13/2003	Expert
Stephen Pordes	4663N	---	3/22/2006	Inactive	---	---	---
Doug Jensen	9541N	---	10/8/2007	10/31/2008	---	4/26/2000	---
Bill Miner	13161N	3/4/2003	5/21/2007	5/31/2008	1/7/2003	1/16/2002	---
Kelly Hardin	12976N	9/5/2002	1/3/2008	1/31/2009	3/11/2003	12/13/2000	---
Hans Jostlein	3972N	1/24/2008	11/5/2007	11/30/2008	11/2/2007	---	---
Mark Ruschman	5006N	3/4/2003	5/10/2007	5/31/2008	12/2/2002	7/27/2001	---
Walter Jaskierny	676N	---	9/5/2006	9/30/2007	9/4/2007	1/16/2002	---

### 3.1 - FMEA

Type Tag Tag Service

Failure or Error Mode

Hazard or Effect

Hazard Class

Remarks

#### Analyzing elements

AE	Tag	Tag	Service	Failure or Error Mode	Hazard or Effect	Hazard Class	Remarks
AE	52	HAr	Filter regeneration moisture monitoring (close to exhaust)	Incorrect reading	O2 filter regeneration may be incomplete	Safe	Operational problem
AE	151	HAr	Filter regeneration moisture monitoring (close to filter)	Incorrect reading	O2 filter regeneration may be incomplete	Safe	Operational problem
AE	311	Ar	Oxygen Analyzer	Incorrect reading	Air lock purge may be incomplete	Safe	Operational problem
AE	312	Ar	Oxygen Analyzer	Not in service	----	----	----
AE	322	Ar	Nitrogen Arc Cell	Not in service	----	----	----

#### Check valves

CV	Tag	Tag	Service	Failure or Error Mode	Hazard or Effect	Hazard Class	Remarks
CV	90	N	LN2 dewar fill line check valve	Fails open	LN2 from dewar could spill into parking lot	Safe	Operational problem if MV-92-N is left open
CV	90	N	LN2 dewar fill line check valve	Fails closed	LN2 dewar cannot be filled	Marginal	Potential trapped volume if PCV-70-N closes. Low probability of a check valve failing shut. Pressure in a trapped volume will increase the probability that a stuck check valve would open. PCV-70-N will only close when the dewar vapor pressure reaches MAWP which also has a low probability. Thus the creation of an unrelieved trapped volume is the product of two low probability events.
CV	150	Ar	LAr vent line	Fails open	Wind effects felt on exhaust	Safe	No hazard
CV	150	Ar	LAr vent line	Fails closed	Potential trapped volume	Marginal	Low probability of a check valve failing shut. Pressure in a trapped volume would increase the probability a stuck check valve would open.
CV	100	N	LN2 dewar liquid use line	Fails open	Potential for back flow into dewar	Safe	No likely source for flowing back into dewar
CV	100	N	LN2 dewar liquid use line	Fails closed	Potential trapped volume	Marginal	Operational problem. Fermilab designed and fabricated check valve has a small diameter hole thru the center of the teflon plug that would relieve a trapped volume.
CV	257	Ar	"Air lock" vent line backflow prevention	Fails open	Potential contamination	Safe	Operational problem, under vacuum contaminants could be pulled into air lock
CV	257	Ar	"Air lock" vent line backflow prevention	Fails closed	Purging not possible	Safe	Operational problem, materials lock cannot be purged with Gar
CV	266	N2	Insulating vacuum bleed up check valve	Fails open	No hazard	Safe	----
CV	266	N2	Insulating vacuum bleed up check valve	Fails closed	GN2 source blocked	Safe	Operational problem, no GN2 to bleed up insulating vacuum with
CV	309	HAr	O2 filter regeneration check valve	Fails open	FI-406-HAr could be over pressurized	Marginal	400 psig GAR could back flow and damage the flowmeter if MV-9-HAr or either MV-10-HAr or MV-12-HAr are closed
CV	309	HAr	O2 filter regeneration check valve	Fails closed	Regeneration gas flow blocked	Safe	Operational problem, can't regenerate O2 filter
CV	415	HAr	Regeneration gas vent line back flow prevention	Fails open	Regeneration vent line can't be evacuated	Safe	Operational problem, possible contamination
CV	415	HAr	Regeneration gas vent line back flow prevention	Fails closed	Regeneration gas flow blocked, PE-416-HAr over pressurized	Marginal	Operational problem, can't regenerate O2 filter and vacuum transmitter could be damaged by several atmospheres of pressure

#### Pump out ports

CVI	Tag	Tag	Service	Failure or Error Mode	Hazard or Effect	Hazard Class	Remarks
CVI	138	V	Luke vacuum pumpout/relief	Fails open	Insulating vacuum spoiled	Safe	Operational problem, PSV-210-Ar can handle excess boil off
CVI	138	V	Luke vacuum pumpout/relief	Fails closed	No relief for insulating vacuum	Marginal	If the ASME coded inner vessel fails, vacuum space is not relieved. Relief is a CVI vacuum pump out with the spring removed. The space that holds the spring retaining clip in place has been epoxied shut so a spring cannot be put back into the pumpout. There is a very low probability of this pumpout failing shut because without the spring it works like a parallel plate relief.
CVI	187	V	Molecular sieve pbar dewar insulating vacuum pumpout/relief	Fails open	Insulating vacuum spoiled	Safe	Operational problem, poor insulation

CVI	187	V	Molecular sieve pbar dewar insulating vacuum pumpout/relief	Fails closed	Insulating vacuum isolated	Marginal	Operational problem, can't improve vacuum, no insulating vacuum relief if inner vessel fails. For liquid to reach the insulating vacuum space, both the LAr piping and the ASME inner vessel must fail which is extremely unlikely. CVI pumpout works like a relief valve in that the sealing surface is held shut by a spring. If pressure was built in the vacuum jacket, its a low probability that the CVI would stay shut.
CVI	207	V	Liquid argon source manifold insulating vacuum pumpout and relief	Fails open	Insulating vacuum spoiled	Safe	Operational problem, poor insulation, likely frost buildup
CVI	207	V	Liquid argon source manifold insulating vacuum pumpout and relief	Fails closed	Insulating vacuum isolated	Marginal	Operational problem, can't improve vacuum, no insulating vacuum relief if inner pipe fails. Low probability of CVI sticking shut as pressure builds because the pumpout works like a spring loaded relief valve. Vacuum jacket is 1.5" stainless steel tube that can withstand a substantial internal pressure.
CVI	220	V	Pbar molecular sieve dewar inner vessel pumpout/relief	Fails open	Insulating vacuum spoiled	Safe	Operational problem, poor insulation, likely frost buildup
CVI	220	V	Pbar molecular sieve dewar inner vessel pumpout/relief	Fails closed	Insulating vacuum isolated	Safe	Operational problem, can't improve vacuum, no insulating vacuum relief if inner pipe fails (PSV-211-Ar and RD-209-Ar also protect space protected by CVI-220-V)
CVI	259	V	Luke LN2-LAr condenser insulating vacuum pumpout/relief	Fails open	Insulating vacuum spoiled	Safe	Operational problem, condenser performance degrades
CVI	259	V	Luke LN2-LAr condenser insulating vacuum pumpout/relief	Fails closed	Insulating vacuum isolated	Marginal	Operational problem, can't improve insulating vacuum, no insulating vacuum relief if inner pipe fails. There is a low probability of the high quality stainless steel inner piping failing. There is also a low probability of the CVI pumpout failing shut as pressure builds because it works like a spring loaded relief valve.
CVI	260	V	LN2 transfer line vacuum pumpout/relief near Luke	Fails open	Insulating vacuum spoiled	Safe	Operational problem, poor insulation, likely frost buildup
CVI	260	V	LN2 transfer line vacuum pumpout/relief near Luke	Fails closed	Insulating vacuum isolated	Safe	Operational problem, can access same vacuum volume using CVI-286-V
CVI	285	V	LN2 transfer line vacuum pumpout/relief dewar side	Fails open	Insulating vacuum spoiled	Safe	Operational problem, poor insulation, likely frost buildup
CVI	285	V	LN2 transfer line vacuum pumpout/relief dewar side	Fails closed	Insulating vacuum isolated	Marginal	Operational problem, can't improve vacuum, no insulating vacuum relief if inner pipe fails. There is a low probability of the high quality stainless steel inner piping failing. There is also a low probability of the CVI pumpout failing shut as pressure builds because it works like a spring loaded relief valve. The vacuum jacket is 1.5" SCH 10 SS which can withstand a substantial internal pressure.
CVI	286	V	LN2 transfer line vacuum pumpout/PAB side	Fails open	Insulating vacuum spoiled	Safe	Operational problem, poor insulation, likely frost buildup
CVI	286	V	LN2 transfer line vacuum pumpout/PAB side	Fails closed	Insulating vacuum isolated	Safe	Operational problem, can access same vacuum volume using CVI-260-V
CVI	289	V	O2 filter pbar dewar insulating vacuum pumpout/relief	Fails open	Insulating vacuum spoiled	Marginal	Pressure in insulating vacuum space could crumple inner vessel
CVI	289	V	O2 filter pbar dewar insulating vacuum pumpout/relief	Fails closed	Insulating vacuum isolated	Marginal	No insulating vacuum relief. It would require a double failure to pressurize the insulating vacuum. Both the piping inside the inner vessel and the inner vessel itself would have to fail.
CVI	382	V	Bo insulating vacuum and relief	Fails open	Insulating vacuum spoiled	Safe	Operational problem, PSV-377-Ar can handle excess boil off
CVI	382	V	Bo insulating vacuum and relief	Fails closed	No relief for insulating vacuum	Marginal	If the ASME coded inner vessel fails, vacuum space is not relieved. Relief is a CVI vacuum pump out with the spring removed. The space that holds the spring retaining clip in place has been epoxied shut so a spring cannot be put back into the pumpout. There is a very low probability of this pumpout failing shut because without the spring it works like a parallel plate relief.

**Differential pressure transmitters**

DPT	67	Ar	Luke Vapor Pump filter liquid level	Incorrect reading	Possible poor pump performance	Safe	Operational problem
DPT	100	N	Liquid Nitrogen Dewar	Incorrect reading	Dewar liquid level unknown	Safe	Operational problem

**Pneumatic valves**

EP	78	Ar	Luke vapor pump equalization valve	Fails open	Liquid cannot be forced from filter	Safe	Operational problem - poor filtration
EP	78	Ar	Luke vapor pump equalization valve	Fails closed	Liquid won't flow into filter	Safe	Operational problem - poor filtration

EP	155	V	Oxygen filter vacuum isolation	Fails open	Insulating vacuum spoiled	Safe	Operational problem - high thermal load during filtration or regeneration
EP	155	V	Oxygen filter vacuum isolation	Fails closed	Insulating vacuum isolated	Safe	Operational problem - can't improve vacuum
EP	205	Ar	Luke Ar vent	Fails open	Cryostat cannot build pressure	Safe	Operational problem - Gar will be vented and system will no longer be closed
EP	205	Ar	Luke Ar vent	Fails closed	Excess pressure not vented	Safe	Operational problem - Gar will be vented thru PSV-210-Ar if needed
EP	222	V	Molecular sieve insulating vacuum isolation	Fails open	Insulating vacuum spoiled	Safe	Operational problem - high thermal load during filtration or regeneration
EP	222	V	Molecular sieve insulating vacuum isolation	Fails closed	Insulating vacuum isolated	Safe	Operational problem - can't improve vacuum
EP	236	V	Cryostat pump cart inter-stage isolation (turbo protection)	Fails open	Turbo not protected	Safe	Operational problem - turbo vacuum pump could be damaged
EP	236	V	Cryostat pump cart inter-stage isolation (turbo protection)	Fails closed	Turbo isolated from rougher	Safe	Operational problem - cryostat cannot be effectively evacuated
EP	308	Ar	Luke vapor pump liquid inlet	Fails open	Filter cannot be regenerated	Safe	Operational problem - poor filtration
EP	308	Ar	Luke vapor pump liquid inlet	Fails closed	LAr cannot enter filter	Safe	Operational problem - poor filtration
EP	362	V	LAr transfer line insulating vacuum isolation	Fails open	Insulating vacuum spoiled	Safe	Operational problem - high thermal load during LAr transfer
EP	362	V	LAr transfer line insulating vacuum isolation	Fails closed	Insulating vacuum isolated	Safe	Operational problem - can't improve vacuum
EP	383	V	Bo vacuum pump cart turbo protection valve	Fails open	Turbo not protected	Safe	Operational problem - turbo vacuum pump could be damaged
EP	383	V	Bo vacuum pump cart turbo protection valve	Fails closed	Turbo isolated from rougher	Safe	Operational problem - cryostat cannot be effectively evacuated

**Electric valves**

EV	79	Air	EP-78-Ar actuation	Fails open	Filter can't be isolated from cryostat	Safe	Operational problem - filter regeneration not possible
EV	79	Air	EP-78-Ar actuation	Fails closed	Liquid can't be forced from insulating space	Safe	Operational problem - poor filtration
EV	105	N2	LN2 transfer line into Luke condenser	Fails open	GAr will not be condensed	Safe	Operational problem - GAr will vent thru EP-205-Ar or PSV-210-Ar
EV	105	N2	LN2 transfer line into Luke condenser	Fails closed	Luke will not maintain positive pressure	Safe	Operational problem - LN2 will vent thru vaporizer
EV	106	N2	LN2 transfer line vent	Fails open	Transfer line cannot pre-cool	Safe	Operational problem - condenser performance could degrade
EV	106	N2	LN2 transfer line vent	Fails closed	LN2 will be wasted	Safe	Operational problem - LN2 will vent thru vaporizer
EV	223	Air	EP-222-V actuation	Fails open	Insulating vacuum spoiled	Safe	Operational problem - high thermal load during filtration or regeneration
EV	223	Air	EP-222-V actuation	Fails closed	Insulating vacuum isolated	Safe	Operational problem - can't improve vacuum
EV	232	V	EP-155-V actuation	Fails open	Insulating vacuum spoiled	Safe	Operational problem - high thermal load during filtration or regeneration
EV	232	V	EP-155-V actuation	Fails closed	Insulating vacuum isolated	Safe	Operational problem - can't improve vacuum
EV	233	Air	EP-362-V actuation	Fails open	Insulating vacuum spoiled	Safe	Operational problem - high thermal load during LAr transfer
EV	233	Air	EP-362-V actuation	Fails closed	Insulating vacuum isolated	Safe	Operational problem - can't improve vacuum
EV	258	Air	Material basket catch/release mechanism actuation	Fails open	Material basket cannot be released	Safe	Operational problem - poor filtration
EV	258	Air	Material basket catch/release mechanism actuation	Fails closed	Material basket cannot be released	Safe	Operational problem - poor filtration
EV	270	N2	EP-205-Ar actuation	Fails open	Cryostat cannot build pressure	Safe	Operational problem - Gar will be vented and system will no longer be closed
EV	270	N2	EP-205-Ar actuation	Fails closed	Excess pressure not vented	Safe	Operational problem - Gar will be vented thru PSV-210-Ar if needed
EV	287	V	EP-236V actuation	Fails open	Turbo isolated from rougher	Safe	Operational problem - cryostat cannot be effectively evacuated
EV	287	V	EP-236V actuation	Fails closed	Turbo not protected	Safe	Operational problem - turbo vacuum pump could be damaged
EV	384	V	EP-383-V actuation	Fails open	Turbo not protected	Safe	Operational problem - turbo vacuum pump could be damaged
EV	384	V	EP-383-V actuation	Fails closed	Turbo isolated from rougher	Safe	Operational problem - cryostat cannot be effectively evacuated

**Filters**

F	395	Ar	Removal of O2, H2O, and HCs from Luke contamination gas	Plugs	Can't introduce contamination gas	Safe	Operational problem - cannot perform contamination gas injection studies
---	-----	----	---	-------	-----------------------------------	------	--

F	395	Ar	Removal of O2, H2O, and HCs from Luke contamination gas	Does not filter	Contaminants not removed from test gas	Safe	Operational problem - contamination test could be invalidated by O2 or H2O contamination
---	-----	----	---	-----------------	--	------	--

**Flowmeters**

FI	278	Ar	Luke vapor pump trapped volume relief (PSV-156-Ar)	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	278	Ar	Luke vapor pump trapped volume relief (PSV-156-Ar)	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	279	Ar	Luke vapor pump electronic purge	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	279	Ar	Luke vapor pump electronic purge	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	280	Ar	Luke ASME relief purge (PSV-210-Ar)	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	280	Ar	Luke ASME relief purge (PSV-210-Ar)	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	281	Ar	Molecular sieve trapped volume relief purge (PSV-219-Ar)	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	281	Ar	Molecular sieve trapped volume relief purge (PSV-219-Ar)	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	282	Ar	O2 filter inlet side trapped volume relief (PSV-249-Ar)	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	282	Ar	O2 filter inlet side trapped volume relief (PSV-249-Ar)	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	283	Ar	O2 filter outlet side trapped volume relief (PSV-250-Ar)	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	283	Ar	O2 filter outlet side trapped volume relief (PSV-250-Ar)	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	284	Ar	Material lock release mechanism argon purge	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	284	Ar	Material lock release mechanism argon purge	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	312	Ar	Oxygen analyzer flow indicator	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - oxygen analyzer may report incorrect concentration
FI	315	Ar	Air lock argon purge	Manual valve fails closed	No GAr purge flow to air lock	Safe	Operational problem - can't remove contamination from air lock
FI	315	Ar	Air lock argon purge	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - purge may be slower than expected
FI	390	Ar	Bo ASME relief purge (PSV-378-Ar)	Manual valve fails closed	No GAr purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	390	Ar	Bo ASME relief purge (PSV-378-Ar)	Incorrect reading	Too little or too much purge flow	Safe	Operational problem - possible oxygen diffusion into clean LAr spaces
FI	391	Ar	Spare	Not in service	----	----	----
FI	392	Ar	Spare	Not in service	----	----	----
FI	406	HAr	Oxygen filter regeneration gas flow rate (metering valve limits to 5 SCFH)	Manual valve fails closed	No HAr regeneration gas flow	Safe	Operational problem - oxygen filter regeneration not possible
FI	406	HAr	Oxygen filter regeneration gas flow rate (metering valve limits to 5 SCFH)	Incorrect reading	Too little or too much gas flow	Safe	Operational problem - possible incomplete oxygen filter regeneration

**Flow restricting orifices**

FO	212	Ar	Liquid argon source manifold argon flow restriction	It is not reasonable for a 0.122 in. dia orifice to plug completely		----	----
----	-----	----	---	---	--	------	------

**Heating elements**

HTR	8	HAr	Oxygen filter regeneration heater	OFF	Oxygen filter cannot be regenerated	Safe	Operational problem - poor filtration
				ON	Oxygen filter overheats	Safe	Hardwired thermocouple interlock cuts heater power
				ON	LAr vaporized	Safe	PSV-249-Ar has enough capacity for LAr vaporization rate
HTR	21	Ar	Vapor pressure building heater	OFF	Can't build vapor pressure	Safe	Operational problem
				ON	Excess vapor pressure	Safe	PSV-210-Ar has enough capacity for LAr vaporization rate
				ON	Overheating	Safe	Hardwired thermocouple interlock cuts heater power
HTR	22	Ar	Vapor pressure building heater	OFF	Can't build vapor pressure	Safe	Operational problem
				ON	Excess vapor pressure	Safe	PSV-377-Ar has enough capacity for LAr vaporization rate
				ON	Overheating	Safe	Hardwired thermocouple interlock cuts heater power
HTR	55	HAr	Oxygen filter gas pre-heater	OFF	No oxygen filter gas preheat	Safe	Operational problem - poor filter regeneration
				ON	Oxygen filter overheats	Safe	Hardwired thermocouple interlock cuts heater power
				ON	LAr vaporized	Safe	PSV-249-Ar has enough capacity for LAr vaporization rate

HTR	72	HAr	Luke vapor pump filter regeneration heater	OFF	Oxygen filter cannot be regenerated	Safe	Operational problem - poor filtration
				ON	Oxygen filter overheats	Safe	Hardwired thermocouple interlock cuts heater power
				ON	LAr vaporized	Safe	Both PSV-156-Ar and PSV-210-Ar each have enough capacity for LAr vaporization rate
HTR	75	Ar	Luke vapor pump cup heater	OFF	LAr not pushed out of filter	Safe	Operational problem - poor filtration
				ON	Vapor generation cup overheats	Safe	Hardwired thermocouple interlock cuts heater power
				ON	LAr vaporized	Safe	Both PSV-156-Ar and PSV-210-Ar each have enough capacity for LAr vaporization rate
HTR	215	Ar	Molecular sieve regeneration heater	OFF	Molecular sieve cannot be regenerated	Safe	Operational problem - poor filtration
				ON	Molecular sieve overheats	Safe	Hardwired thermocouple interlock cuts heater power
				ON	LAr vaporized	Safe	PSV-219-Ar has enough capacity for LAr vaporization rate

**Output to DAQ**

INTL	325	Ar	24 VDC output to purity monitor for liquid level interlock	OPEN (0 VDC)	Can't operate purity monitor	Safe	Operational problem - liquid argon purity cannot be measured
INTL	325	Ar	24 VDC output to purity monitor for liquid level interlock	CLOSED (24 VDC)	Purity monitor HV arcing	Safe	Purity monitor could arc and damage itself if liquid level is too low - no personnel damage due to current limits and a well grounded cryostat.

**Liquid level transmitters**

LT	10	N2	Luke condenser LN2 level	Incorrect reading	GAr condenser control difficult	Safe	Operational problem - poor GAr vapor space pressure control
LT	13	Ar	Luke cryostat LAr level	Incorrect reading	Unknown quantity of LAr in cryostat	Safe	PSV-210-Ar can handle over filling of cryostat
LT	372	Ar	Bo cryostat LAr level	Incorrect reading	Unknown quantity of LAr in cryostat	Safe	PSV-377-Ar can handle over filling of cryostat

**Manual valves**

MV	80	N	LN2 dewar pressure gauge isolation	Fails open	Can't isolate PI-100-N	Safe	Operational problem - dewar must be blown down to fix instrumentation
MV	80	N	LN2 dewar pressure gauge isolation	Fails closed	PI-100-N is isolated	Safe	Operational problem - dewar vapor pressure not indicated, consult PT-51-N
MV	85	N	LN2 dewar vapor line pressure sensing isolation	Fails open	Can't isolate DPI-100-N	Safe	Operational problem - dewar must be blown down to fix instrumentation
MV	85	N	LN2 dewar vapor line pressure sensing isolation	Fails closed	DPI-100-N reads incorrectly	Safe	Operational problem - dewar liquid level not indicated properly
MV	86	N	LN2 dewar level gauge equalization	Fails open	Can't service gauge	Safe	Gauge could be damaged if equalization valve can't be closed and re-opened
MV	86	N	LN2 dewar level gauge equalization	Fails closed	DPI-100-N could be damaged	Safe	Operational problem - dewar liquid level gauge could be damaged
MV	87	N	LN2 dewar liquid line pressure sensing isolation	Fails open	Can't isolate DPI-100-N	Safe	Operational problem - dewar must be emptied to fix instrumentation
MV	87	N	LN2 dewar liquid line pressure sensing isolation	Fails closed	DPI-100-N reads incorrectly	Safe	Operational problem - dewar liquid level not indicated properly
MV	88	N	LN2 dewar pressure building regulator isolation	Fails open	Can't isolate pressure building regulator	Safe	MV-96-N, MV-95-N, and MV-89-N can still isolate pressure building loop
MV	88	N	LN2 dewar pressure building regulator isolation	Fails closed	Can't operate pressure building loop	Safe	Operational problem - dewar might not maintain adequate vapor pressure
MV	89	N	LN2 dewar pressure building loop isolation	Fails open	Can't isolate pressure building regulator	Safe	MV-96-N, MV-95-N, and MV-88-N can still isolate pressure building loop
MV	89	N	LN2 dewar pressure building loop isolation	Fails closed	Can't operate pressure building loop	Safe	Operational problem - dewar might not maintain adequate vapor pressure
MV	90	V	LN2 dewar vacuum pump out	Fails open	Insulating vacuum spoils	Safe	Operational problem - SV-100-N or SV-99-N can handle boil-off
MV	90	V	LN2 dewar vacuum pump out	Fails closed	Insulating vacuum can't be pumped on	Safe	Operational problem - dewar vacuum cannot be improved
MV	90	N	LN2 dewar pressure relieving regulator isolation	Fails open	RV-90-N can't be isolated	Safe	Operational problem - dewar must be blown down to service regulator
MV	90	N	LN2 dewar pressure relieving regulator isolation	Fails closed	RV-90-N can't vent excess pressure	Safe	SV-100-N or SV-99-N will safely vent excess vapor
MV	91	V	LN2 dewar vacuum readout isolation	Fails open	If PE-91-V leaks, insulating vacuum will spoil	Safe	Operational problem - SV-100-N or SV-99-N can handle boil-off

MV	91	V	LN2 dewar vacuum readout isolation	Fails closed	Inaccurate reading from PE-91-V	Safe	Operational problem - SV-100-N or SV-99-N can handle boil-off
MV	91	N	LN2 dewar fill line drain valve	Fails open	Large LN2 leak during fill	Safe	Operational problem - driver will not be able to fill LN2 dewar
MV	91	N	LN2 dewar fill line drain valve	Fails closed	Can't drain fill line	Safe	Excess pressure will vent thru SV-90-N
MV	92	N	LN2 dewar fill line isolation	Fails open	LN2 dewar drains into parking lot	Safe	Operational problem - dewar cannot be filled
MV	92	N	LN2 dewar fill line isolation	Fails closed	LN2 dewar cannot be filled	Safe	Operational problem - upstream components can handle tanker pump dead head pressure
MV	93	N	LN2 dewar vapor vent	Fails open	LN2 dewar blows down	Safe	Operational problem - no vapor pressure to transfer liquid
MV	93	N	LN2 dewar vapor vent	Fails closed	LN2 dewar can't be easily blown down	Safe	Operational problem - dewar will be hard to fill without blow down valve
MV	94	N	LN2 dewar full trycock	Fails open	LN2 dewar blows down	Safe	Operational problem - no vapor pressure to transfer liquid
MV	94	N	LN2 dewar full trycock	Fails closed	Difficult for tanker driver to determine when full	Safe	Operational problem - Driver can use DPI-100-N
MV	95	N	LN2 dewar pressure building loop bypass	Fails open	Excess vapor generation	Safe	SV-100-N or SV-99-N will safely vent excess vapor, closing MV-89-N stops vapor generation
MV	95	N	LN2 dewar pressure building loop bypass	Fails closed	No bypass for pressure building loop	Safe	Operational problem
MV	96	N	LN2 dewar pressure building regulator isolation	Fails open	Can't isolate pressure building regulator	Safe	Operational problem - closing MV-88-N or MV-89-N stops vapor generation
MV	96	N	LN2 dewar pressure building regulator isolation	Fails closed	Can't build vapor pressure	Safe	Operational problem - no vapor pressure to transfer liquid
MV	97	N	LN2 dewar liquid withdrawal	Fails open	LN2 dewar drains into parking lot	Safe	Operational problem
MV	97	N	LN2 dewar liquid withdrawal	Fails closed	Can't fill small hand dewars	Safe	Operational problem
MV	98	N	LN2 dewar relief valve selector	Fails open	Valve cannot fail open	Safe	Valve is open to either one side or the other of the relief "tree" such that it is always open
MV	98	N	LN2 dewar relief valve selector	Fails closed	One set of relief devices isolated	Safe	Operational problem - if valve sticks, can't switch between relief devices
MV	99	N	LN2 dewar vapor vent valve	Fails open	LN2 dewar blows down	Safe	Operational problem - no vapor pressure to transfer liquid
MV	99	N	LN2 dewar vapor vent valve	Fails closed	Can't vent pressure to service relief valve	Safe	Operational problem
MV	100	N	LN2 dewar liquid into PAB isolation	Fails open	Can't isolate PAB from LN2 dewar	Safe	MV-119-N and MV-120-N provide downstream isolation
MV	100	N	LN2 dewar liquid into PAB isolation	Fails closed	No LN2 flow into PAB	Safe	Operational problem
MV	101	N	LN2 dewar vapor vent valve	Fails open	LN2 dewar blows down	Safe	Operational problem - no vapor pressure to transfer liquid
MV	101	N	LN2 dewar vapor vent valve	Fails closed	Can't vent pressure to service relief valve	Safe	Operational problem
MV	107	N	LN2 dewar isolation for future gas use	Fails open	LN2 dewar drains into parking lot	Safe	Operational problem
MV	107	N	LN2 dewar isolation for future gas use	Fails closed	Normal position for current setup	Safe	Operational problem only if gas use is desired
MV	119	N	LN2 liquid transfer line branch isolation	Fails open	Can't isolate future LN2 branch	Safe	PSV-117-N2 @ 100 psig plugs LN2 branch supplied at a max of 75 psig
MV	119	N	LN2 liquid transfer line branch isolation	Fails closed	Normal position for current setup	Safe	Operational problem only if future LN2 expansion is required
MV	120	N	LN2 liquid transfer line Luke/Bo branch isolation	Fails open	Can't isolate LN2 supply to GAR condensers	Safe	EV-105-N2 and EV-106-N isolate LN2 flow downstream of MV-120-N
MV	120	N	LN2 liquid transfer line Luke/Bo branch isolation	Fails closed	No LN2 for GAR condensers	Safe	EP-205-Ar and PSV-210-Ar will vent cryostat boil-off
MV	124	Ar	Ar with O2 contamination source bottle regulator outlet isolation	Fails open	Can't isolate bottle regulator	Safe	Operational problem - can't isolate bottle regulator from vacuum pump
MV	124	Ar	Ar with O2 contamination source bottle regulator outlet isolation	Fails closed	No O2/Ar gas flow	Safe	Operational problem - can't perform contamination test
MV	127	Ar	Ar with O2 contamination source line regulator outlet isolation	Fails open	Can't isolate line regulator	Safe	Operational problem - can't isolate line regulator from vacuum pump
MV	127	Ar	Ar with O2 contamination source line regulator outlet isolation	Fails closed	No O2/Ar gas flow	Safe	Operational problem - can't perform contamination test
MV	128	Ar	Gas contamination introduction isolation	Fails open	No issue	Safe	MV-246-Ar provides a redundant function
MV	128	Ar	Gas contamination introduction isolation	Fails closed	No contamination gas flow	Safe	Operational problem - can't perform contamination test
MV	131	N2	N2 contamination source regulator outlet isolation	Fails open	Can't isolate bottle regulator	Safe	Operational problem - can't isolate bottle regulator from vacuum pump
MV	131	N2	N2 contamination source regulator outlet isolation	Fails closed	No N2/Ar gas flow	Safe	Operational problem - can't perform contamination test

MV	132	N2	Contamination manifold vacuum isolation	Fails open	Can't isolate vacuum pump	Safe	Operational problem - contamination gas will be vented thru vacuum pump
MV	132	N2	Contamination manifold vacuum isolation	Fails closed	Can't evacuate gas lines	Safe	Operational problem - gas lines must be evacuated for purity reasons
MV	202	Ar	Filter assembly inlet isolation	Fails open	Can't isolate filter	Safe	Operational problem - Only an issue if filter is removed from system and regenerated on a bench top
MV	202	Ar	Filter assembly inlet isolation	Fails closed	Potential trapped volume	Safe	Valve cannot be accessed from outside the vacuum jacket. It is a high quality all stainless steel valve that is unlikely to close.
MV	204	Ar	Liquid argon source manifold argon line isolation/pumpout	Fails open	LAr dumps onto floor	Safe	ODH analysis indicates this is acceptable and loud sound of high pressure liquid venting will cause those present to shut the valve
MV	204	Ar	Liquid argon source manifold argon line isolation/pumpout	Fails closed	Can't evacuate argon liquid line	Safe	Operational problem - contaminants will be left in argon liquid line
MV	208	Ar	Filter assembly outlet isolation	Fails open	Can't isolate filter	Safe	Operational problem - Only an issue if filter is removed from system and regenerated on a bench top
MV	208	Ar	Filter assembly outlet isolation	Fails closed	Potential trapped volume	Safe	To create trapped volume, MV-202-Ar must also be closed. MV-202-Ar cannot be accessed from outside the vacuum jacket. It is a high quality all stainless steel valve that is unlikely to close.
MV	213	Ar	Liquid argon source manifold isolation	Fails open	Can't isolate LAr source manifold	Safe	Operational problem - contamination may be introduced into system without proper isolation and evacuation
MV	213	Ar	Liquid argon source manifold isolation	Fails closed	Can't transfer LAr	Safe	Operational problem
MV	217	Ar	Molecular sieve isolation	Fails open	Can't isolate molecular sieve	Safe	Operational problem - regeneration and purity concerns
MV	217	Ar	Molecular sieve isolation	Fails closed	Can't transfer LAr	Safe	Operational problem - PSV-219-Ar relieves potential trapped volume
MV	218	Ar	Molecular sieve isolation/pumpout	Fails open	LAr dumps onto PAB floor	Safe	ODH analysis indicates this is acceptable and loud sound of high pressure liquid venting will cause those present to shut the valve
MV	218	Ar	Molecular sieve isolation/pumpout	Fails closed	Can't evacuate molecular sieve	Safe	Operational problem - regeneration and purity concerns
MV	224	V	Transfer line insulating vacuum pump cart roughing pump port isolation	Fails open	Can't evacuate transfer line	Safe	Operational problem - possible turbo pump damage if opened at wrong time
MV	224	V	Transfer line insulating vacuum pump cart roughing pump port isolation	Fails closed	Normal position	Safe	Operational problem - if another vacuum port is needed
MV	227	V	Insulating vacuum pump cart port isolation	Fails open	Can't evacuate transfer line	Safe	Operational problem - possible turbo pump damage if opened at wrong time
MV	227	V	Insulating vacuum pump cart port isolation	Fails closed	Normal position	Safe	Operational problem - if another vacuum port is needed
MV	228	V	Insulating vacuum pump cart port isolation	Fails open	Can't evacuate transfer line	Safe	Operational problem - possible turbo pump damage if opened at wrong time
MV	228	V	Insulating vacuum pump cart port isolation	Fails closed	Normal position	Safe	Operational problem - if another vacuum port is needed
MV	229	V	Cryostat pump cart port isolation	Fails open	Can't evacuate cryostat to high vacuum	Safe	Operational problem - possible turbo pump damage if opened at wrong time
MV	229	V	Cryostat pump cart port isolation	Fails closed	Can't evacuate cryostat	Safe	Operational problem - if another vacuum port is needed
MV	237	V	Seal monitor pump cart isolation	Fails open	Can't isolate vacuum pump	Safe	Operational problem
MV	237	V	Seal monitor pump cart isolation	Fails closed	Can't vacuum pump flange seal or air lock	Safe	Operational problem - purity difficult to obtain without this vacuum pump
MV	239	Ar	Liquid argon "dump" before Luke	Fails open	Can't fill cryostat	Safe	Operational problem - LAr vaporized and vented outside.
MV	239	Ar	Liquid argon "dump" before Luke	Fails closed	Can't dump initial flow thru filter	Safe	Operational problem - purity difficult to obtain without dumping initial flow thru filter
MV	241	Ar	Gas contamination introduction isolation	Fails open	No problem	Safe	MV-242-Ar performs the same function
MV	241	Ar	Gas contamination introduction isolation	Fails closed	Can't introduce gas samples	Safe	Operational problem
MV	242	Ar	Gas contamination introduction isolation	Fails open	No problem	Safe	MV-241-Ar performs the same function
MV	242	Ar	Gas contamination introduction isolation	Fails closed	Can't introduce gas samples	Safe	Operational problem
MV	244	Ar	Luke cryo isolation valve	Fails open	Can't isolate cryostat	Safe	Operational problem - filter warming up could release contaminants
MV	244	Ar	Luke cryo isolation valve	Fails closed	Can't fill cryostat	Safe	Operational problem - PSV-250-Ar relieves potential trapped volume
MV	246	Ar	Gas contamination introduction isolation	Fails open	Can't isolate sample bottle	Safe	Operational problem - need isolation to deliver a known volume
MV	246	Ar	Gas contamination introduction isolation	Fails closed	Can't introduce contaminants	Safe	Operational problem

MV	247	Ar	Luke vapor pump filter regeneration gas outlet isolation	Fails open	Filter is not isolated	Safe	Operational problem - could depressurize cryostat or introduce contamination
MV	247	Ar	Luke vapor pump filter regeneration gas outlet isolation	Fails closed	Filter regeneration not possible	Safe	Operational problem
MV	248	Ar	Luke vapor pump filter regeneration gas inlet isolation	Fails open	Filter is not isolated	Safe	Operational problem - could force liquid from cryostat or introduce contamination
MV	248	Ar	Luke vapor pump filter regeneration gas inlet isolation	Fails closed	Filter regeneration not possible	Safe	Operational problem
MV	251	V	"Air lock" vacuum isolation	Fails open	Air lock not isolated from turbo	Safe	Operational problem - can't use air lock
MV	251	V	"Air lock" vacuum isolation	Fails closed	Air lock evacuation not possible	Safe	Operational problem - contamination can't be removed from air lock
MV	252	Ar	"Air lock" argon bottle purge isolation	Fails open	Air lock is constantly purged	Safe	Operational problem
MV	252	Ar	"Air lock" argon bottle purge isolation	Fails closed	Air lock can't be purged with bottle gas	Safe	Operational problem - air lock can still be purged using cryostat gas
MV	253	Ar	"Air lock" cryostat vapor purge isolation	Fails open	Air lock is constantly purged	Safe	Operational problem
MV	253	Ar	"Air lock" cryostat vapor purge isolation	Fails closed	Air lock can't be purged with boil-off gas	Safe	Operational problem
MV	254	V	Luke materials test station air lock pass thru	Fails open	Air lock can't be isolated from cryostat	Safe	Operational problem - air lock must be isolated to remove contamination
MV	254	V	Luke materials test station air lock pass thru	Fails closed	Materials cannot be placed into cryostat	Safe	Operational problem
MV	255	Ar	Luke manual vapor vent	Fails open	Cryostat blows down	Safe	Operational problem
MV	255	Ar	Luke manual vapor vent	Fails closed	Can't manually vent cryostat	Safe	Operational problem - EP-205-Ar can vent vapor
MV	256	Ar	"Air lock" purge vent isolation	Fails open	Can't evacuate air lock	Safe	Operational problem - contamination not removed from air lock
MV	256	Ar	"Air lock" purge vent isolation	Fails closed	Can't purge air lock with Ar gas	Safe	Operational problem - contamination not removed from air lock
MV	261	V	Luke insulating vacuum isolation/pumpout	Fails open	Cryostat could loose insulating vacuum	Safe	Operational problem - PSV-210-Ar can handle boil-off
MV	261	V	Luke insulating vacuum isolation/pumpout	Fails closed	Can't vacuum pump insulating space	Safe	Operational problem - PSV-210-Ar can handle boil-off
MV	265	N2	Bleed up cylinder regulator outlet isolation	Fails open	No hazard	Safe	Normal position
MV	265	N2	Bleed up cylinder regulator outlet isolation	Fails closed	Can't use N2 gas	Safe	Operational problem - can't bleed up insulating vacuum with dry gas
MV	267	V	Transfer line insulating vacuum nitrogen bleed up isolation	Fails open	Insulating vacuum not isolated	Safe	Operational problem - MV-265-N2 also provides isolation
MV	267	V	Transfer line insulating vacuum nitrogen bleed up isolation	Fails closed	Can't use N2 gas	Safe	Operational problem - can't bleed up insulating vacuum with dry gas
MV	268	Air	Shop air isolation	Fails open	Shop air can't be isolated	Safe	Operational problem
MV	268	Air	Shop air isolation	Fails closed	Shop air not available for valve actuation	Safe	Operational problem - safety not dependent on actuated valves
MV	277	Ar	Argon purge regulator outlet isolation at flow meter panel	Fails open	No hazard	Safe	Normal position
MV	277	Ar	Argon purge regulator outlet isolation at flow meter panel	Fails closed	No Ar gas purge	Safe	Operational problem - O2 diffusion thru o-rings will contaminate cryostat
MV	290	Ar	Air lock purge inlet isolation	Fails open	No hazard	Safe	Redundant valving can provide isolation if required
MV	290	Ar	Air lock purge inlet isolation	Fails closed	Air lock can't be purged	Safe	Operational problem - Air lock can't be purged which could lead to cryostat contamination
MV	291	Ar	Air lock purge oxygen monitor isolation	Fails open	No hazard	Safe	Redundant valving can provide equivalent functionality
MV	291	Ar	Air lock purge oxygen monitor isolation	Fails closed	No hazard	Safe	Redundant valving can provide equivalent functionality
MV	294	Ar	Oxygen monitor manifold inlet isolation	Fails open	No hazard	Safe	Redundant valving can provide equivalent functionality
MV	294	Ar	Oxygen monitor manifold inlet isolation	Fails closed	No hazard	Safe	Redundant valving can provide equivalent functionality
MV	295	V	Oxygen monitor vacuum pump isolation	Fails open	Can't isolate vacuum pump	Marginal	Vacuum pump could be damaged by excessive inlet pressure or oxygen monitor could be damaged by vacuum
MV	295	V	Oxygen monitor vacuum pump isolation	Fails closed	Vacuum pump cannot be used	Safe	Operational problem - gas sampling lines cannot be evacuated before use
MV	296	Ar	Oxygen monitor open port isolation	Fails open	Sample gas flow fails to reach meter	Safe	Operational problem - air lock purge cannot be monitored
MV	296	Ar	Oxygen monitor open port isolation	Fails closed	No effect	Safe	Normal position
MV	300	Ar	Oxygen monitor metering valve	Fails open	Can't control gas sample gas flow	Safe	Operational problem - air lock purge gas sample reading will be inaccurate if flowmeter does not indicate 2 SCFH
MV	300	Ar	Oxygen monitor metering valve	Fails closed	Sample gas flow fails to reach meter	Safe	Operational problem - air lock purge cannot be monitored

MV	310	Ar	Oxygen monitor inlet isolation	Fails open	No hazard	Safe	Normal position
MV	310	Ar	Oxygen monitor inlet isolation	Fails closed	Sample gas flow fails to reach meter	Safe	Operational problem - air lock purge cannot be monitored
MV	316	Ar	Argon purge regulator outlet isolation at bottle	Fails open	No hazard	Safe	Normal position
MV	316	Ar	Argon purge regulator outlet isolation at bottle	Fails closed	No Ar gas purge	Safe	Operational problem - O2 diffusion thru o-rings will contaminate cryostat
MV	327	Ar	Luke condenser argon space vent	Fails open	Luke depressurizes	Safe	Operational problem - ODH analysis takes this venting into account
MV	327	Ar	Luke condenser argon space vent	Fails closed	Condenser GAR space inaccessible	Safe	Operational problem - can't perform contamination test
MV	328	Ar	Luke vapor pump equalization isolation	Fails open	Can't isolate during regeneration	Safe	Operational problem - When filter is removed for regeneration, it cannot be isolated from atmosphere and regeneration will fail
MV	328	Ar	Luke vapor pump equalization isolation	Fails closed	Vapor pump can't cycle	Safe	Operational problem - Blocks the cycling action of EP-78-Ar which stops the filter from cycling
MV	329	Ar	Luke vapor pump vent isolation	Fails open	Luke depressurizes	Safe	Gas vents to the outside thru the vent header
MV	329	Ar	Luke vapor pump vent isolation	Fails closed	No effect	Safe	Normal position
MV	333	CO2	Vapor pump transport CO2 bottle regulator outlet isolation	Fails open	CO2 sees LAr temperatures in cold valve	Safe	Operational problem - liquid in cold valve actuator may cause a malfunction
MV	333	CO2	Vapor pump transport CO2 bottle regulator outlet isolation	Fails closed	CO2 can't reach cold valve	Safe	Operational problem - can't shut cold valve during filter regeneration
MV	336	V	Vapor pump cold valve vacuum isolation	Fails open	Cold valve sticks open	Safe	Operational problem - can't shut cold valve during filter regeneration
MV	336	V	Vapor pump cold valve vacuum isolation	Fails closed	Cold valve cannot be opened	Safe	Operational problem - liquid cannot be filtered unless the cold valve is open
MV	337	He	Vapor pump cold valve isolation at vapor pump top flange	Fails open	No effect	Safe	Normal position, CO2, He, and vacuum isolation provided by other valves
MV	337	He	Vapor pump cold valve isolation at vapor pump top flange	Fails closed	Cold valve cannot be opened	Safe	Operational problem - liquid cannot be filtered unless the cold valve is open
MV	338	He	Vapor pump cold valve He supply isolation	Fails open	Can't open cold valve	Safe	Operational problem - liquid cannot be filtered unless the cold valve is open
MV	338	He	Vapor pump cold valve He supply isolation	Fails closed	Cold valve can't be closed in LAr	Safe	Operational problem - can't close cold valve without He gas if the valve is immersed in LAr
MV	342	He	He bottle regulator outlet isolation	Fails open	No hazard	Safe	Normal position
MV	342	He	He bottle regulator outlet isolation	Fails closed	Cold valve can't be closed in LAr	Safe	Operational problem - can't close cold valve without He gas if the valve is immersed in LAr
MV	354	Ar	Luke liquid space tap isolation	Fails closed	No hazard	Safe	Normal position
MV	354	Ar	Luke liquid space tap isolation	Fails open	Luke depressurizes	Safe	Operational problem - ODH analysis takes this venting into account
MV	360	V	Luke vacuum pumpout isolation valve	Fails open	Can't isolate cryostat from turbo pump cart	Safe	Operational problem - cryostat could wreck turbo
MV	360	V	Luke vacuum pumpout isolation valve	Fails closed	Can't evacuate cryostat	Safe	Operational problem - cryostat must be evacuated to remove air contamination
MV	365	V	O2 filter vacuum isolation (downstream tap)	Fails open	Can't use O2 filter	Safe	Operational problem
MV	365	V	O2 filter vacuum isolation (downstream tap)	Fails closed	Can't evacuate filter from downstream side	Safe	Operational problem - may not be able to effectively remove contamination
MV	366	V	O2 filter vacuum isolation (upstream tap)	Fails open	Can't use O2 filter	Safe	Operational problem
MV	366	V	O2 filter vacuum isolation (upstream tap)	Fails closed	Can't evacuate filter from upstream side	Safe	Operational problem - may not be able to effectively remove contamination
MV	368	V	Bo insulating vacuum isolation	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	368	V	Bo insulating vacuum isolation	Fails closed	No effect	Safe	Redundant valving can provide equivalent functionality
MV	369	V	Bo insulating vacuum isolation/pumpout	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	369	V	Bo insulating vacuum isolation/pumpout	Fails closed	No effect	Safe	Redundant valving can provide equivalent functionality
MV	370	Ar	Luke drain valve	Fails open	Cryostat empties	Safe	Operational problem - LAr is vaporized and vents outside
MV	370	Ar	Luke drain valve	Fails closed	Can't drain liquid from cryostat	Safe	Operational problem - could use heaters to vaporize LAr
MV	375	N2	PT-27-N2 isolation	Fails open	Must disrupt process to service transmitter	Safe	Operational problem

MV	375	N2	PT-27-N2 isolation	Fails closed	Transmitter fails to report accurate pressure	Safe	Operational problem
MV	379	Ar	Bo LAr fill isolation valve	Fails open	Can't bypass during cooldown	Safe	Operational problem - purity difficult to obtain without dumping initial flow thru filter
MV	379	Ar	Bo LAr fill isolation valve	Fails closed	Can't fill Bo with LAr	Safe	Operational problem
MV	380	Ar	Bo venting isolation	Fails open	Cryostat blows down	Safe	Operational problem
MV	380	Ar	Bo venting isolation	Fails closed	Can't manually vent cryostat	Safe	Operational problem - PSV-377-Ar and PSV-378-Ar can vent vapor
MV	381	V	Bo inner vessel vacuum pumpout	Fails open	Can't isolate cryostat from turbo pump cart	Safe	Operational problem - cryostat pressure could wreck turbo
MV	381	V	Bo inner vessel vacuum pumpout	Fails closed	Can't evacuate cryostat	Safe	Operational problem - cryostat must be evacuated to remove air contamination
MV	386	V	Bo vacuum pump cart rough pump isolation	Fails open	No effect	Safe	Normal position
MV	386	V	Bo vacuum pump cart rough pump isolation	Fails closed	Can't evacuate cryostat	Safe	Operational problem - cryostat must be evacuated to remove air contamination
MV	387	V	Bo vacuum pump cart bleed up valve	Fails open	Can't evacuate cryostat	Safe	Operational problem - cryostat must be evacuated to remove air contamination
MV	387	V	Bo vacuum pump cart bleed up valve	Fails closed	No effect	Safe	Normal position
MV	393	Ar	Luke contamination gas filter isolation	Fails open	No effect	Safe	Normal position
MV	393	Ar	Luke contamination gas filter isolation	Fails closed	Can't filter gas	Safe	Operational problem - contaminant test may be flawed
MV	394	Ar	Luke contamination gas filter isolation	Fails open	No effect	Safe	Normal position
MV	394	Ar	Luke contamination gas filter isolation	Fails closed	Can't filter gas	Safe	Operational problem - contaminant test may be flawed
MV	401	HAr	5% H2 95% Ar O2 filter regeneration gas metering valve	Fails open	No effect	Safe	Normal position is fully open
MV	401	HAr	5% H2 95% Ar O2 filter regeneration gas metering valve	Fails closed	Can't regenerate O2 filter	Safe	Operational problem
MV	418	HAr	Regeneration vacuum pump isolation	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	418	HAr	Regeneration vacuum pump isolation	Fails closed	No effect	Safe	Redundant valving can provide equivalent functionality
MV	419	HAr	Regeneration vacuum pump isolation	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	419	HAr	Regeneration vacuum pump isolation	Fails closed	No effect	Safe	Redundant valving can provide equivalent functionality
MV	420	HAr	Regeneration vacuum pump bleed up	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	420	HAr	Regeneration vacuum pump bleed up	Fails closed	Can't start vacuum valve	Safe	Oil sealed valve might not start under vacuum
MV	461	HAr	O2 filter regeneration isolation (exhaust)	Fails open	LAr transfer line vents outside	Safe	Operational problem - venting liquid could damage transmitters
MV	461	HAr	O2 filter regeneration isolation (exhaust)	Fails closed	Can't regenerate filter	Safe	Operational problem
MV	480	HAr	O2 filter regeneration isolation (inlet)	Fails open	Possible contamination	Safe	Operational problem - contamination could reach LAr piping
MV	480	HAr	O2 filter regeneration isolation (inlet)	Fails closed	Can't regenerate filter	Safe	Operational problem
MV	V2	HAr	Regulator isolation	Fails open	No effect - Not in use	Safe	----
MV	V2	HAr	Regulator isolation	Fails closed	No effect - Not in use	Safe	----
MV	V4	HAr	Regulator isolation	Fails open	No effect - Not in use	Safe	----
MV	V4	HAr	Regulator isolation	Fails closed	No effect - Not in use	Safe	----
MV	V7	HAr	Line pressure regulator outlet isolation	Fails open	Possible contamination	Safe	Operational problem - could introduce contaminants into regeneration gas
MV	V7	HAr	Line pressure regulator outlet isolation	Fails closed	No effect - Not in use	Safe	Normal position
MV	V8	HAr	Regeneration vacuum pump isolation	Fails open	Can't regenerate O2 filter	Safe	Operational problem
MV	V8	HAr	Regeneration vacuum pump isolation	Fails closed	Can't evacuate regeneration piping	Safe	Operational problem - possible contamination
MV	V9	HAr	Bench top oxygen filter regeneration isolation	Fails open	Can't regenerate "p-bar" O2 filter	Safe	Operational problem
MV	V9	HAr	Bench top oxygen filter regeneration isolation	Fails closed	Can't regenerate local O2 filter	Safe	Operational problem
MV	V10	HAr	Regeneration gas isolation	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	V10	HAr	Regeneration gas isolation	Fails closed	No effect	Safe	Redundant valving can provide equivalent functionality

MV	V12	HAr	Regeneration gas isolation	Fails open	No effect	Safe	Redundant valving can provide equivalent functionality
MV	V12	HAr	Regeneration gas isolation	Fails closed	No effect	Safe	Redundant valving can provide equivalent functionality
MV	V14	HAr	5% H2 95% Ar O2 filter regeneration gas bottle regulator outlet isolation	Fails open	No effect	Safe	Normal position is fully open
MV	V14	HAr	5% H2 95% Ar O2 filter regeneration gas bottle regulator outlet isolation	Fails closed	Can't regenerate O2 filter	Safe	Operational problem

**Pressure regulators and pressure control valves**

PCV	70	N	Fill shut off valve	Fails open	LN2 dewar not protected from overflow	Marginal	LN2 dewar could be over pressurized during a fill if dewar relief valves are over powered by the tanker truck centrifugal pump. There is a very low probability of PCV-70-N failing to protect the dewar. It is a high quality valve with a TUV certificate.
PCV	70	N	Fill shut off valve	Fails closed	LN2 dewar cannot be filled	Safe	Operational problem - No LN2 to condense GAR
PCV	121	Ar	Ar with O2 contamination source bottle regulator	Fails open	Downstream components see bottle pressure	Safe	PSV-136-Ar protects downstream components
PCV	121	Ar	Ar with O2 contamination source bottle regulator	Fails closed	Contamination gas cannot flow	Safe	Operational problem
PCV	125	Ar	Ar with O2 contamination source line regulator	Fails open	No additional line pressure regulation	Safe	Operational problem
PCV	125	Ar	Ar with O2 contamination source line regulator	Fails closed	Contamination gas cannot flow	Safe	Operational problem
PCV	129	N2	Nitrogen contamination source bottle regulator	Fails open	Downstream components see bottle pressure	Safe	PSV-136-Ar protects downstream components
PCV	129	N2	Nitrogen contamination source bottle regulator	Fails closed	Contamination gas cannot flow	Safe	Operational problem
PCV	262	N2	LAr transfer line insulating vacuum bleed up regulator	Fails open	Downstream components see bottle pressure	Safe	PSV-137-N2 protects downstream components
PCV	262	N2	LAr transfer line insulating vacuum bleed up regulator	Fails closed	Bleed up gas cannot flow	Safe	Operational problem
PCV	269	Air	Shop air point of use regulator	Fails open	Shop air is unregulated	Safe	Operational problem
PCV	269	Air	Shop air point of use regulator	Fails closed	Shop air not available for valve actuation	Safe	Operational problem - safety not dependent on actuated valves
PCV	273	Ar	Argon purge bottle regulator	Fails open	Downstream components see bottle pressure	Safe	PSV-276-ar protects downstream components
PCV	273	Ar	Argon purge bottle regulator	Fails closed	Contamination gas cannot flow	Safe	Operational problem
PCV	292	Air	Materials basket catch/release mechanism line pressure regulation	Fails open	Catch/release mechanism operates poorly	Safe	Operational problem - PCV-269-AIR provides additional regulation
PCV	292	Air	Materials basket catch/release mechanism line pressure regulation	Fails closed	Catch/release mechanism does not operate	Safe	Operational problem
PCV	297	Ar	Oxygen monitor inlet pressure regulation	Fails open	Purge gas over pressurizes meter	Marginal	Possible damage to oxygen meter if purge gas pressure is too high. However the metering valve MV-300-Ar should provide enough pressure drop to protect the meter
PCV	297	Ar	Oxygen monitor inlet pressure regulation	Fails closed	Can't analyze purge gas	Safe	Operational problem
PCV	330	CO2	Vapor pump transport CO2 bottle regulator	Fails open	Unregulated CO2 pressure	Safe	PSV-335-CO2 relieves excess pressure and MV-333-CO2 is rated for 3000 psig which is > ~1000 psig CO2 bottle pressure
PCV	330	CO2	Vapor pump transport CO2 bottle regulator	Fails closed	Can't close vapor pump cold valve	Safe	Operational problem when cryostat is warm
PCV	339	He	Vapor pump cold valve He supply bottle regulator	Fails open	Unregulated He pressure	Safe	PSV-343-He relieves excess pressure and MV-342-He can handle the bottle pressure
PCV	339	He	Vapor pump cold valve He supply bottle regulator	Fails closed	Can't close vapor pump cold valve	Safe	Operational problem when cryostat is cold
PCV	388	N2	Luke condenser back pressure regulator	Fails open	No hazard	Safe	Operational problem if increased LN2 temperature is desired
PCV	388	N2	Luke condenser back pressure regulator	Fails closed	Trapped volume	Safe	PSV-389-N2 relieves trapped volume
PCV	396	HAr	O2 filter regeneration gas bottle regulator (located outside PAB)	Fails open	Unregulated bottle pressure	Safe	PSV-399-HAr and PSV-400-HAr relieve excess pressure and MV-V14-HAr is rated for bottle pressure
PCV	396	HAr	O2 filter regeneration gas bottle regulator (located outside PAB)	Fails closed	Can't regenerate O2 filter	Safe	Operational problem
PCV	402	Ar	Line pressure regulation	Fails open	No effect - Not in use	Safe	----
PCV	402	Ar	Line pressure regulation	Fails closed	No effect - Not in use	Safe	----

**Vacuum pressure elements**

PE	91	V	LN2 dewar insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - SV-99-N or SV-100-N handles excess boil-off
PE	91	V	LN2 dewar insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem

PE	225	V	Liquid argon source manifold insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid loss during LAr transfer
PE	225	V	Liquid argon source manifold insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	226	V	Insulating vacuum pump cart inter-stage pressure	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - may have trouble turning on turbo
PE	226	V	Insulating vacuum pump cart inter-stage pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	230	V	Insulating vacuum pump cart pressure	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - redundant instrument with PE-231-V
PE	230	V	Insulating vacuum pump cart pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	231	V	Insulating vacuum pump cart pressure	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - redundant instrument with PE-230-V
PE	231	V	Insulating vacuum pump cart pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	234	V	Transfer line insulating vacuum pressure	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid loss during LAr transfer
PE	234	V	Transfer line insulating vacuum pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	235	V	Oxygen filter insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid loss during LAr transfer, PT-15-V provides another measurement of this vacuum
PE	235	V	Oxygen filter insulating vacuum	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	238	V	Seal monitor pump cart pressure	Incorrect reading -low	Seal vacuum worse than indicated	Safe	Operational problem - poor vacuum can lead to contamination, PT-69-V provides another measurement of this vacuum
PE	238	V	Seal monitor pump cart pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem PT-69-V provides another measurement of this vacuum
PE	288	V	Cryostat pump cart vacuum pressure	Incorrect reading -low	Pump cart vacuum worse than indicated	Safe	Operational problem - PT-19-V and PT-33-V will indicate if vacuum is poor
PE	288	V	Cryostat pump cart vacuum pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	312	V	Oxygen monitor manifold vacuum pump inlet pressure	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - possible contamination
PE	312	V	Oxygen monitor manifold vacuum pump inlet pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	348	V	LN2 transfer insulating vacuum near Luke	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid loss during LN2 transfer
PE	348	V	LN2 transfer insulating vacuum near Luke	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem, PE-409-V provides redundant instrumentation
PE	371	V	Bo insulating vacuum gauge tube	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid losses, PSV-377-Ar can handle loss of vacuum boiloff and PT-17-V provides redundant instrumentation
PE	371	V	Bo insulating vacuum gauge tube	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem, PT-17-V provides redundant instrumentation
PE	408	V	LN2 transfer insulating vacuum dewar side	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid loss during LN2 transfer
PE	408	V	LN2 transfer insulating vacuum dewar side	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	409	V	LN2 transfer insulating vacuum dewar side	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - larger liquid loss during LN2 transfer, PE-348-V provides redundant instrumentation
PE	409	V	LN2 transfer insulating vacuum dewar side	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem, PE-348-V provides redundant instrumentation.
PE	416	HAr	Regeneration gas vent line pressure	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - possible contamination
PE	416	HAr	Regeneration gas vent line pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PE	417	HAr	Regeneration gas vacuum pump inlet pressure	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - possible contamination
PE	417	HAr	Regeneration gas vacuum pump inlet pressure	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem

**Pressure indicating gauges**

PI	12	Ar	Luke cryostat Ar pressure	Incorrect reading -low	No hazard	Safe	Operational problem - PT-11-Ar provides redundant instrumentation
PI	12	Ar	Luke cryostat Ar pressure	Incorrect reading - high	No hazard	Safe	Operational problem - PT-11-Ar provides redundant instrumentation
PI	44	N2	LN2 transfer line pressure	Incorrect reading -low	No hazard	Safe	Operational problem - PT-27-N2 provides redundant instrumentation
PI	44	N2	LN2 transfer line pressure	Incorrect reading - high	No hazard	Safe	Operational problem - PT-27-N2 provides redundant instrumentation
PI	100	N	LN2 dewar pressure	Incorrect reading -low	No hazard	Safe	Operational problem - could make it difficult for tanker truck driver to match dewar pressure during fill, PT-51-N provides redundant instrumentation
PI	100	N	LN2 dewar pressure	Incorrect reading - high	No hazard	Safe	Operational problem - could make it difficult for tanker truck driver to match dewar pressure during fill, PT-51-N provides redundant instrumentation
PI	122	Ar	Ar with O2 contamination source bottle pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	122	Ar	Ar with O2 contamination source bottle pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	123	Ar	Ar with O2 contamination source regulated bottle pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	123	Ar	Ar with O2 contamination source regulated bottle pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	126	Ar	Ar with O2 contamination source regulated line pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	126	Ar	Ar with O2 contamination source regulated line pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	130	N2	N2 contamination source bottle pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	130	N2	N2 contamination source bottle pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	133	N2	LN2 vent back pressure	Incorrect reading -low	No hazard	Safe	Operational problem - PT-1-N2 provides redundant instrumentation
PI	133	N2	LN2 vent back pressure	Incorrect reading - high	No hazard	Safe	Operational problem - PT-1-N2 provides redundant instrumentation
PI	134	N2	N2 contamination regulated pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	134	N2	N2 contamination regulated pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	243	Ar	Gas contamination sample bottle isolation	Incorrect reading -low	No hazard	Safe	Operational problem
PI	243	Ar	Gas contamination sample bottle isolation	Incorrect reading - high	No hazard	Safe	Operational problem
PI	263	N2	Bleed up cylinder bottle pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	263	N2	Bleed up cylinder bottle pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	264	N2	Bleed up cylinder regulated pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	264	N2	Bleed up cylinder regulated pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	272	Air	Shop air regulated pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	272	Air	Shop air regulated pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	274	Ar	Argon purge cylinder pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	274	Ar	Argon purge cylinder pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	275	Ar	Argon purge cylinder regulated pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	275	Ar	Argon purge cylinder regulated pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	293	Air	Materials basket catch/release mechanism line pressure regulator outlet	Incorrect reading -low	Catch/release mechanism could malfunction	Safe	Operational problem if supplied pressure is incorrect
PI	293	Air	Materials basket catch/release mechanism line pressure regulator outlet	Incorrect reading - high	Catch/release mechanism could malfunction	Safe	Operational problem if supplied pressure is incorrect
PI	298	Ar	Oxygen monitor line pressure regulator inlet pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	298	Ar	Oxygen monitor line pressure regulator inlet pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	299	Ar	Oxygen monitor line pressure regulator outlet pressure	Incorrect reading -low	Over pressurize oxygen meter	Marginal	Metering valve MV-300-Ar should provide enough pressure drop restriction to prevent over pressurizing the meter
PI	299	Ar	Oxygen monitor line pressure regulator outlet pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	326	Ar	Material lock pressure	Incorrect reading -low	No hazard	Safe	Operational problem

PI	326	Ar	Material lock pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	331	CO2	Vapor pump transport CO2 bottle regulator inlet pressure	Incorrect reading -low	No hazard	Safe	Operational problem - bottle may not be empty despite indication
PI	331	CO2	Vapor pump transport CO2 bottle regulator inlet pressure	Incorrect reading - high	No hazard	Safe	Operational problem - bottle may empty despite indication
PI	332	CO2	Vapor pump transport CO2 bottle regulator outlet pressure	Incorrect reading -low	No hazard	Safe	Operational problem - PI-334-CO2 provides redundant instrumentation
PI	332	CO2	Vapor pump transport CO2 bottle regulator outlet pressure	Incorrect reading - high	No hazard	Safe	Operational problem - PI-334-CO2 provides redundant instrumentation
PI	334	CO2	Vapor pump cold valve pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	334	CO2	Vapor pump cold valve pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	340	He	He bottle regulator inlet	Incorrect reading -low	No hazard	Safe	Operational problem
PI	340	He	He bottle regulator inlet	Incorrect reading - high	No hazard	Safe	Operational problem
PI	341	He	He bottle regulator outlet	Incorrect reading -low	No hazard	Safe	Operational problem
PI	341	He	He bottle regulator outlet	Incorrect reading - high	No hazard	Safe	Operational problem
PI	345	Ar	LAr supply manifold line pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	345	Ar	LAr supply manifold line pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	363	Ar	Bo cryostat Ar pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	363	Ar	Bo cryostat Ar pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	397	HAr	5% H2 95% Ar O2 filter regeneration gas bottle regulator inlet pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	397	HAr	5% H2 95% Ar O2 filter regeneration gas bottle regulator inlet pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	398	HAr	5% H2 95% Ar O2 filter regeneration gas bottle regulator outlet pressure	Incorrect reading -low	No hazard	Safe	Operational problem
PI	398	HAr	5% H2 95% Ar O2 filter regeneration gas bottle regulator outlet pressure	Incorrect reading - high	No hazard	Safe	Operational problem
PI	403	Ar	Line pressure (not in use)	Incorrect reading -low	No hazard	Safe	Operational problem
PI	403	Ar	Line pressure (not in use)	Incorrect reading - high	No hazard	Safe	Operational problem
PI	404	Ar	Line pressure regulator inlet pressure (not in use)	Incorrect reading -low	No hazard	Safe	Operational problem
PI	404	Ar	Line pressure regulator inlet pressure (not in use)	Incorrect reading - high	No hazard	Safe	Operational problem
PI	405	Ar	Line pressure regulator outlet pressure (not in use)	Incorrect reading -low	No hazard	Safe	Operational problem
PI	405	Ar	Line pressure regulator outlet pressure (not in use)	Incorrect reading - high	No hazard	Safe	Operational problem

**Pressure relief valves**

PSV	101	N2	LN2 transfer line trapped volume relief	Fails open	LN2 vents outside	Safe	Operational problem
PSV	101	N2	LN2 transfer line trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	117	N2	LN2 transfer line trapped volume relief	Fails open	LN2 vents outside	Safe	Operational problem
PSV	117	N2	LN2 transfer line trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	118	N2	LN2 transfer line trapped volume relief	Fails open	LN2 vents outside	Safe	Operational problem
PSV	118	N2	LN2 transfer line trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	136	Ar	Contamination gas supply line relief	Fails open	Bottle gas vents into PAB	Safe	ODH analysis indicates this is acceptable
PSV	136	Ar	Contamination gas supply line relief	Fails closed	Components unprotected against bottle failure	Marginal	Requires both the bottle regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.
PSV	137	N2	Bleed up gas supply line relief	Fails open	Bottle gas vents into PAB	Safe	ODH analysis indicates this is acceptable
PSV	137	N2	Bleed up gas supply line relief	Fails closed	Components unprotected against bottle failure	Marginal	Requires both the bottle regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.

PSV	156	Ar	Luke vapor pump trapped volume relief	Fails open	GAr vents outside	Safe	Operational problem - Vapor pump will malfunction,
PSV	156	Ar	Luke vapor pump trapped volume relief	Fails closed	Potential trapped volume	Safe	Bellows in Fermilab designed and fabricated "cold" valve EP-308-Ar will fail and vent filter volume into cryostat.
PSV	203	Ar	Liquid argon source manifold trapped volume relief	Fails open	GAr vents outside	Safe	----
PSV	203	Ar	Liquid argon source manifold trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	210	Ar	Luke LAr volume pressure relief	Fails open	GAr vents outside	Safe	Operational problem - Can't build pressure in cryostat
PSV	210	Ar	Luke LAr volume pressure relief	Fails closed	Potential trapped volume	Safe	Very low probability of an ASME coded relief valve failing shut. Rupture disk RD-302-Ar will blow at 55 psig which is 1.5x MAWP
PSV	211	Ar	Pbar molecular sieve filter dewar inner vessel relief	Fails open	Spoils molecular sieve insulating vacuum	Safe	Increased losses during LAr transfer or increased heat load during filter regeneration
PSV	211	Ar	Pbar molecular sieve filter dewar inner vessel relief	Fails closed	No Hazard	Safe	CVI-220-V provides relief at ~ 0 psig with its spring removed
PSV	219	Ar	Molecular sieve trapped volume relief	Fails open	LAr flows to vaporizer and vents outside PAB	Safe	Operational problem - poor LAr transfer, contamination introduction if piping is evacuated
PSV	219	Ar	Molecular sieve trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	249	Ar	LAr transfer line trapped volume relief	Fails open	LAr vents outside PAB	Safe	Operational problem - poor LAr transfer, contamination introduction if piping is evacuated
PSV	249	Ar	LAr transfer line trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	250	Ar	LAr transfer line trapped volume relief	Fails open	LAr vents outside PAB	Safe	Operational problem - poor LAr transfer, contamination introduction if piping is evacuated
PSV	250	Ar	LAr transfer line trapped volume relief	Fails closed	Potential trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
PSV	276	Ar	Argon purge pressure relief	Fails open	Bottle supplied GAr vents inside PAB	Safe	Operational problem - Possible o-ring O2 diffusion contamination, ODH analysis indicates GAr venting is acceptable
PSV	276	Ar	Argon purge pressure relief	Fails closed	Downstream components unprotected	Marginal	Requires both the bottle regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.
PSV	313	Ar	Materials lock pressure relief	Fails open	Materials lock & possibly cryostat depressurize	Safe	Operational problem
PSV	313	Ar	Materials lock pressure relief	Fails closed	Materials lock & and bellows over pressurized	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase. Also its very difficult for liquid to reach this space.
PSV	335	CO2	Vapor pump transport CO2 supply relief (also relieves He when in Luke)	Fails open	CO2 or He vents into PAB	Safe	Operational problem - can't close cold valve
PSV	335	CO2	Vapor pump transport CO2 supply relief (also relieves He when in Luke)	Fails closed	Downstream components unprotected	Marginal	Requires both the bottle regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.
PSV	343	He	He bottle supply relief valve	Fails open	He vents into PAB	Safe	Operational problem
PSV	343	He	He bottle supply relief valve	Fails closed	Downstream components unprotected	Marginal	Requires both the bottle regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.
PSV	344	V	LAr transfer line vacuum relief	Fails open	Spoils LAr transfer line insulating vacuum	Safe	Operational problem - Increased liquid loss during LAr transfer
PSV	344	V	LAr transfer line vacuum relief	Fails closed	Potential trapped volume	Marginal	Unlikely a cryogenic leak from the inner line could build up much pressure in a vacuum jacket constructed from vacuum fittings. There is a very low probability of a parallel plate relief failing open.
PSV	377	Ar	Bo LAr volume pressure relief	Fails open	GAr vents outside	Safe	Operational problem - Can't build pressure in cryostat

PSV	377	Ar	Bo LAr volume pressure relief	Fails closed	Potential trapped volume	Safe	Very low probability of an ASME coded relief valve failing shut. Rupture disk RD-302-Ar will blow at 55 psig which is 1.5x MAWP and can handle all relieving conditions. PSV-378-Ar will open at 10 psig.
PSV	378	Ar	Bo LAr volume operational relief	Fails open	GAr vents outside	Safe	Operational problem - Can't build pressure in cryostat
PSV	378	Ar	Bo LAr volume operational relief	Fails closed	No Hazard	Safe	----
PSV	389	N2	Luke condenser trapped volume relief	Fails open	LAr vents outside	Safe	Operational problem - Can't build pressure in condenser
PSV	389	N2	Luke condenser trapped volume relief	Fails closed	Potential trapped volume	Safe	Requires both relieving regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.
PSV	399	HAr	5% H2 95% Ar O2 filter regeneration gas supply relief	Fails open	5% H2 / 95% Ar vents outside PAB	Safe	Operational problem - can't regenerate oxygen filters
PSV	399	HAr	5% H2 95% Ar O2 filter regeneration gas supply relief	Fails closed	No Hazard	Safe	PSV-400-HAr protects all downstream piping except for MV-V14-Har which is rated for bottle pressure
PSV	400	HAr	5% H2 95% Ar O2 filter regeneration gas supply relief	Fails open	5% H2 / 95% Ar vents outside PAB	Safe	Operational problem - can't regenerate oxygen filters
PSV	400	HAr	5% H2 95% Ar O2 filter regeneration gas supply relief	Fails closed	Downstream components unprotected	Safe	Requires both the bottle regulator and the relief valve to fail to create a hazard. There is a very low probability of both components failing simultaneously.
PSV	407	Ar	Gas supply relief valve	Fails open	No Hazard - not in use	Safe	----
PSV	407	Ar	Gas supply relief valve	Fails closed	No Hazard - not in use	Safe	----

**Pressure transmitters**

PT	1	N2	Luke condenser LN2 back pressure	Incorrect reading -low	No Hazard	Safe	Operational problem - PI-133-N2 provides redundant instrumentation
PT	1	N2	Luke condenser LN2 back pressure	Incorrect reading - high	No Hazard	Safe	Operational problem - PI-133-N2 provides redundant instrumentation
PT	11	Ar	Luke Ar vapor pressure	Incorrect reading -low	Luke vapor pressure hard to control	Safe	Operational problem - PI-12-Ar provides redundant instrumentation
PT	11	Ar	Luke Ar vapor pressure	Incorrect reading - high	Luke vapor pressure hard to control	Safe	Operational problem - PI-12-Ar provides redundant instrumentation
PT	15	V	LAr transfer line insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - increased LAr losses, PE-235-V provides redundant instrumentation
PT	15	V	LAr transfer line insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem, PE-235-V provides redundant instrumentation
PT	17	V	Bo dewar insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - possible high LAr boil-off leading to increased LN2 consumption or GAr venting thru PSV-377-Ar which ODH analysis indicates is OK
PT	17	V	Bo dewar insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	19	V	Luke Argon volume rough vacuum	Incorrect reading -low	Ion gauge PT-33-V could be damaged	Safe	Operational problem
PT	19	V	Luke Argon volume rough vacuum	Incorrect reading - high	Ion gauge PT-33-V won't turn on	Safe	Operational problem
PT	27	N2	Nitrogen transfer line pressure	Incorrect reading -low	Possible controls issues	Safe	Operational problem
PT	27	N2	Nitrogen transfer line pressure	Incorrect reading - high	Possible controls issues	Safe	Operational problem
PT	33	V	Luke Argon volume high vacuum	Incorrect reading -low	Argon volume vacuum worse than indicated	Safe	Operational problem - possible contamination issues if high vacuum is not achieved before fill
PT	33	V	Luke Argon volume high vacuum	Incorrect reading - high	Argon volume vacuum better than indicated	Safe	Operational problem - time may be wasted by unnecessary pumping
PT	51	N	LN2 dewar pressure transmitter	Incorrect reading -low	Possible controls issues	Safe	Operational problem
PT	51	N	LN2 dewar pressure transmitter	Incorrect reading - high	Possible controls issues	Safe	Operational problem
PT	68	V	Luke dewar insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - possible high LAr boil-off leading to increased LN2 consumption or GAr venting thru PSV-210-Ar which ODH analysis indicates is OK
PT	68	V	Luke dewar insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	69	V	Luke seal monitoring at vacuum pump	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - poor vacuum can lead to O2 diffusion thru o-ring seals

PT	69	V	Luke seal monitoring at vacuum pump	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	180	V	P-bar mole sieve filter dewar - filter insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - high LAr losses during transfer and high heat loads during regeneration
PT	180	V	P-bar mole sieve filter dewar - filter insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	181	V	P-bar mole sieve filter dewar - dewar insulating vacuum	Incorrect reading -low	Insulating vacuum worse than indicated	Safe	Operational problem - high LAr losses during transfer and high heat loads during regeneration
PT	181	V	P-bar mole sieve filter dewar - dewar insulating vacuum	Incorrect reading - high	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	185	V	Materials lock rough vacuum	Incorrect reading -low	Ion gauge PT-33-V could be damaged	Safe	Operational problem
PT	185	V	Materials lock rough vacuum	Incorrect reading - high	Ion gauge PT-33-V won't turn on	Safe	Operational problem
PT	186	V	Materials lock high vacuum	Incorrect reading -low	Vacuum worse than indicated	Safe	Operational problem - if not properly evacuated, contamination may be an issue
PT	186	V	Materials lock high vacuum	Incorrect reading - high	Vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	154	V	Pbar oxygen filtering dewar filter insulating vacuum	Incorrect reading -low	Insulating vacuum better than indicated	Safe	Operational problem - time could be spent investigating a non-existent problem
PT	154	V	Pbar oxygen filtering dewar filter insulating vacuum	Incorrect reading - high	Insulating vacuum worse than indicated	Safe	Operational problem - high LAr losses during transfer and high heat loads during regeneration
PT	320	Air	Shop Air Pressure Transmitter	Incorrect reading -low	Regulated air pressure higher than indicated	Safe	----
PT	320	Air	Shop Air Pressure Transmitter	Incorrect reading - high	Regulated air pressure lower than indicated	Safe	Possible operational problems if shop air is too low, PI-272-Air provides a redundant measurement
PT	323	Ar	Argon purge pressure transmitter	Incorrect reading -low	Regulated argon pressure higher than indicated	Safe	----
PT	323	Ar	Argon purge pressure transmitter	Incorrect reading - high	Regulated argon pressure lower than indicated	Safe	Possible operational problems if argon purge supply is too low, PI-275-Ar provides a redundant measurement
PT	373	Ar	Bo Ar vapor pressure	Incorrect reading -low	Luke vapor pressure hard to control	Safe	Operational problem - PI-363-Ar provides redundant instrumentation
PT	373	Ar	Bo Ar vapor pressure	Incorrect reading - high	Luke vapor pressure hard to control	Safe	Operational problem - PI-363-Ar provides redundant instrumentation
PT	374	Ar	Bo Argon volume rough vacuum	Incorrect reading -low	No Hazard	Safe	Operational problem
PT	374	Ar	Bo Argon volume rough vacuum	Incorrect reading - high	No Hazard	Safe	Operational problem
PT	382	V	Bo vacuum pump cart inlet full range pressure transmitter	Incorrect reading -low	Turbo may turn on at high pressure	Marginal	Turbo could be destroyed
PT	382	V	Bo vacuum pump cart inlet full range pressure transmitter	Incorrect reading - high	No Hazard	Safe	Operational problem - Turbo pump may not turn on
PT	385	V	Bo vacuum pump cart rough pump inlet pressure transmitter	Incorrect reading -low	No Hazard	Safe	Operational problem
PT	385	V	Bo vacuum pump cart rough pump inlet pressure transmitter	Incorrect reading - high	No Hazard	Safe	Operational problem

**Rupture disks**

RD	99	N	LN2 dewar rupture disk	Fails open	LN2 dewar blows down - No LN2 transfer	Safe	Operational problem - No LN2 will be supplied to GAR condensers
RD	99	N	LN2 dewar rupture disk	Fails closed	No hazard	Safe	SV-99-N provides dewar relief
RD	100	N	LN2 dewar rupture disk	Fails open	LN2 dewar blows down - No LN2 transfer	Safe	Operational problem - No LN2 will be supplied to GAR condensers
RD	100	N	LN2 dewar rupture disk	Fails closed	No hazard	Safe	SV-100-N provides dewar relief
RD	209	Ar	Pbar molecular sieve filter dewar inner vessel relief	Fails open	Spoils molecular sieve insulating vacuum	Safe	Increased losses during LAr transfer or increased heat load during filter regeneration
RD	209	Ar	Pbar molecular sieve filter dewar inner vessel relief	Fails closed	No Hazard	Safe	CVI-220-V provides relief at ~ 0 psig with its spring removed
RD	301	V	Pbar oxygen filtering dewar filter insulating volume pressure relief	Fails open	Spoils O2 filter insulating vacuum	Safe	Increased losses during LAr transfer or increased heat load during filter regeneration
RD	301	V	Pbar oxygen filtering dewar filter insulating volume pressure relief	Fails closed	No Hazard	Safe	Parallel plate relief PSV-344-V provides adequate relief
RD	302	V	Luke cryostat LAr volume pressure relief	Fails open	Cryostat blows down	Safe	Operational problem
RD	302	V	Luke cryostat LAr volume pressure relief	Fails closed	No Hazard	Safe	PSV-210-Ar provides adequate relief
RD	376	V	Bo cryostat LAr volume pressure relief	Fails open	Cryostat blows down	Safe	Operational problem

RD	376	V	Bo cryostat LAr volume pressure relief	Fails closed	No Hazard	Safe	PSV-377-Ar provides adequate relief
----	-----	---	--	--------------	-----------	------	-------------------------------------

**Pressure regulators**

RV	36	N	LN2 dewar pressure building regulator	Fails open	Excess N2 vapor is created	Safe	Operational problem - SV-99-N and SV-100-N will vent vapor
RV	36	N	LN2 dewar pressure building regulator	Fails closed	Can't build pressure	Safe	Operational problem - need pressure to transfer LN2 into PAB
RV	90	N	LN2 dewar pressure relieving regulator	Fails open	LN2 dewar blows down	Safe	Operational problem - need pressure to transfer LN2 into PAB
RV	90	N	LN2 dewar pressure relieving regulator	Fails closed	LN2 dewar above normal operating pressure	Safe	Operational problem, SV-99-N and SV-100-N will vent vapor

**Strainers**

S	91	N	LN2 dewar fill line strainer	Plugged up	LN2 dewar can't be filled	Safe	Operational problem
S	91	N	LN2 dewar fill line strainer	Does not filter	Debris from outside pass thru fill line	Safe	Operational problem, dirt can keep valves from sealing tight

**Relief valves**

SV	90	N	LN2 dewar fill line trapped volume relief	Fails open	LN2 vents into parking lot during fill	Safe	Operational problem
SV	90	N	LN2 dewar fill line trapped volume relief	Fails closed	Potential unrelieved trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
SV	90	V	LN2 dewar vacuum jacket relief	Fails open	Insulating vacuum spoils	Safe	Operational problem - SV-99-N and SV-100-N have adequate capacity
SV	90	V	LN2 dewar vacuum jacket relief	Fails closed	Vacuum space is not relieved	Marginal	A parallel plate relief without spring loading is unlikely to fail closed
SV	96	N	LN2 dewar pressure building loop trapped volume relief	Fails open	LN2 vents into parking lot	Safe	Operational problem - loop can be isolated to fix relief valve
SV	96	N	LN2 dewar pressure building loop trapped volume relief	Fails closed	Potential unrelieved trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
SV	97	N	LN2 dewar pressure building loop trapped volume relief	Fails open	LN2 vents into parking lot	Safe	Operational problem - loop can be isolated to fix relief valve
SV	97	N	LN2 dewar pressure building loop trapped volume relief	Fails closed	Potential unrelieved trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
SV	98	N	LN2 dewar pressure building loop trapped volume relief	Fails open	LN2 vents into parking lot	Safe	Operational problem - loop can be isolated to fix relief valve
SV	98	N	LN2 dewar pressure building loop trapped volume relief	Fails closed	Potential unrelieved trapped volume	Marginal	Low probability of a quality Circle-Seal relief valve failing completely shut. As pressure in the trapped volume exceeded the relief valve set point, the probability of a stuck relief valve opening would increase.
SV	99	N	LN2 dewar relief valve	Fails open	LN2 dewar blows down	Safe	Operational problem - need pressure to transfer LN2 into PAB
SV	99	N	LN2 dewar relief valve	Fails closed	RD-99-N will vent dewar	Safe	Operational problem - rupture disk would have to be replaced after failure
SV	100	N	LN2 dewar relief valve	Fails open	LN2 dewar blows down	Safe	Operational problem - need pressure to transfer LN2 into PAB
SV	100	N	LN2 dewar relief valve	Fails closed	RD-100-N will vent dewar	Safe	Operational problem - rupture disk would have to be replaced after failure

**Temperature elements**

TE	6	N2	LN2 transfer line cool down temperature (control)	Incorrect reading -low	Cool down falsely indicated complete	Safe	Operational problem - could cause controls issues
TE	6	N2	LN2 transfer line cool down temperature (control)	Incorrect reading - high	Cool down falsely indicated incomplete	Safe	Operational problem - could cause controls issues, wasted LN2
TE	7	Ar	O2 filter internal temperature (hard wired interlock)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage filter material
TE	7	Ar	O2 filter internal temperature ((hard wired interlock)	Incorrect reading - high	Filter regeneration heater prematurely shuts off	Safe	TE-54-Ar provides redundant instrumentation for PLC control
TE	23	Ar	Luke pressure building heater internal temperature (read out)	Incorrect reading -low	PLC does not shut off heater	Safe	If hard wired interlock also fails, heater could overheat and damage silver soldered joints
TE	23	Ar	Luke pressure building heater internal temperature (read out)	Incorrect reading - high	Pressure building heater prematurely shuts off	Safe	Operational problem - controls issue could arise
TE	24	Ar	Luke pressure building heater internal temperature ((hard wired interlock)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage silver soldered joints
TE	24	Ar	Luke pressure building heater internal temperature ((hard wired interlock)	Incorrect reading - high	Pressure building heater prematurely shuts off	Safe	Operational problem - controls issue could arise

TE	25	Ar	Bo pressure building heater internal temperature (read out)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage silver soldered joints
TE	25	Ar	Bo pressure building heater internal temperature (read out)	Incorrect reading - high	Pressure building heater prematurely shuts off	Safe	Operational problem - controls issue could arise
TE	26	Ar	Bo pressure building heater internal temperature ((hard wired interlock)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage silver soldered joints
TE	26	Ar	Bo pressure building heater internal temperature ((hard wired interlock)	Incorrect reading - high	Pressure building heater prematurely shuts off	Safe	Operational problem - controls issue could arise
TE	54	Ar	O2 filter internal temperature (control)	Incorrect reading -low	Filter regeneration temperature too high	Safe	If hardwired interlock also fails, heater could overheat and damage filter material
TE	54	Ar	O2 filter internal temperature (control)	Incorrect reading - high	Filter regeneration temperature too low	Safe	Operational problem - poorly regenerated filter could result
TE	56	Ar	O2 filter regeneration gas pre-heater temperature (control)	Incorrect reading -low	Filter regeneration gas temperature too high	Safe	If hardwired interlock also fails, heater could overheat
TE	56	Ar	O2 filter regeneration gas pre-heater temperature (control)	Incorrect reading - high	Filter regeneration gas temperature too low	Safe	Operational problem - poorly regenerated filter could result
TE	57	Ar	O2 filter regeneration gas pre-heater temperature ((hard wired interlock)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage filter material
TE	57	Ar	O2 filter regeneration gas pre-heater temperature ((hard wired interlock)	Incorrect reading - high	Filter regeneration gas heater prematurely shuts off	Safe	TE-56-Ar provides redundant instrumentation for PLC control
TE	73	HAr	Luke Vapor pump filter regeneration heater (control)	Incorrect reading -low	Filter regeneration temperature too high	Safe	If hardwired interlock also fails, heater could overheat and damage filter material
TE	73	HAr	Luke Vapor pump filter regeneration heater (control)	Incorrect reading - high	Filter regeneration temperature too low	Safe	Operational problem - poorly regenerated filter could result
TE	74	HAr	Luke Vapor pump filter regeneration heater (hard wired interlock)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage filter material
TE	74	HAr	Luke Vapor pump filter regeneration heater (hard wired interlock)	Incorrect reading - high	Filter regeneration heater prematurely shuts off	Safe	TE-73-HAr provides redundant instrumentation for PLC control
TE	76	Ar	Luke Vapor pump "cup" heater (control)	Incorrect reading -low	Vapor producing heater overheats	Safe	If hardwired interlock also fails, heater could overheat and damage silver soldered joints
TE	76	Ar	Luke Vapor pump "cup" heater (control)	Incorrect reading - high	PLC prematurely shuts off heater	Safe	Operational problem - need properly functioning heater to make GAR to push LAr out of pump
TE	77	Ar	Luke Vapor pump "cup" heater (hard wired interlock)	Incorrect reading -low	Interlock does not protect heater	Safe	If PLC controls fails, heater could overheat and damage silver soldered joints
TE	77	Ar	Luke Vapor pump "cup" heater (hard wired interlock)	Incorrect reading - high	Heater prematurely shuts off	Safe	TE-76-HAr provides redundant instrumentation for PLC control
TE	81	HAr	Luke Vapor pump filter bed (ID)	Incorrect reading -low	No Hazard	Safe	Operational problem - poorly regenerated filter could result
TE	81	HAr	Luke Vapor pump filter bed (ID)	Incorrect reading - high	No Hazard	Safe	Operational problem - poorly regenerated filter could result
TE	82	HAr	Luke Vapor pump filter bed (OD)	Incorrect reading -low	No Hazard	Safe	Operational problem - poorly regenerated filter could result
TE	82	HAr	Luke Vapor pump filter bed (OD)	Incorrect reading - high	No Hazard	Safe	Operational problem - poorly regenerated filter could result
TE	83	HAr	Luke Vapor pump filter bed (middle)	Incorrect reading -low	No Hazard	Safe	Operational problem - poorly regenerated filter could result
TE	83	HAr	Luke Vapor pump filter bed (middle)	Incorrect reading - high	No Hazard	Safe	Operational problem - poorly regenerated filter could result
TE	214	Ar	Molecular sieve regeneration temperature (hard wired interlock)	Incorrect reading -low	No Hazard	Safe	If PLC controls fails, heater could overheat and damage filter material
TE	214	Ar	Molecular sieve regeneration temperature (hard wired interlock)	Incorrect reading - high	Filter regeneration heater prematurely shuts off	Safe	TE-216-Ar provides redundant instrumentation for PLC control
TE	216	Ar	Molecular sieve regeneration temperature (controls)	Incorrect reading -low	Filter regeneration temperature too high	Safe	If hardwired interlock also fails, heater could overheat and damage filter material
TE	216	Ar	Molecular sieve regeneration temperature (controls)	Incorrect reading - high	Filter regeneration temperature too low	Safe	Operational problem - poorly regenerated filter could result
TE	324	Ar	Material lock elevator temperature probe	Incorrect reading -low	No Hazard	Safe	Operational problem - wrong material test temperature
TE	324	Ar	Material lock elevator temperature probe	Incorrect reading - high	No Hazard	Safe	Operational problem - wrong material test temperature
TE	410	Air	PAB high bay ambient air temperature	Incorrect reading -low	No Hazard	Safe	Operational problem - wrong ambient temperature
TE	410	Air	PAB high bay ambient air temperature	Incorrect reading - high	No Hazard	Safe	Operational problem - wrong ambient temperature
TE	411	CS	Luke top flange temperature	Incorrect reading -low	No Hazard	Safe	Operational problem - wrong flange temperature
TE	411	CS	Luke top flange temperature	Incorrect reading - high	No Hazard	Safe	Operational problem - wrong flange temperature



Component FLARE Material Test Station  
and TPC cryostat \_\_\_\_\_  
Location PAB \_\_\_\_\_  
Date 4/10/08 \_\_\_\_\_  
By Terry Tope \_\_\_\_\_

**3.2 - WHAT-IF WORKSHEET**

WHAT-IF	CONSEQUENCE/HAZARD	CONCLUSION/RECOMMENDATIONS
Loss of liquid nitrogen	Argon boil off will vent thru vent valve or relief valve and cryostat pressure control is lost.	Safe condition. Operational impact only – need a closed system for material contamination tests.
Loss of insulating vacuums	System frosts over. Higher heat load to LN2 and LAr circuits. Potential for relief valves to open.  May cause high consumption of liquid nitrogen.	Safe condition. System is protected with relief valves that vent outdoors.  Safe condition. Operational impact.
Loss of instrumentation	May cause system instability with respect to cryostat pressure control or regeneration heater control.	Safe condition. Operational impact.
Power outage occurs at PAB	All control and instrumentation fails.	Safe condition. Operational impact – Historical values no longer recorded, no pressure control, relief valves vent.
Leaking stem packing on a cryo valve	Gas will vent into room.	Safe condition (see ODH analysis).
Transfer line inner lines rupture, weld cracks, or silver solder joint breaks	Loss of insulating vacuum and pressurization of the vacuum space.	Safe condition. Gas will vent into room thru vacuum reliefs into room (see ODH analysis).
Weld cracks, bellows break on the vacuum circuit.	Air will fill the vacuum space, thus creating a higher heat load to the cryo circuits.	Safe condition. System is protected with relief valves. May cause long cool down times for LN2 circuit or zero delivery condition.

<p>Liquid nitrogen dewar is pressurized to MAWP and all valves that would normally keep the transfer line connected to a vent are closed.</p>	<p>Piping pressurized to dewar MAWP.</p> <p>High LN2 delivery pressure may make it hard to control pressure in Luke using the condenser.</p>	<p>Safe condition. MAWP = 75 psig for LN2 dewar. The sizing calculations for the dewar reliefs prove that this pressure cannot be exceeded. All of the components of the transfer line have pressure ratings greater than 75 psig.</p> <p>Safe condition. Operational problem.</p>
<p>PLC failure</p>	<p>Pressure control and heater control lost.</p>	<p>Safe condition. Operational impact. LAr will vent thru relief valves.</p>
<p>A fire in PAB</p>	<p>Fire detectors go into alarm. Sprinklers open in high bay. Fire Department dispatched.</p> <p>Likely equipment damage.</p> <p>Fire or water from sprinklers could cause significant damage to controls hardware, wiring, and instrumentation.</p> <p>Superinsulation on piping and vessels could be damaged.</p> <p>Heat input into cryogenic liquids builds pressure in piping and cryostat.</p> <p>Insulating vacuums may spoil if o-rings are subjected to intense heat.</p>	<p>Safe condition. Operational problem - Control system not required for system safety but required for operation.</p> <p>Safe condition. Operational problem - Heat leaks during normal operation would be unacceptable if radiation blankets are damaged.</p> <p>Safe condition. Pressure vessels and piping protected by relief valves (see relief calculations and FMEA). Relief valves vent outside.</p> <p>Safe condition. System is protected with relief valves that vent outdoors. Operational problem - Heat leaks during normal operation would be unacceptable if insulating vacuums are spoiled.</p>

### **3.5a1 - ODH Analysis of the Proton Assembly Building for the FLARE Materials Test Station and TPC Cryostats**

#### **Introduction**

The Liquid Argon TPC R&D effort also known as FLARE has fabricated a cryogenic system inside the Proton Assembly Building (PAB). The system is designed to quantify the contamination effect of various materials on ultra high purity liquid argon and test a small TPC wire chamber.

***In addition to the Liquid Argon TPC R&D efforts at PAB (“Bo” and “Luke”), a third liquid argon cryostat known as T962 will be present at PAB for a few months of commissioning this summer before it is moved into the MINOS Hall.***

The cryogenic safety documentation for T962 can be found at the following location:

<http://projects-docdb.fnal.gov/cgi-bin/ShowDocument?docid=287>

The ODH analysis for T962 combines the fatality rate of  $4.57 \times 10^{-9}$  fatalities per hour computed in this document with its own contributions to reach an overall fatality rate of  $8.90 \times 10^{-9}$  fatalities per hour for the PAB high bay area. Thus the PAB high bay area remains ODH class zero with the addition of the T962 cryostat.

The T962 ODH analysis can be found here:

<http://projects-docdb.fnal.gov/cgi-bin/RetrieveFile?docid=287&version=7&filename=t962-pab-odh.pdf>

#### **Description of the System**

The cryogenic system contains both liquid nitrogen and liquid argon. Liquid nitrogen is supplied by an 1875 gallon dewar located outside PAB. The liquid nitrogen flows into PAB thru a half inch stainless steel tube that is vacuum jacketed by 1.5 inch SCH 10 pipe stainless steel pipe. The liquid nitrogen is used in a condenser that liquefies argon boil off so that the argon cryostat can remain a closed system. The nitrogen gas is then vented outdoors after passing thru a heat exchanger. The nitrogen circuit also contains a cool down solenoid valve which directs the nitrogen flow directly thru the heat exchanger and then outside. Nitrogen circuit trapped volume reliefs vent outside PAB.

Liquid argon is supplied by up to four 160 liter high pressure (350 psig relief setpoint) dewars that are supplied by the Fermilab stock room. These dewars

are used to fill two 250 liter cryostats. The cryostat known as “Luke” contains the materials test station while the cryostat known as “Bo” contains the TPC wire chamber. Typically four dewars would not be required to fill one cryostat. But there are significant losses due to flashing and system cool down. It has also been our experience that it is difficult to obtain completely full dewars from the stock room. Operational experience with “Luke” indicates that 3 dewars are required to fill one cryostat. The fourth argon spigot has been replaced by a pressure indicator. However, the ODH analysis assumes 4 supply dewars are connected. The argon dewars are plumbed to a manifold to create a common argon source. The argon flows thru a series of valves and filters before it reaches the cryostat. All relief devices on the argon circuit are vented outdoors except for the cryostat rupture disk which is a secondary relief device.

**Quantity of Cryogens, Building Volume, and Minimum Oxygen Concentrations**

The PAB high bay has a volume of 138,425 cubic feet. The amount of warm gas contained in the 1875 gallon liquid nitrogen dewar is calculated as follows:

$$1,875 \text{ gal} \times \frac{\text{ft}^3}{7.481 \text{ gal}} \times \frac{50.4 \text{ lb}}{\text{ft}^3} \times \frac{\text{ft}^3}{0.07247 \text{ lb}} = 174,307 \text{ ft}^3 \text{ where } 50.4 \text{ lb/ft}^3 \text{ is the density}$$

of liquid nitrogen and 0.07247 lb/ft<sup>3</sup> is the density of nitrogen gas at standard conditions.

Thus there is enough nitrogen contained in the supply dewar to fully inert the PAB high bay enclosure.

The equivalent amount of warm argon gas contained in four stock room dewars

$$\text{is } 4 \times 160 \text{ liters} \times \frac{\text{ft}^3}{28.32 \text{ liters}} \times \frac{87 \text{ lb}}{\text{ft}^3} \times \frac{\text{ft}^3}{0.1034 \text{ lb}} = 19,015 \text{ ft}^3.$$

The equivalent amount of warm argon gas in the 250 liter cryostat is

$$250 \text{ liters} \times \frac{\text{ft}^3}{28.32 \text{ liters}} \times \frac{87 \text{ lb}}{\text{ft}^3} \times \frac{\text{ft}^3}{0.1034 \text{ lb}} = 7,428 \text{ ft}^3.$$

If the four stockroom dewars are instantly vented into PAB, the minimum O2 concentration reached is

$$138,425 \text{ ft}_{\text{air}}^3 - 19,015 \text{ ft}_{\text{argon}}^3 = 119,410 \text{ ft}_{\text{air}}^3$$

$$119,410 \text{ ft}_{\text{air}}^3 \times 0.21 = 25,076 \text{ ft}_{\text{oxygen}}^3$$

$$\frac{25,076 \text{ ft}^3_{\text{oxygen}}}{138,425 \text{ ft}^3_{\text{air}}} \times 100 = 18.1\%_{\text{oxygen}}$$

If the four stockroom dewars are instantly vented into PAB along with the two 250 liter cryostats, the minimum O2 concentration reached is

$$138,425 \text{ ft}^3_{\text{air}} - (19,015 \text{ ft}^3_{\text{argon}} + 2 \times 7,428 \text{ ft}^3_{\text{argon}}) = 104,554 \text{ ft}^3_{\text{air}}$$

$$104,554 \text{ ft}^3_{\text{air}} \times 0.21 = 21,956 \text{ ft}^3_{\text{oxygen}}$$

$$\frac{21,956 \text{ ft}^3_{\text{oxygen}}}{138,425 \text{ ft}^3_{\text{air}}} \times 100 = 15.9\%_{\text{oxygen}}$$

Argon is heavier than air so it cannot be assumed to perfectly mix with air to create the above minimum oxygen concentrations.

The PAB high bay floor is about 100 feet by 49 feet. If the argon is assumed to spread out across the floor and remain separate from the air, the thickness of the stratified argon layer for four stock room dewars instantly dumped into the room is

$$\frac{19,015 \text{ ft}^3}{100 \text{ ft} \times 49 \text{ ft}} = 3.9 \text{ ft}$$

If the two 250 liter cryostats are dumped into the room along with the four stock room dewars the argon layer depth is

$$\frac{19,015 \text{ ft}^3 + 2 \times 7,428 \text{ ft}^3}{100 \text{ ft} \times 49 \text{ ft}} = 6.9 \text{ ft}$$

To keep the analysis simple, it is assumed that the entire liquid argon inventory is vented during an ODH event.

### **Ventilation System and ODH monitors**

PAB is equipped with 3 ceiling exhaust fans. FESS has determined the capacity of each fan to be at least 2000 SCFM Air. All three ceiling fans will turn on in the event of an ODH alarm. They are also wired in a manner that allows each fan to be turned on manually. In addition to the ceiling fans, a dedicated ODH fan has been installed in the cryogenic area. This fan pulls the cold dense gas from the floor and pushes it thru a duct which exhausts outside PAB. Together all four fans yield a volume change in the high bay area every 17 minutes. Only the dedicated ODH fan is included in the ODH analysis. At the end of this section

the details of the dedicated ODH fan and ODH hardware layout are documented. Figure 3.5a.1 shows the locations of ODH heads, horns, and fans.

### **ODH Event Leak rates for Nitrogen Circuit**

#### **Severed Line**

Several leak rates are postulated for the nitrogen circuit. The most severe of these considers the liquid nitrogen supply line to be severed just inside PAB. The flow rate at this point is then a function of the resistance offered by the piping outside PAB and the pressure of the dewar. The dewar pressure is taken to be the maximum allowable pressure under fire conditions which is 121% of the dewar MAWP of 75 psig or

$$1.21(75 + 15) - 15 = 93.9 \text{ psig.}$$

The flow rate thru the LN2 piping outside PAB is calculated using the following equation from Crane's Technical Paper 410 for discharge of liquid

$$W = 1891d^2 \sqrt{\frac{\Delta P \rho}{K}}$$

where

$W =$  rate of liquid nitrogen flow in pounds per hour.

$d =$  internal diameter of pipe,  $= 0.5 - 2 \times 0.035 = 0.43$  inches.

$\Delta P =$  differential pressure, 93.9 psi.

$\rho =$  density of liquid nitrogen saturated at 93.9 psig, 43.19 lb/ft<sup>3</sup>.

$K =$  resistance coefficient, sum of  $K_{pipe} + K_{elbow} + K_{valve} + K_{exit}$

$K_{pipe} =$  resistance of straight pipe outside PAB,  $K_{pipe} = f \frac{L}{D}$  where

$f =$  friction factor determined from pipe size and Reynolds number, = 0.029 (page A-25 of Crane 410)

$L =$  length of pipe outside PAB, 227 inches.

$D =$  internal diameter of pipe, 0.43 inches.

$K_{elbow}$  = resistance of a standard elbow which =  $30 \times f_T$  where  $f_T$  is the friction factor in the zone of complete turbulence for 0.43 inch internal diameter pipe which is 0.029. Piping outside PAB has 2 elbows.

$K_{exit}$  = resistance of a sharp edged pipe exit for the severed pipe, = 1.0

$K_{valve}$  = resistance of the Cryolab isolation valve at the dewar exit,

$$K_{valve} = \frac{894d^4}{C_v^2} \text{ where}$$

$C_v$  = flow coefficient for valve,  $C_v = 12$  for Cryolab valve

$R_e$  = Reynolds number, ratio of inertial and viscous forces

$$R_e = 6.31 \frac{W}{d\mu} \text{ where}$$

$\mu$  = absolute viscosity of LN2 saturated at 93.9 psig, = 0.088 centipoise

The above equations yield

$$K = 0.029 \frac{227}{0.43} + 2 \times 30 \times 0.029 + \frac{894(0.43)^4}{12^2} + 1.0 = 18.26$$

$$R_e = 6.31 \frac{4889}{(0.43)0.088} = 815264$$

$W = 1891(0.43)^2 \sqrt{\frac{93.9(43.19)}{18.26}} = 5211 \frac{lb}{hr}$  which converts to SCFM in the following manner

$$5211 \frac{lb}{hr} \times \frac{ft^3}{0.07247lb} \times \frac{hr}{60min} = 1198 \frac{ft^3}{min}$$

Thus the maximum flow the liquid nitrogen dewar can supply into PAB is equivalent to 1198 SCFM of nitrogen gas.

### Valve and Instrument Leakage

For leakage from valves and instruments on the LN2 supply line, the leak was modeled as an orifice whose diameter is 25% of the pipe diameter. It is unlikely that valve bodies or instruments will fail in a manner that completely opens up the

supply piping. Before use, all piping will be pressure tested and helium leak checked.

The leak rate is calculated using the following equation from Crane Technical Paper 410 for liquid flow thru nozzles and orifices

$$W = 1891d_1^2 C \sqrt{\Delta P \rho} \text{ where}$$

all variables except C and  $d_1$  are previously defined.

$d_1$  = orifice diameter, 25% of 0.5 inch nominal tube diameter = 0.125 inch.

C = flow coefficient for nozzles and orifices (Crane 410 Page A-20), = 0.60 for this case.

The maximum flow of nitrogen thru such a leak is

$$W = 1891(0.125^2)0.60\sqrt{(93.9)43.19} = 1129 \frac{lb}{hr} \text{ which converts to}$$

$$1129 \frac{lb}{hr} \times \frac{ft^3}{0.07247lb} \times \frac{hr}{60min} = 260 \frac{ft^3}{min} \text{ of warm atmospheric N2 gas.}$$

The factor C was found from the plot on page A-20 using

$$R_e = 6.31 \frac{1129}{(0.125)0.088} = 647635 \text{ and } \beta = \frac{d_1}{d_2} = \frac{0.125}{0.43} = 0.29 \text{ where } d_2 \text{ is the actual ID}$$

of the LN2 supply pipe.

Thus on the liquid nitrogen supply line, the leak rate for components is estimated as 260 SCFM which is 23% of the total mass flow available inside PAB.

### **ODH Event Leak rates for Argon Circuit**

#### **Severed Line**

The four argon supply dewars are each equipped with a liquid isolation valve with a  $C_v$  of 1.08. Thus the worst case leak is a severed line just after all four dewars are tied together. From Crane 410, the flow rate out of one dewar can be calculated as

$$Q = C_v \sqrt{\Delta P \frac{62.4}{\rho}} \text{ where}$$

- $Q =$  rate of liquid argon flow in gallons per minute.
- $C_v =$  flow coefficient for valve,  $C_v = 1.08$  for dewar liquid isolation valve according to Airgas.
- $\Delta P =$  differential pressure, 350 psi based on stockroom supplied high pressure liquid argon dewars with reliefs set at 350 psig.
- $\rho =$  density of liquid argon saturated at 350 psig, 63.37 lb/ft<sup>3</sup>.

The maximum liquid flowrate out of one stock room dewar is found to be

$$Q = 1.08 \sqrt{350 \frac{62.4}{63.37}} = 20.05 \frac{\text{gal}}{\text{min}}$$
 which converts to

$$20.05 \frac{\text{gal}}{\text{min}} \times \frac{1 \text{ft}^3}{7.48 \text{gal}} \times \frac{63.37 \text{lb}}{\text{ft}^3} \times \frac{\text{ft}^3}{0.1034 \text{lb}} = 1643 \frac{\text{ft}^3}{\text{min}}$$
 where 0.1034 lb/ft<sup>3</sup> is the

density of argon gas at standard conditions. Thus four dewars could

supply 6572 SFCM of warm argon gas. This is conservative because the hoses and tubing connecting the four dewars would provide additional restriction that would lower this flow rate.

### LAr Supply Dewar Relief Valves

The relief valves on the LAr supply dewars could prematurely open. The typical relief valve on the Airgas supplied dewars is a Generant LCV-250B-K-350 which according to the manufacturer has a maximum flow of 81.4 SCFM Nitrogen at 120% of its 350 psig set point. This converts to lb/hr as

$$\frac{81.4 \text{ft}^3}{\text{min}} \times \frac{60 \text{min}}{\text{hr}} \times \frac{0.07247 \text{lb}}{\text{ft}^3} = 354 \frac{\text{lb}}{\text{hr}}$$

This can be converted to SCFM argon using the method outlined in ASME Section VIII Appendix 11 Division 1 entitled "Capacity Conversions for Safety Relief Valves."

For any gas or vapor,

$$W = CKAP \sqrt{\frac{M}{T}}$$
 where

$W =$  rated capacity in lb/hr, 354 lb/hr for nitrogen, argon value to be solved for.

$C =$  constant for gas or vapor which is a function of the ratio of specific heats,  $C = 356$  for nitrogen and 378 for argon.

$KAP =$  constant for the relief valve.

$M =$  molecular weight, 28.02 for nitrogen and 39.9 for argon.

$T =$  absolute temperature in Rankin, choose 530 °R.

For the nitrogen rating,

$$KAP = \frac{W}{C\sqrt{\frac{M}{T}}} = \frac{354}{356\sqrt{\frac{28.02}{530}}} = 4.325.$$

The argon mass flow rate is then

$$W = (356)(4.325)\sqrt{\frac{39.9}{530}} = 422.5 \frac{lb}{hr} \text{ which converts to}$$

$$422.5 \frac{lb}{hr} \times \frac{ft^3}{0.1034 lb} \times \frac{hr}{60 min} = 68.1 \frac{ft^3}{min}.$$

Thus the maximum rate at which the supply dewar can relieve itself is 68.1 SCFM.

MV-204-Ar, MV-218-Ar, MV-365-V, and MV-366-V

MV-204-Ar is an isolation valve where a vacuum pump can be connected to pump out the argon source manifold. If this valve with a  $C_v$  of 1.2 is left wide open while the circuit is pressurized, the leak rate is found to be

$$Q = C_v \sqrt{\Delta P \frac{62.4}{\rho}} = 1.20 \sqrt{350 \frac{62.4}{63.37}} = 22.28 \frac{gal}{min}.$$

$$\text{flow rate of } 22.28 \frac{gal}{min} \times \frac{1 ft^3}{7.48 gal} \times \frac{63.37 lb}{ft^3} \times \frac{ft^3}{0.1034 lb} = 1825 \frac{ft^3}{min}.$$

This leak rate is also used for MV-218-Ar, MV-365-V, and MV-366-V which are identical to MV-204-Ar and is conservative because these three valves are separated from the argon source by significant piping restrictions.

### Valve and Instrument Leakage for Components Upstream of the Cryostat

For leakage from valves and instruments on the LAr transfer line, the leak is modeled as an orifice whose diameter is 0.125 inches which is 33% of the nominal 3/8 inch tube diameter used to construct most of the LAr piping. It is unlikely that valve bodies or instruments will fail in a manner that completely opens up the supply piping. Most valves on the argon circuit are high quality stainless steel construction with metal bellows seal to atmosphere.

The leak rate is calculated using the following equation from Crane Technical Paper 410 for liquid flow thru nozzles and orifices

$$W = 1891d_1^2 C \sqrt{\Delta P \rho} \text{ where}$$

$d_1$  = orifice diameter, 33% of 0.375 inch nominal tube diameter = 0.125 inch.

$C$  = flow coefficient for nozzles and orifices (Page A-20 from Crane 410), = 0.60 for this case.

$\mu$  = absolute viscosity of liquid argon saturated at 350 psig, 0.0751 centipoise.

The maximum flow of argon thru such a leak is

$$W = 1891(0.125^2)0.61\sqrt{(350)63.37} = 2684 \frac{lb}{hr} \text{ which converts to}$$

$$2684 \frac{lb}{hr} \times \frac{ft^3}{0.1034lb} \times \frac{hr}{60min} = 433 \frac{ft^3}{min} \text{ of warm atmospheric argon gas.}$$

The factor  $C$  was found from the plot on Crane 410 page A-20 using

$$R_e = 6.31 \frac{2684}{(0.125)0.0751} = 1804105 \text{ and } \beta = \frac{d_1}{d_2} = \frac{0.125}{0.305} = 0.41 \text{ where } d_2 \text{ is the actual}$$

ID of the LAr supply pipe (3/8 inch OD – 2 x 0.035 inch wall = 0.305 inch).

Thus on the liquid argon transfer line, the leak rate for components upstream of the cryostat is estimated as 433 SCFM.

### Valve and Instrument Leakage for Components Attached to the Cryostat

From the relief valve calculations, the maximum mass flow rate into the cryostat was found to be 1437 pounds per hour. This equates to warm argon gas flowrate of 232 SCFM using the following conversion

$$1437 \frac{lb}{hr} \times \frac{ft^3}{0.1034lb} \times \frac{hr}{60min} = 232 \frac{ft^3}{min}. \text{ This value was used as the leak rate for all}$$

components attached to the cryostat.

### **ODH Risk Assessment**

As explained in Section 5064 of Fermilab's ES&H Manual, the ODH classification of an enclosure is determined by calculating the ODH fatality rate,  $\phi$ . It is defined as:

$$\phi = \sum_{i=1}^n P_i F_i \text{ where}$$

$P_i$  = the expected rate of the  $i^{th}$  failure per hour

$F_i$  = the fatality factor for the  $i^{th}$  event.

The summation is taken over all events, which may cause oxygen deficiency and result in fatality. Fatality factors are calculated based on the maximum spill rate, the rate of ventilation, and the size of the PAB enclosure. Events that could potentially lead to an ODH condition were identified and tabulated for the PAB high bay area in the tables at the end of this section. A single event probability was estimated in most cases using Table 2 "NRC Equipment Failure Rate" on page 5064TA-4 of Fermilab's ES&H Manual. In some cases, a failure probability was based on Fermilab experience since an applicable number was not readily available in the NRC table. Based on the number of components present in the PAB enclosure, a total event probability was calculated. The lowest oxygen concentration (as time approaches infinity) was computed by applying equation 4 on page 5064TA-8 of Fermilab's ES&H Manual:

$$C_r(t) = 0.21 \left\{ 1 - \frac{R}{Q} \left[ 1 - e^{\left( \frac{-Qt}{V} \right)} \right] \right\} = 0.21 \left\{ 1 - \frac{R}{Q} \right\} \text{ as } t \Rightarrow \infty \text{ where}$$

$R$  = spill rate into enclosure, SCFM.

$Q$  = enclosure ventilation rate, CFM.

This equation assumes complete mixing of the gases with the ventilation fans drawing contaminated atmosphere from the confined volume. A fatality factor was then determined from Figure 1 on page 5064TA-2 of Fermilab's ES&H Manual. By multiplying this fatality factor by the total event probability, an ODH rate in fatalities/hour was calculated. The sum of all the ODH rates gives the total ODH rate for the enclosure.

This ODH analysis relies on the use of mechanical ventilation to remove the inert gas from PAB. Although this ventilation reduces the overall ODH risk, it is also subject to failure. Therefore, the probability that these failures will occur and compromise the ventilation system needs to be factored into the overall risk assessment. There are two main areas of concern. One is the failure of a ventilation fan motor to turn on or the fan louvers to open. The second is an unplanned electrical power outage during cryogenic operation. The total probability of any one of these events occurring is simply the sum of their probabilities. The ODH rate calculation table includes two cases. The first case is for the ventilation system running. The second case considers the loss of the ventilation system. In that case the failure rate of the forced ventilation is factored into the calculation. The probability of a component event failure and a ventilation failure occurring is the product of their failure probabilities since they are independent events.

The probability of ventilation failure was determined as follows. The probability of a power outage is  $1 \times 10^{-4}$  / hr based on Fermilab equipment failure rates. The probability of an electric motor not starting is  $3 \times 10^{-4}$  /  $D$  based on NRC data. To be conservative, the demand ( $D$ ) is taken to be once an hour such that  $D = 1$ . This probability is used for both the fan motor starting and the actuated louvers opening. Thus the probability of a ventilation failure is  $1 \times 10^{-4} + 2 \times 3 \times 10^{-4} = 7 \times 10^{-4}$  / hr. This value is used in the table that considers a ventilation failure. The fan availability rate is then  $1 - 7 \times 10^{-4}$  or 0.9993. This value is used in the table that considers the ventilation to be running.

The probability of a valve such as MV-204-Ar being left wide open was taken to be  $(0.1 / D)$  which is much greater than the value of  $(3 \times 10^{-3} / D)$  described as a general human error of commission in Table 3 of FESHM 5064TA. If the valve is assumed to be cycled once per day, then the probability of an error is  $(0.1 / D) \times (D / \text{hr}) = (0.1 / 1) \times (1/24 \text{ hr}) = 4.17 \times 10^{-3}$  per hour.

The probability of the operator ignoring high pressure liquid or gas audibly venting into the room is also taken to be  $(0.1 / D)$ . If the valve is again assumed to be cycled once per day, the probability of the operator ignoring the error is  $4.17 \times 10^{-3}$  per hour.

These two tasks are independent events such that the total probability of a valve staying in the wide open position and its venting into the room being ignored is the product of the two task probabilities or  $4.17 \times 10^{-3} \times 4.17 \times 10^{-3} = 1.74 \times 10^{-5}$  per hour.

### **ODH Results**

Table 1 finds the ODH fatality rate to be  $1.19 \times 10^{-9}$  which is less than  $10^{-7}$  such that with ventilation running the PAB high bay enclosure is ODH class zero.

Table 2 finds the ODH fatality rate to be  $4.57 \times 10^{-9}$  which is less than  $10^{-7}$  such that when ventilation failure is considered the PAB high bay enclosure is ODH class zero.

## ODH Hardware Layout and Dedicated ODH Fan Details

Figure 3.5a.1 shows the ODH hardware layout for PAB. Four ODH heads mounted 6 inches from the floor surround the cryogenic area. One alarm horn is mounted inside the high bay area. The second alarm horn is mounted in the room adjacent to the high bay.

The dedicated ODH fan is a GreenHeck SWB backward inclined centrifugal utility fan rated at 2000 SCFM air at 4 inches of water static pressure. The fan pushes the cold vapor from a spill thru a duct that includes two elbows, a 15 foot vertical rise, a damper, and two enlargements.

To verify the fan installation is adequate, the pressure drop thru the duct is estimated.

Equation 3-20 shown below from Crane Technical Paper 410 was used to calculate the pressure drop due to the flow of gas thru the duct

$$W = 1891Yd^2 \sqrt{\frac{\Delta P}{K\bar{V}_1}} \Rightarrow \Delta P = \left( \frac{W}{1891Yd^2} \right)^2 K\bar{V}_1$$

where

$W$  = rate of flow in lbs per hour. ODH analysis is based on a 2000 SCFM flow of either nitrogen or argon. The nitrogen mass flow rate is then

$$2,000 \frac{ft^3}{min} N_2 \times \frac{60 min}{hr} \times 0.07247 \frac{lb}{ft^3} = 8,696 \frac{lb}{hr} N_2 \text{ and the argon mass}$$

flow rate is

$$2,000 \frac{ft^3}{min} Ar \times \frac{60 min}{hr} \times 0.1034 \frac{lb}{ft^3} = 12,408 \frac{lb}{hr} Ar.$$

$Y$  = net expansion factor for compressible flow, 1.0 for the small pressure drops in this duct flow analysis.

$d$  = internal diameter of duct, inches. Duct is square, so an equivalent diameter is calculated as

$$d = 4 \frac{\text{cross sectional flow area}}{\text{wetted perimeter}} = 4 \frac{13 \times 20}{13 \times 2 + 20 \times 2} = 15.76 \text{ in.}$$

$\bar{V}_1$  = specific volume of fluid, 2.774 ft<sup>3</sup>/lb for saturated argon vapor, 9.673 ft<sup>3</sup>/lb for argon gas at STP, 3.465 ft<sup>3</sup>/lb for saturated nitrogen vapor, and 13.8 ft<sup>3</sup>/lb for nitrogen gas at STP.

$\Delta P$  = pressure drop in psi, converted to inches of water for comparison.

$K$  = total resistance coefficient, sum of  $K_{elbow}$ ,  $K_{enlarge1}$ ,  $K_{enlarge2}$ ,  $K_{straight}$ ,  $K_{entrance}$ , and  $K_{exit}$ .

$K_{elbow}$  = 30 x  $f_T$  where  $f_T$  is the friction factor in the zone of complete turbulence, 0.0132 for the ~16 inch equivalent duct diameter.

$K_{enlarge1}$  = resistance of enlargement from 9.625 x 13 inch fan outlet to 13 x 20 inch duct, 1.0 to be conservative.

$K_{enlarge2}$  = resistance of enlargement from 13 x 20 duct to 20 x 20 inch duct, 1.0 to be conservative.

$K_{straight}$  = resistance to flow thru straight pipe,  $K_{straight} = f \times L / d$  where  $f$  is the friction factor based on Reynolds # and  $L$  is the length of the straight section which is 15 feet x 12 inches per ft. = 180 inches.

$K_{entrance}$  = resistance due to entrance into duct, 0.78.

$K_{exit}$  = resistance due to exit from duct, 1.0.

$Re$  = Reynolds number,  $Re = 6.31 \frac{W}{d\mu}$  (ratio of inertial to viscous forces).

$\mu$  = dynamic viscosity, 0.007029 centipoise for saturated argon vapor, 0.02246 centipoise for argon gas at STP, 0.005373 centipoise for saturated nitrogen vapor, and 0.01769 centipoise for nitrogen gas at STP.

The static head loss is calculated from the specific volume of the gas and the height of the duct as shown below

$$\frac{1 \text{ lb}}{\bar{V}_1 \text{ ft}^3} \times \frac{L \text{ in}}{1} \times \frac{\text{ft}}{12 \text{ in}} \times \frac{1 \text{ ft}^2}{144 \text{ in}^2} \times \frac{27.6799 \text{ in. H}_2\text{O}}{1 \text{ psi}}$$

For saturated argon vapor, the static head is found to be

$$\frac{1 \text{ lb}}{2.774 \text{ ft}^3} \times \frac{180 \text{ in}}{1} \times \frac{\text{ft}}{12 \text{ in}} \times \frac{1 \text{ ft}^2}{144 \text{ in}^2} \times \frac{27.6799 \text{ in. H}_2\text{O}}{1 \text{ psi}} = 1.039 \text{ in. H}_2\text{O}.$$

The louver pressure drop was provided by the vendor for a 2000 SCFM air flow. It would be slightly more for the warm argon flow and less for the cold gas flows. For the warm argon gas flow, the louver pressure drop is adjusted upward by the ratio of the warm argon to nitrogen flowing pressure drops,  $0.887 / 0.622 = 1.43$ .

Table 3.5a.3 provides estimates of pressure drop for the various cases. The fan rating of 2000 SCFM at 4 inches of H<sub>2</sub>O is more than adequate to handle the flow rates considered in the ODH analysis.

Table 3.5a.3: Pressure drop for both warm and cold gas flow thru the ODH duct.

	<i>Re</i>	<i>f</i>	<i>K</i>	Flowing $\Delta P$ in. H <sub>2</sub> O	Static Head $\Delta P$ in. H <sub>2</sub> O	Louver $\Delta P$ in. H <sub>2</sub> O	Total $\Delta P$ in. H <sub>2</sub> O
Warm N <sub>2</sub>	196,815	0.016	4.742	0.622	0.209	0.12	0.950
Cold N <sub>2</sub>	648,150	0.014	4.72	0.155	0.832	<0.12	1.107
Warm Ar	221,181	0.016	4.743	0.887	0.298	~0.17	1.355
Cold Ar	706,870	0.014	4.72	0.253	1.039	<0.12	1.412

Table 3.5a.1: PAB ODH Risk Analysis with ventilation running.

ITEM	Comment	Type of Failure	# of Items	PI Fail Rate events/hr	Source of Fail Rate	Group Fail Rate (PI x #)	Exhaust fan Availability events/hr	R leak rate SCFM	O vent rate SCFM	O2 Concentration %	FI Fatality Factor fatality/event	ODH Rate fatality/hr
<b>Nitrogen circuit</b>												
LN2 supply piping	< 3" diameter, max flow into PAB	Rupture - severed line	1	1.00E-09	NRC	1.00E-09	0.9993	1198	2000	8.42	1.00E+00	9.99E-10
Condenser	Treat as dewar, 25% pipe diameter	Leak/rupture	1	1.00E-06	FNAL	1.00E-06	0.9993	260	2000	18.27	3.95E-08	3.95E-14
EV-104-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
EV-105-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
EV-106-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
LT-10-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	260	2000	18.27	3.95E-08	1.18E-14
MV-119-N	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
MV-120-N	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
PI-44-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	260	2000	18.27	3.95E-08	1.18E-14
PT-133-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	260	2000	18.27	3.95E-08	1.18E-14
PT-1-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	260	2000	18.27	3.95E-08	1.18E-14
PT-27-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	260	2000	18.27	3.95E-08	1.18E-14
PSV-101-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
PSV-101-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
PSV-101-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
TE-6-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	260	2000	18.27	3.95E-08	1.18E-14
SV-117-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
Welds	Max flow thru 25% pipe diameter	Leak/rupture	50	3.00E-09	NRC	1.50E-07	0.9993	260	2000	18.27	3.95E-08	5.92E-15
Flanges	Max flow thru 25% pipe diameter	Leak/rupture	10	3.00E-07	NRC	3.00E-06	0.9993	260	2000	18.27	3.95E-08	1.18E-13
LN2 vent piping	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-09	NRC	1.00E-09	0.9993	260	2000	18.27	3.95E-08	3.95E-17
PCV-388-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
PSV-389-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
MV-375-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	260	2000	18.27	3.95E-08	3.95E-16
<b>Argon Circuit</b>												
LA supply piping	< 3" diameter, max flow into PAB	Rupture - severed line	1	1.00E-09	NRC	1.00E-09	0.9993	6572	2000	15.9	2.51E-06	2.51E-15
LA supply dewar reliefs	Max flow thru relief valve	Premature open	4	1.00E-05	NRC	4.00E-05	0.9993	68.1	2000	20.28	1.16E-09	4.63E-14
PSV-204-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-204-Ar	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	1825	2000	15.90	2.51E-06	4.37E-11
MV-204-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-213-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-218-Ar	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	1825	2000	15.90	2.51E-06	4.37E-11
MV-218-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
PSV-219-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-217-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-365-V	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-365-V	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-365-V	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	1825	2000	15.90	2.51E-06	4.37E-11
MV-366-V	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	1825	2000	15.90	2.51E-06	4.37E-11
MV-480-HAr	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-461-HAr	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
PSV-250-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
PSV-249-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-202-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-208-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-239-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-244-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
MV-370-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	433	2000	16.45	9.53E-07	9.52E-15
LT-13-Ar	Treat as flange, max flow into cryostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	232	2000	18.56	2.36E-08	7.07E-15
MV-360-V	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-360-V	Max flow into cryostat	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	232	2000	18.56	2.36E-08	4.10E-13
MV-241-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-247-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-248-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
DPT-67-Ar	Treat as flange, max flow into cryostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	232	2000	18.56	2.36E-08	7.07E-15
DPT-153-Ar	Treat as flange, max flow into cryostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	232	2000	18.56	2.36E-08	7.07E-15
MV-148-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
EP-307-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
EP-78-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
PSV-156-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-242-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
PI-243-Ar	Treat as flange, max flow into cryostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	232	2000	18.56	2.36E-08	7.07E-15
MV-246-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-128-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
PSV-136-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-132-N2	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-132-N2	Max flow into cryostat	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	232	2000	18.56	2.36E-08	4.10E-13
MV-131-N2	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-127-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-251-V	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-252-V	Max flow into cryostat	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	0.9993	232	2000	18.56	2.36E-08	4.10E-13
MV-252-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-253-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-290-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
MV-254-V	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
PT-185-V	Treat as flange, max flow into cryostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	232	2000	18.56	2.36E-08	7.07E-15
PT-186-V	Treat as flange, max flow into cryostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	0.9993	232	2000	18.56	2.36E-08	7.07E-15
MV-256-Ar	Max flow into cryostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	0.9993	232	2000	18.56	2.36E-08	2.36E-16
CV-256-Ar	Max flow into cryostat	Leak										

Table 3.5a.2: PAB ODH Risk Analysis with NO ventilation running.

ITEM	Comment	Type of Failure	# of Items	PI Fail Rate events/hr	Source of Fail Rate	Group Fail Rate (PI x #)	Fan Availability Rate events/hr	R leak rate SCFM	Q vent rate SCFM	O2 Concentration %	FI Fatality Factor fatality/event	φ-SPIFI ODH Rate fatality/hr
<b>Nitrogen circuit</b>												
LN2 supply piping	< 3" diameter, max flow into PAB	Rupture - severed line	1	1.00E-09	NRC	1.00E-09	7.00E-04	1198	0	0	1.00E+00	7.00E-13
Condenser	Treat as dewar, 25% pipe diameter	Leak/rupture	1	1.00E-06	FNAL	1.00E-06	7.00E-04	260	0	0	1.00E+00	7.00E-10
EV-104-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
EV-105-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
EV-106-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
LT-10-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	260	0	0	1.00E+00	2.10E-10
MV-119-N	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
MV-120-N	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
PI-44-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	260	0	0	1.00E+00	2.10E-10
PI-133-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	260	0	0	1.00E+00	2.10E-10
PT-1-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	260	0	0	1.00E+00	2.10E-10
PT-27-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	260	0	0	1.00E+00	2.10E-10
PSV-101-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
PSV-101-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
PSV-101-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
TE-6-N2	Treat as flange, max flow thru 25% pipe diameter	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	260	0	0	1.00E+00	2.10E-10
SV-117-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
Welds	Max flow thru 25% pipe diameter	Leak/rupture	50	3.00E-09	NRC	1.50E-07	7.00E-04	260	0	0	1.00E+00	1.05E-10
Flanges	Max flow thru 25% pipe diameter	Leak/rupture	10	3.00E-07	NRC	3.00E-06	7.00E-04	260	0	0	1.00E+00	2.10E-09
LN2 vent piping	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-09	NRC	1.00E-09	7.00E-04	260	0	0	1.00E+00	7.00E-13
PCV-388-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
PSV-389-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
MV-375-N2	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	260	0	0	1.00E+00	7.00E-12
<b>Argon Circuit</b>												
LAr supply piping	< 3" diameter, max flow into PAB	Rupture - severed line	1	1.00E-09	NRC	1.00E-09	7.00E-04	6572	0	15.9	2.51E-06	2.51E-15
LAr supply dewar reliefs	Max flow thru relief valve	Premature open	4	1.00E-05	NRC	4.00E-05	7.00E-04	68.1	0	15.9	2.51E-06	1.00E-10
PSV-204-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-204-Ar	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	1825	0	15.9	2.51E-06	4.37E-11
MV-204-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-213-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-218-Ar	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	1825	0	15.9	2.51E-06	4.37E-11
MV-218-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
PSV-219-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-217-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-365-V	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-365-V	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-365-V	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	1825	0	15.9	2.51E-06	4.37E-11
MV-366-V	Max flow thru valve (Cv = 1.2)	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	1825	0	15.9	2.51E-06	4.37E-11
MV-480-HAr	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-461-HAr	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
PSV-250-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
PSV-249-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-202-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-208-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-239-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-244-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
MV-370-Ar	Max flow thru 25% pipe diameter	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	433	0	15.9	2.51E-06	1.76E-17
LT-13-Ar	Treat as flange, max flow into cvrostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	232	0	15.9	2.51E-06	5.28E-16
MV-360-V	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-360-V	Max flow into cvrostat	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	232	0	15.9	2.51E-06	3.06E-14
MV-241-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-247-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-248-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
DPT-67-Ar	Treat as flange, max flow into cvrostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	232	0	15.9	2.51E-06	5.28E-16
DPT-153-Ar	Treat as flange, max flow into cvrostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	232	0	15.9	2.51E-06	5.28E-16
MV-246-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
EP-307-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
EP-78-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
PSV-156-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-242-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
PI-243-Ar	Treat as flange, max flow into cvrostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	232	0	15.9	2.51E-06	5.28E-16
MV-246-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-128-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
PSV-136-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-132-N2	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-132-N2	Max flow into cvrostat	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	232	0	15.9	2.51E-06	3.06E-14
MV-131-N2	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-127-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-251-V	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-252-V	Max flow into cvrostat	Valve left wide open	1	1.74E-05	33 x 5064 TBL 3	1.74E-05	7.00E-04	232	0	15.9	2.51E-06	3.06E-14
MV-252-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-253-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-290-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-254-V	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
PT-185-V	Treat as flange, max flow into cvrostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	232	0	15.9	2.51E-06	5.28E-16
PT-186-V	Treat as flange, max flow into cvrostat	Leak/rupture	1	3.00E-07	NRC	3.00E-07	7.00E-04	232	0	15.9	2.51E-06	5.28E-16
MV-256-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
CV-256-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08	NRC	1.00E-08	7.00E-04	232	0	15.9	2.51E-06	1.76E-17
MV-291-Ar	Max flow into cvrostat	Leak/rupture	1	1.00E-08								

**3.5a2 – ODH Fan Manufacturer Info**

**ENGINEERING DATA**

Approx. Fan Weight (lb)	Max. T Motor Frame Size
170	145

\*\*Fan weight is without accessories.

Drive Type
Variable

**CONFIGURATION**

Arrangement	Rotation	Discharge Position
10	CW	TH

**INSTALLATION**

Air Stream Temp. (F)
70

**MOTOR SPECS**

Size (hp)	RPM	V/C/P	Enclosure	Motor Frame Size	FLA (A)
2	1725	460/60/3	ODP	56	3.4

FLA - Based on tables 150 or 148 of National Electrical Code 2002.

# SWB Backward Inclined Centrifugal Utility Fan

Tag: Mark 1

**STANDARD CONSTRUCTION FEATURES**

**HOUSING:** Heavy gauge steel housing with Lock-seam construction • Unit support angles with prepunched mounting holes • Adjustable motor plate • Corrosion resistant fasteners • Entire unit is phosphatized and coated.  
**BEARINGS, SHAFT, AND WHEEL:** Heavy duty lubricatable, self-aligning ball bearing pillow blocks • Polished, solid steel shafts • Backward inclined fan wheel  
(Fans with EXP. motors include: aluminum wheel, aluminum rub ring, and shaft seal)

**SELECTED OPTIONS & ACCESSORIES**

Neoprene Isolators Indoor/Outdoor, Single Deflection 1/4"  
Steel Wheel Construction  
Outlet Flange - Punched  
Permatector - Standard Coating on Entire Fan


**PERFORMANCE** Elevation ft = 0

Qty.	Model	Volume (CFM)	SP (in wg)	TS (ft/min)	OV (ft/min)	FRPM	Operating Power (hp)	SE %
1	SWB-212-20	2,000	4	9,653.0	2,433.0	3,010	1.97	64

**SOUND**

Inlet Sound Power by Octave Band								LwA	dBA	Noise Criteria	Sones
62.5	125	250	500	1000	2000	4000	8000				
90	79	78	86	78	78	74	69	86	75	73	24


LwA - A weighted sound power level, based on ANSI S1.4. dBA - A weighted sound pressure level, based on 11.5 dB attenuation per octave band at 5.0 ft. Noise Criteria (NC) based on an average attenuation of 11.5 dB per octave band at 5.0 ft.



Size: 12  
Arrangement: 10

# SWB Backward Inclined Centrifugal Utility Fan

NOTES: All dimensions shown are in units of inches.  
Drawings are not to scale. Drawings are of standard unit and do not include dimensions for accessories or design modifications.




# VCD-23

## Low Leakage Control Damper

### Application & Design

The model VCD-23 is a ruggedly built low leakage control damper for application as an automatic control or manual balancing damper. A wide range of electric and pneumatic actuators are available. Non-jackshafed dampers will be supplied with a blade drive lever for internal actuator mounting unless external actuator mounting is specified in which case an extension pin kit will be provided. The VCD-23 is intended for applications in low to medium pressure and velocity systems.

- **FRAME:** Galvanized, 5 in x 1 in hat channel, reinforced corners, low profile head and sill on dampers 17 in high and smaller. (When 304 SS material is selected the frame, blades and all damper components will be provided in 304 SS except the actuator, mounting hardware and jackshaft)
- **BLADES:** Galvanized, reinforced with 3 longitudinal structurally designed v's.
- **LINKAGE:** Side linkage out of air stream.
- **AXLES:** 0.5 in dia.



Notes: All dimensions shown are in units of inches.

W & H furnished approximately 0.25 in undersized and only refer to damper dimensions (sleeve thickness is not included).

Electrical accessory wiring terminates at the accessory. Field wiring is required to individual components.

### CONSTRUCTION FEATURES

<b>Blade Action:</b>	Opposed	<b>Sizing:</b>	Nominal
<b>Frame Type:</b>	Channel	<b>Frame Thickness (ga):</b>	16
<b>Material:</b>	Galvanized	<b>Actuator Type:</b>	120 VAC
<b>Axle Material:</b>	Steel	<b>Actuator Mount:</b>	Ext Sideplate
<b>Axle Bearings:</b>	Bronze	<b>Actuator Location:</b>	Left Side
<b>Linkage Material:</b>	Steel	<b>Fail Position:</b>	Open
<b>Blade Seal:</b>	Silicone	<b>Cycle:</b>	60 Cycle
<b>Jamb Seal Mat:</b>	304 SS		



ID #	Tag	Qty	W (in)	H (in)	Drive Arr.	Actuator	Act. Qty.	Sideplate Length...	A-Dim. (in)
1-1		1	20.000	20.000	11-1FEL-0	FSLF-120	1	8	1.5

# EDJ-430


## Drainable Head - 30° Blade

### Application & Design

High Performance Drainable Head Stationary Louver Model EDJ-430 is a weather louver designed to protect air intake and exhaust openings in building exterior walls. Design incorporates drainable head, J style blades, sloped sill and high free area to provide maximum resistance to rain and weather while providing minimum resistance to airflow. The EDJ-430 is an extremely efficient louver with AMCA LICENSED PERFORMANCE DATA enabling designers to select and apply with confidence.

#### STANDARD CONSTRUCTION FEATURES

- Frame: Heavy gauge 6063T5 extruded aluminum, 4 in x 0.081 in nominal dimensions.
- Blades: J style, 6063T5 extruded aluminum, 0.081 in nominal wall thickness, positioned at 30° angles on approximately 3 in centers.
- Bird Screen: 0.75 in x 0.051 in flattened expanded aluminum in removable frame. Screen is mounted on inside (rear).
- Finish: Mill.



Notes: All dimensions shown are in units of inches.  
Height & Width furnished approximately 0.25 in under size.

### CONSTRUCTION FEATURES

Frame Type: Flanged  
Flange Width (in): 1.5  
Frame Thickness (in): 0.081  
Blade Thickness (in): 0.081  
Sizing: Nominal  
Shape: Rectangular  
Material: Aluminum  
Tag List:

### SELECTED OPTIONS & ACCESSORIES

Internally mounted flattened expanded aluminum bird screen


ID #	Tag	Qty	W (in)	H (in)	Free Area (ft <sup>2</sup> )	Sect. Wide	Sect. High	Ship Sec.
2-1		1	26.000	26.000	2.05	1	1	1

### PERFORMANCE

ID #	Tag	Qty	Volume (CFM)	Pres. Drop (in wg)	Air Velocity (ft/min)	BPWP
2-1		1	2,000	0.12	977	941

---

### Damper & Louver Drive Arrangements



11-1FEL-0 or 11CEL-0

### **3.5b1 – Pressure Vessel Engineering Note for Luke**

See 4.1a for relief valve calculations and 4.1aa for supporting relief valve calculation documentation.

Relief valve certifications are included at end of pressure vessel engineering note along with the Form U-1A Manufacturer's Data Report for Pressure Vessels.

PRESSURE VESSEL ENGINEERING NOTE

PER CHAPTER 5031

Prepared by: Terry Tope
Preparation date: 3.15.07

- 1. Description and Identification
Fill in the label information below:

This vessel conforms to Fermilab ES&H Manual Chapter 5031

Vessel Title FLARE Materials Test Station Cryostat

Vessel Number PPD#10100

← Obtain from Division/Section Safety Officer

Vessel Drawing Number D-13109101

Maximum Allowable Working Pressures (MAWP):

Internal Pressure 35 psig

External Pressure 15 psig

Working Temperature Range -320 OF 100 OF

Contents Liquid Argon

Designer/Manufacturer Chart, Inc.

Test Pressure (if tested at Fermi) Acceptance Date:

← Document per Chapter 5034 of the Fermilab ES&H Manual

PSIG, Hydraulic Pneumatic
Accepted as conforming to standard by

of Division/Section PPD Date: 4/17/07

← Actual signature required

NOTE: Any subsequent changes in contents, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review.

Reviewed by: [Signature] Date: 6/12/07

Director's signature (or designee) if the vessel is for manned areas but doesn't conform to the requirements of the chapter.

Date:

Date:

ES&H Director Concurrence
Amendment No.: Reviewed by: Date:

[Signature lines for concurrence]

Lab Property Number(s): 099938 \_\_\_\_\_  
 Lab Location Code: 502 \_\_\_\_\_ (obtain from safety officer)  
 Purpose of Vessel(s): Test contamination effects of proposed LArTPC  
 materials on ultra high purity liquid argon. \_\_\_\_\_

Vessel Capacity/Size: 250 liter\_\_ Diameter: 22 inches Length: 37.5 inches  
 Normal Operating Pressure (OP) 20 psig \_\_\_\_\_  
 MAWP-OP = 15 \_\_\_\_\_ PSI

List the numbers of all pertinent drawings and the location of the originals.

<u>Drawing #</u>	<u>Location of Original</u>
D-13109101 _____	Chart Inc., 1300 Airport Drive, _____ Ball Ground GA 30107 _____
_____	_____
_____	_____
_____	_____


2. Design Verification

Is this vessel designed and built to meet the Code or "In-House Built" requirements?  
 Yes X No \_\_\_\_\_.

If "No" state the standard that was used \_\_\_\_\_.  
 Demonstrate that design calculations of that standard have been made and that other requirements of that standard have been satisfied.  
 Skip to part 3 "system venting verification."

Does the vessel(s) have a U stamp? Yes X No \_\_\_\_\_. If "Yes", complete section 2A; if "No", complete section 2B.

A. Staple photo of U stamp plate below.  
 Copy "U" label details to the side



Copy data here:  
 NAT'L. BD. NO. \_\_\_\_\_  
 168161 \_\_\_\_\_  
 CERTIFIED BY \_\_\_\_\_  
 CHART, INC. \_\_\_\_\_  
 RT-2 \_\_\_\_\_  
 MODEL: DEWAR R \_\_\_\_\_  
 M.A.W.P.: 35 P.S.I. @ 100 °F  
 M.D.M.T. -320 °F @ 35 P.S.I.  
 MAEWP 15 psi @ 100 °F \_\_\_\_\_  
 2005 S/N CEGRZ05L102 \_\_\_\_\_  
 DUPLICATE \_\_\_\_\_

Provide ASME design calculations in an appendix. On the sketch below, circle all applicable sections of the ASME code per Section VIII, Division I. (Only for non-coded vessels)




Figure 1. ASME Code: Applicable Sections

2B.

Summary of ASME Code

<u>Item</u>	<u>Reference ASME Code Section</u>	<u>CALCULATION RESULT</u> (Required thickness or stress level vs. actual thickness calculated stress level)
_____	_____	VS _____

3. System Venting Verification Provide the vent system schematic.

Does the venting system follow the Code UG-125 through UG-137?  
Yes  No

Does the venting system also follow the Compressed Gas Association Standards S-1.1 and S-1.3?  
Yes  No

A "no" response to both of the two proceeding questions requires a justification and statement regarding what standards were applied to verify system venting is adequate.

List of reliefs and settings:

<u>Manufacturer</u>	<u>Model #</u>	<u>Set Pressure</u>	<u>Flow Rate</u>	<u>Size</u>
Anderson Greenwood	83SF1216F	35 psig	227 SCFM Ar	1.5" x 2.0"
BS&B (rupture disc)	JRS	55 psig	1066 SCFM Ar	1.5"
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

4. Operating Procedure

Is an operating procedure necessary for the safe operation of this vessel?  
Yes  No  (If "Yes", it must be appended)

5. Welding Information

Has the vessel been fabricated in a non-code shop? Yes  No   
If "Yes", append a copy of the welding shop statement of welder qualification (Procedure Qualification Record, PQR) which references the Welding Procedure Specification (WPS) used to weld this vessel.

6. Existing, Used and Unmanned Area Vessels

Is this vessel or any part thereof in the above categories?  
Yes  No

If "Yes", follow the requirements for an Extended Engineering Note for Existing, Used and Unmanned Area Vessels.

7. Exceptional Vessels

Is this vessel or any part thereof in the above category?  
Yes  No

If "Yes", follow the requirements for an Extended Engineering Note for Exceptional Vessels.

**THIS VESSEL CONFORMS TO FERMILAB ES&H MANUAL  
CHAPTER 5031**

Vessel Title \_\_\_\_\_

Vessel Number \_\_\_\_\_

Vessel Drawing Number \_\_\_\_\_

Maximum Allowable Working Pressures (MAWP):

Internal Pressure \_\_\_\_\_

External Pressure \_\_\_\_\_

Working Temperature Range \_\_\_\_\_ °F \_\_\_\_\_ °F

Contents \_\_\_\_\_

Designer \_\_\_\_\_

Test Pressure (if tested at Fermi) \_\_\_\_\_ DATE \_\_\_\_/\_\_\_\_/\_\_\_\_

\_\_\_\_\_ PSIG, Hydraulic \_\_\_\_\_ Pneumatic \_\_\_\_\_

Accepted as conforming to standard by \_\_\_\_\_

Of Division/Section \_\_\_\_\_

NOTE: Any subsequent changes in content, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review and test.

Figure 2. Sample of sticker to be completed and be placed on vessel.

**FORM U-1A MANUFACTURER'S DATA REPORT FOR PRESSURE VESSELS**  
**(Alternative Form for Single Chamber, Completely Shop-Fabricated Vessels Only)**  
**As Required by the Provisions of the ASME Code Rules, Section VIII, Division 1**

1. Manufactured and certified by CHART, Inc., 1300 Airport Drive, Ball Ground GA 30107  
 (Name and address of Manufacturer)

2. Manufactured for STOCK  
 (Name and address of purchaser)

3. Location of installation Unknown  
 (Name and address)

4. Type Vertical / Tank CEGRZ05L101-102 D-13109101 168160-168161 2005  
 (Horiz. or vert., tank) (Mfg.'s serial No.) (CRN) (Drawing No.) (Nat'l. Bd. No.) (Year built)

5. The chemical and physical properties of all parts meet the requirements of material specifications of the ASME BOILER AND PRESSURE VESSEL CODE. The design, construction, and workmanship conform to ASME Rules, Section VIII, Division 1 2004

to A04 N/A Low Temp / UHA-51 (a)  
 Addenda (Date) Code Case Nos. Special Service per UG-120 (d)

6. Shell: SA-240 T304 .090 NOM 0.0 1 ft. 10.24 in. 3 ft. 1.5 in.  
 (Matl. (Spec. No., Grade)) (Nom. Thk. (in.)) (Corr. Allow. (in.)) Dia. I.D. (ft. & in.) Length (overall) (ft. & in.)

7. Seams: TYPE 3 NONE 60 N/A N/A TYPE 3 NONE 1  
 Long. (Welded, Dbl., Sngl., Lap, Butt) R.T. (Spot or Full) Eff. (%) H.T. Temp. (°F) Time (hr) Girth (welded, Dbl., Sngl., Lap, Butt) R.T. (Spot, Partial, or Full) No. of Courses

8. Heads: (a) Matl. N/A (b) Matl. SA-240 T 304  
 (Spec. No., Grade) (Spec. No., Grade)

	Location (top, Bottom, Ends)	Minimum Thickness	Corrosion Allowance	Crown Radius	Knuckle Radius	Elliptical Ratio	Conical Apex Angle	Hemispherical Radius	Flat Diameter	Side to Pressure (Convex or Concave)
(a)	Top	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
(b)	Bottom	0.095	0.0	22"	1.375"	N/A	N/A	N/A	N/A	Concave

If removable, bolts used (describe other fastenings) BOLTS ARE NOT FURNISHED  
 (Matl., Spec. No., Gr., Size, No.)

9. MAWP 35 15 psi at max. temp. 100 100 °F.  
 (internal) (external) (internal) (external)  
 Min. design metal temp. -320 °F at 35 psi. Hydro, pneu., or COMB. test pressure 53 psi.

10. Nozzles, inspection and safety valve openings:

Purpose (Inlet, Outlet, Drain)	No.	Diam. or Size	Type	Matl.	Nom. Thk.	Reinforcement Matl.	How Attached	Location
INLET/ OUTLET	1	22.09" ID	FLANGE	SA240 T304	1"	None	UW-13.2(h)	N/A

11. Supports: Skirt No Lugs N/A Legs N/A Other NONE Attached N/A  
 (Yes or No) (No.) (No.) (Describe) (where and How)


12. Remarks: Manufacturer's Partial Data reports properly identified and signed by Commissioned Inspectors have been furnished for the following items of the report: N/A  
 (Name of part, item number, Mfg.'s name and identifying stamp)  
Vacuum Jacketed Dewar. Low Temperature Service. Design Pressure is 35 PSI.  
Impact test Exempt Per UHA51 (d) (1) (a). Hydro Test Is Vertical For Noncorrosive Service.

CERTIFICATION OF SHOP COMPLIANCE	
We certify that the statements made in this report are correct and that all details of design, material, construction, and workmanship of this vessel conform to the ASME Code for Pressure Vessels, Section VIII, Division 1. "U" Certificate of Authorization No. <u>19.262</u> expires <u>03/14, 2008</u> .	
Date <u>12/1/05</u> Co. name <u>CHART, Inc.</u> Signed _____	Signed _____
(Manufacturer)	(Representative)
CERTIFICATE OF SHOP INSPECTION	
Vessel constructed by <u>CHART, Inc.</u> at <u>Canton, GA</u>	
I, the undersigned, holding a valid commission issued by the National Board of Boiler and Pressure Vessel Inspectors and/or the State or Province of <u>Georgia</u> and employed by <u>OneBeacon America Insurance Company</u>	
have inspected the component described in this Manufacturer's Data Report on <u>12/1</u> , <u>2005</u> , and state that, to the best of my Knowledge and belief, the Manufacturer has constructed this pressure vessel in accordance with the ASME Code, Section VIII, Division 1. By signing this certificate neither the inspector nor his employer makes any warranty, expresses or implied, concerning the pressure vessel described in this Manufacturer's Data Report. Furthermore, neither the inspector nor his employer shall be liable in any manner for any personal injury or property damage or a loss of any kind arising from or connected with this inspection.	
Date <u>12/13/05</u> Signed _____	Commissions <u>NB# : 121244 GA #538</u>
(Authorized Inspector)	(Nat'l Bd. (include endorsements), State, Prov. and No.)

ASME Manufacturer's Certificate of Conformance for Pressure Relief Valves  
Form UV-1 (Section VIII)

1. Manufactured by: Anderson Greenwood Crosby - Stafford, Texas

2. Table of Code symbol stamped items:


ID (Serial No)	Date	NR Cert #	QTY	Type	Size, (NPS)	Set Pressure,psig (Nameplate)	Capacity	Test Fluid	Date Code	CI Name	CI Signature
06-55706	11/03/06	01089	1	83SF1216-F	1 1	00035 PSIG	244 SCFM	AIR	SBE ID#	M. Howard	

3. Remarks: L61448.001

CERTIFICATE OF SHOP COMPLIANCE

By the signature of the Certified Individual (CI) noted above, we certify that the statements made in this report are correct and that all details for design, material, construction and workmanship of the pressure relief devices conform with the requirements of Section VIII, Division 1 of the ASME Boiler and Pressure Vessel Code.

UV Certificate of Authorization No. 3793 Expires December 31, 2007

Date: 11.03.06 Signed:  Name: Anderson Greenwood Crosby - Stafford, Texas  
(Responsible representative) (Manufacturer)

TYCO VALVES & CONTROLS LP  
STAFFORD DIVISION  
ANDERSON GREENWOOD CROSBY

SALES ORDER NO: L61448.001

FUNCTIONAL TEST REPORT

DATE PRINTED: 11/03/06

PAGE: 1

CUSTOMER: TYCO VALVES & CONTROLS-S  
PO NUMBER: 1735082-00

SHIP TO CUST: FERMI LABS  
PRODUCT NUMBER: 830555F12..16..F00035GBBS  
PART NBR: L61448.001

MARKS: 572105

GAUGE NO:

*A60005*

SERIAL NO	TAG	PRIMARY PRESSURE PARTS TEST	BELLOWS OR O-RING TEST	SECONDARY PRESSURE ZONE TEST	ASSY TECH	NAMEPLATE SET 35 COTP	SPECIFIED RESEAT	LEAK TEST 30 1 MIN TIME	FINAL TRCH
06-55706			<i>NA</i>	<i>30</i>	<i>OK</i>	<i>36</i>	<i>FIXED 1 turn</i>	<i>0</i>	<i>OK</i>

TRACEABILITY REQUIREMENTS - HEAT/CODE NUMBERS FOR TRACEABLE COMPONENTS

SERIAL NO	BODY/CYLINDER	BASE	BONNET	FLANGE IN	FLANGE OUT	NOZZLE	STUB IN	STUB OUT	DISC
06-55706									

CUSTOMER/DATE  
WITNESSED:

UNITS	UNITS OF MEASURE			TEST MEDIUM		
	PRES.	VAC.	AIR	H2O	STEAM	
PSIG	<i>/</i>		<i>/</i>			
*WC						

VERIFIED/DATE  
INSPECTED BY:  
*M.H.*  
NOV 08 2006

SDJDE FORMS-GRABAR, FORMAT-FMT2C, MODIFY-CMS2, END;

**3.5b2 – Updated Pressure Vessel Engineering Note for PAB (Formally PS1)  
Liquid Nitrogen Dewar**

See 4.1c for relief valve calculations.

Relief valve certifications included at end of pressure vessel engineering note.

Lab Property Number: \_\_\_\_\_  
Lab Location Code: \_\_\_\_\_  
Purpose of Vessel(s): To supply liquid nitrogen to P&S.  
**PRESSURE VESSEL ENGINEERING NOTE**

**PER CHAPTER 5031**

Prepared by: Terry Tope \_\_\_\_\_  
Preparation date: 4.23.07 \_\_\_\_\_

1. Description and Identification  
Fill in the label information below:

This vessel conforms to Fermilab ES&H Manual Chapter 5031

Vessel Title Liquid Nitrogen Dewar #14 \_\_\_\_\_

Vessel Number RD#1079 \_\_\_\_\_

Vessel Drawing Number N/A \_\_\_\_\_

Maximum Allowable Working Pressures (MAWP):  
Internal Pressure 75 psig + full vacuum \_\_\_\_\_  
External Pressure Not Rated \_\_\_\_\_

Working Temperature Range -320 °F 100 °F

Contents Liquid Nitrogen

Designer/Manufacturer C.E. Howard Corporation

Test Pressure (if tested at Fermi) Acceptance Date: \_\_\_\_\_

\_\_\_\_\_ PSIG, Hydraulic \_\_\_\_\_ Pneumatic \_\_\_\_\_  
Accepted as conforming to standard by  
*[Signature]*

of Division/Section PPD Date: 4/17/07

← Obtain from Division/Section Safety Officer

← Document per Chapter 5034 of the Fermilab ES&H Manual

← Actual signature required

NOTE: Any subsequent changes in contents, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review.

Reviewed by: *[Signature]* Date: 4/24/07

Director's signature (or designee) if the vessel is for manned areas but doesn't conform to the requirements of the chapter.

\_\_\_\_\_ Date: \_\_\_\_\_

\_\_\_\_\_ Date: \_\_\_\_\_

ES&H Director Concurrence  
Amendment No.: \_\_\_\_\_ Reviewed by: \_\_\_\_\_ Date: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

Lab Property Number(s): \_\_\_\_\_  
 Lab Location Code: 502 \_\_\_\_\_ (obtain from safety officer)  
 Purpose of Vessel(s): To supply liquid nitrogen to PAB. \_\_\_\_\_

Vessel Capacity/Size: 7000 liters Diameter: 84 inches Length: 167 inches  
 Normal Operating Pressure (OP) 30 psig \_\_\_\_\_  
 MAWP-OP = 45 \_\_\_\_\_ PSI

List the numbers of all pertinent drawings and the location of the originals.

<u>Drawing #</u>	<u>Location of Original</u>
N/A _____	_____
_____	_____
_____	_____
_____	_____
_____	_____


2. Design Verification

Is this vessel designed and built to meet the Code or "In-House Built" requirements?  
 Yes X No \_\_\_\_\_.

If "No" state the standard that was used \_\_\_\_\_.  
 Demonstrate that design calculations of that standard have been made and that other requirements of that standard have been satisfied.  
 Skip to part 3 "system venting verification."

Does the vessel(s) have a U stamp? Yes X No \_\_\_\_\_. If "Yes", complete section 2A; if "No", complete section 2B.

A. Staple photo of U stamp plate below.  
 Copy "U" label details to the side



Copy data here:  
 C.E. Howard Corporation \_\_\_\_\_  
 Built for Cryo Sonics Inc. \_\_\_\_  
 Service: Liquid Nitrogen \_\_\_\_  
 Date: 1961 Code: 1959 \_\_\_\_  
 Design Pressure: \_\_\_\_\_  
 75 psig + Full Vac. \_\_\_\_\_  
 Test Pressure: 150 psig \_\_\_\_  
 Design Temp: \_\_\_\_\_  
 -320 °F to 100 °F I.T \_\_\_\_  
 Serial Number 489 \_\_\_\_\_  
 \_\_\_\_\_



3. System Venting Verification Provide the vent system schematic.

Does the venting system follow the Code UG-125 through UG-137?  
Yes  No

Does the venting system also follow the Compressed Gas Association Standards S-1.1 and S-1.3?  
Yes  No

A "no" response to both of the two preceding questions requires a justification and statement regarding what standards were applied to verify system venting is adequate.

List of reliefs and settings:

<u>Manufacturer</u>	<u>Model #</u>	<u>Set Pressure</u>	<u>Flow Rate</u>	<u>Size</u>
Anderson Greenwood	81S1216G	75 psig	731 SCFM Air	1.5" x 2.0"
Fike (rupture disc)	CPV BT	105 psig	3024 SCFM Air	1.5"
Chart Industries	Herose EPD	75 psig	30 ms close	1 1/2"
Fill Shut Off Valve				

4. Operating Procedure

Is an operating procedure necessary for the safe operation of this vessel?

Yes  No  (If "Yes", it must be appended)

5. Welding Information

Has the vessel been fabricated in a non-code shop? Yes  No

If "Yes", append a copy of the welding shop statement of welder qualification (Procedure Qualification Record, PQR) which references the Welding Procedure Specification (WPS) used to weld this vessel.

6. Existing, Used and Unmanned Area Vessels

Is this vessel or any part thereof in the above categories?

Yes  No

If "Yes", follow the requirements for an Extended Engineering Note for Existing, Used and Unmanned Area Vessels.

7. Exceptional Vessels

Is this vessel or any part thereof in the above category?

Yes  No

If "Yes", follow the requirements for an Extended Engineering Note for Exceptional Vessels.

**THIS VESSEL CONFORMS TO FERMILAB ES&H MANUAL  
CHAPTER 5031**

Vessel Title \_\_\_\_\_

Vessel Number \_\_\_\_\_

Vessel Drawing Number \_\_\_\_\_

Maximum Allowable Working Pressures (MAWP):

Internal Pressure \_\_\_\_\_

External Pressure \_\_\_\_\_

Working Temperature Range \_\_\_\_\_ °F \_\_\_\_\_ °F

Contents \_\_\_\_\_

Designer \_\_\_\_\_

Test Pressure (if tested at Fermi) \_\_\_\_\_ DATE \_\_\_\_/\_\_\_\_/\_\_\_\_

\_\_\_\_\_ PSIG, Hydraulic \_\_\_\_\_ Pneumatic \_\_\_\_\_

Accepted as conforming to standard by \_\_\_\_\_

Of Division/Section \_\_\_\_\_

NOTE: Any subsequent changes in content, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review and test.

Figure 2. Sample of sticker to be completed and be placed on vessel.

# Tyco Valves & Controls

Bolingbrook, IL 60440  
800-261-3324

# VALVE REPAIR WORK ORDER

Page \_\_\_\_\_ of \_\_\_\_\_ TVCR- 5678 R

Customer FERMI LAB PO# \_\_\_\_\_

Location BATAVIA IL Date Rec'd 3-15-06

### RECORD OF ORIGINAL NAMEPLATE DATA

Prv. Mfr. Anderson Greenwood Capacity 442 SCFM CHANGE IN SET PRESSURE:  
Type No. 81512166 ASME Code Stamp UV Reset To 75 PSIG  
Inlet/Outlet 1.5 in. / 1 in. Mfr. S/N 86109675 New Capacity 731.5 SCFM  
Set Press 40 PSIG Tag No. SV099N

### RECORD OF PRETEST (AS FOUND)

Test Pressure \_\_\_\_\_ Pretest Sign-Off \_\_\_\_\_  
Blowdown \_\_\_\_\_ Tested by \_\_\_\_\_  
Tightness \_\_\_\_\_ Date \_\_\_\_\_  
Action \_\_\_\_\_ M&T E S/N \_\_\_\_\_

### RECORD OF PREVIOUS REPAIR

By Allied VALVE  
Model - Set -  
Capacity - Date 9-14-98  
Unique # 286028-2-FWR Stamp TESTED ONL

RECORD OF DISASSEMBLY & CLEANING	RECORD OF CRITICAL INSPECTION & MACHINING				
	Item (s): "As Found Conditions"	Comments	OK	Machine	Replace
Cap and Lever		X			
Bonnet/Compr Scr: <u>1.972</u>		X			
Spring/Steps	Spring#	X			X
Spindle/Disc	T.I.R.				X
Base/Nozzle	Bore Dia.			<u>L9P</u>	
Guide/Adj. Rings		X			
Other (Specify)					

RECORD OF REPLACEMENT PARTS		
Part No	Description	PO#
<u>04.4805-009</u>	<u>SOFT GOODS KIT</u>	<u>1731417-00</u>
<u>03.1062.002</u>	<u>Spring</u>	<u>1732392-00</u>

Notes Reset VALVE to 75PSI at Customer request.

### RECORD OF TECHNICIAN SIGN-OFF

Repair Step	Initials	Date
Nameplate	<u>MP</u>	<u>3-15-06</u>
Disassembly	<u>DA</u>	<u>3-22-06</u>
Cleaning	<u>DA</u>	<u>3-23-06</u>
Inspection	<u>DA</u>	<u>3-23-06</u>
Machining		
Parts	<u>DA</u>	<u>3-23-06</u>
Assembly	<u>DA</u>	<u>3-23-06</u>
Testing	<u>DA</u>	<u>3-24-06</u>
Final-Assembly	<u>DA</u>	<u>3-24-06</u>
VR Stamp	<u>(Y) N DA</u>	<u>3-24-06</u>

### RECORD OF FINAL TEST RESULTS

Test Stand/Media TB1000B-A11  
Test Pressure 75  
Blowdown -  
Tightness 69  
M&T E S/N 767

Repaired by

**TYCO VALVES & CONTROLS**  
Bolingbrook, IL VR No. 396 & 500

TVCR- 5678R DATE 3-06

STYLE 81512166

SET PRESS 75

CAP 731.5 SCFM YR

# Tyco Valves & Controls

Bolingbrook, IL 60440  
800-261-3324

# VALVE REPAIR WORK ORDER

Page \_\_\_\_\_ of \_\_\_\_\_ TVCR- 5677R

Customer FERMI LAB PO# \_\_\_\_\_

Location BATAVIA IL Date Rec'd 3-15-06

### RECORD OF ORIGINAL NAMEPLATE DATA

Prv. Mfr. Anderson Greenwood Capacity 442 SCFM CHANGE IN SET PRESSURE:  
Type No. 81512166 ASME Code Stamp UV Reset To 75 PSIG  
Inlet/Outlet 1.5 in. in. Mfr. S/N 86109676 New Capacity 731.5 SCFM  
Set Press 40 PSIG Tag No. SV 100 N

### RECORD OF PRETEST (AS FOUND)

Test Pressure \_\_\_\_\_ Pretest Sign-Off \_\_\_\_\_  
Blowdown \_\_\_\_\_ Tested by \_\_\_\_\_  
Tightness \_\_\_\_\_ Date \_\_\_\_\_  
Action \_\_\_\_\_ M&TE S/N \_\_\_\_\_

Trim No. T00

### RECORD OF PREVIOUS REPAIR

By Allied VALVE  
Model \_\_\_\_\_ Set \_\_\_\_\_  
Capacity \_\_\_\_\_ Date 9-14-98  
Unique # 286028-4-PAWR Stamp TESTED ONLY

### RECORD OF DISASSEMBLY & CLEANING

Item (s): "As Found Conditions"  
Cap and Lever  
Bonnet/Compr Scr: 1.969  
Spring/Steps  
Spindle/Disc  
Base/Nozzle  
Guide/Adj. Rings  
Other (Specify)

### RECORD OF CRITICAL INSPECTION & MACHINING

Comments	OK	Machine	Replace
	X		
	X		
Spring#	-		X
T.I.R.			X
Bore Dia.		<u>L98</u>	
	X		

### RECORD OF REPLACEMENT PARTS

Part No	Description	PO#
<u>04.4805.009</u>	<u>SOFT GOODS KIT</u>	<u>1732392.00</u>
<u>03.1062.002</u>	<u>Spring</u>	<u>1732392.00</u>

Notes

### RECORD OF TECHNICIAN SIGN-OFF

Repair Step Initials Date  
Nameplate MP 3-15-06  
Disassembly DA 3-23-06  
Cleaning DA 3-23-06  
Inspection DA 3-23-06  
Machining  
Parts DA 3-23-06  
Assembly DA 3-23-06  
Testing DA 3-24-06  
Final-Assembly DA 3-24-06  
VR Stamp (Y) N DA 3-24-06

### RECORD OF FINAL TEST RESULTS

Test Stand/Media TB 100B-Air  
Test Pressure 76  
Blowdown -  
Tightness 68  
M&TE S/N T6700

Repaired by  
**TYCO VALVES & CONTROLS**  
Bolingbrook, IL VR No. 396 & 500

TVCR- 5677R DATE 3-26

STYLE 81512166

SET PRESS 75

CAP 731.5 SCFM VR


### **3.5b3 – Old Pressure Vessel Engineering Note for PS1 Liquid Nitrogen Dewar**

Previous relief valve calculations are included.

**PRESSURE VESSEL ENGINEERING NOTE  
PER CHAPTER 5031**

Prepared by: Bruce Squires  
Preparation date: 31-Aug-92

1. Description and Identification  
Fill in the label information below:

This vessel conforms to Fermilab ES&H Manual Chapter 5031	
Vessel Title	<u>Liquid Nitrogen Dewar #14</u>
Vessel Number	<u>RD 0079</u>
Division/Section	
Vessel Drawing Number	<u>N/A</u>
Maximum Allowable Working Pressure (MAWP)	<u>75 psig + Full Vac.</u>
Working Temperature Range	<u>-320</u> °F <u>100</u> °F
Contents	<u>Liquid Nitrogen</u>
Designer/Manufacturer	<u>C.E. Howard Corporation</u>
Test Pressure (if tested at Fermi)	Acceptance Date: _____
<input checked="" type="checkbox"/> PSI, Hydraulic	<input type="checkbox"/> Pneumatic
Accepted as conforming to standard by 	
of Division/Section	<u>RD</u> Date: <u>11/9/92</u>

Obtain from Safety Officer

Document per Chapter 5034 of the Fermilab ES&H Manual

Actual signature required

NOTE: Any subsequent changes in contents, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review.

Reviewed by: Jay Mahajan AD-CRYO. Date: 11/5/92

Director's signature (or designee) if the vessel is for manned areas but doesn't conform to the requirements of the chapter.

\_\_\_\_\_  
Date: \_\_\_\_\_

Amendment No.:	Reviewed by:	Date:
_____	_____	_____
_____	_____	_____

Lab Property Number(s) : \_\_\_\_\_

Lab Location Code: PS1 (obtain from safety officer)

Purpose of Vessel(s) : To supply liquid nitrogen to the PS1 service building

Vessel Capacity/Size: 7000 liters Diameter: 84" Length: 167"

Normal Operating Pressure (OP) 24 - 27 psig

MAWP-OP = 48 PSI

List the numbers of all pertinent drawings and the location of the originals.


<u>Drawing #</u>	<u>Location of Original</u>
N/A	

2. Design Verification

Does the vessel(s) have a U stamp? Yes<sup>X</sup> No. If "Yes", fill out data below and skip page 3; if "No", fill out page 3 and skip this page.

Staple photo of U stamp plate below.

Copy "U" label details to the side



Copy data here:

C.E. Howard Corporation

Built for Cryo Sonics Inc.

Service: Liquid Nitrogen

Date: 1961 CODE: 1959

Design Presssure:

75 psig + Full Vac.


Test Pressure: 150 psig

Design Temp.:

-320°F to 100°F.I.T.

Serial Number: 489

Provide ASME design calculations in an appendix. On the sketch below, circle all applicable sections of the ASME code per Section VIII, Division I. (Only for non-coded vessels)



Summary of ASME Code

CALCULATION RESULT

(Required thickness or stress level vs. actual thickness calculated stress level)

Item	Reference ASME Code Section	
_____	_____	vs _____

3. System Venting Verification Provide the system schematic in the Appendix.

Is it possible to isolate the relief valves by a valve from the vessel?

Yes  No

If "Yes", the system must conform to code rules. Provide an explanation on the appended schematic. (An isolatable vessel, not conforming to code rule is non-compliant under this chapter.)

Is the relief cracking pressure set at or below the M.A.W.P.?

Yes  No  Actual setting 40 PSIG

(A "No" response violates this chapter.)

Is the pressure drop of the relief system at maximum anticipated flow such that vessel pressure never rises above the following? (UG 125)

Yes  No  110% of MAWP (one relief)  
 116% of MAWP (multiple reliefs)  
 121% of MAWP (unexpected heat source)

Provide test or calculational proof in the Appendix.

(Non-conforming pressure rises is non-compliant under this Chapter.)

List of reliefs and settings:

<u>Manufacturer</u>	<u>Model #</u>	<u>Set Pressure</u>	<u>Flow Rate</u>	<u>Size</u>
Anderson Greenwood	81S1216G	40 PSIG	442 SCFM Air	1-1/2 x 2"
Fike	CPV BT	105.33psig	N/A	1-1/2"
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

Does the primary relief device follow UG-129? Yes  No

(A "No" response is non-compliant under this chapter)

4. Operating Procedure

Is an operating procedure necessary for the safe operation of this vessel?

Yes  No  (If "Yes", it must be appended)

5. Welding Information

Has the vessel been fabricated in a non-code shop? Yes  No

If "Yes", append a copy of the welding shop statement of welder qualification (Procedure Qualification Record, PQR) which references the Welding Procedure Specification (WPS) used to weld this vessel.

6. Exceptional, Existing, Used and Unmanned Area Vessels

Is this vessel or any part thereof in the above categories?

Yes  No  Existing

If "Yes", follow the Engineering Note requirements for documentation and append to Note.

*Reviewer note: formerly vessel # RD3006 from TPL. Thm*

## APPENDIX A

### Venting Calculations for the Inner Vessel of the Liquid Nitrogen Dewar #14

#### INTRODUCTION

This appendix to the liquid nitrogen dewar #14 engineering note shows that the inner vessel is properly relieved in accordance with Section S-1.3 of the Compressed Gas Association (CGA) Standard and the Fermilab ES&H manual. This appendix is divided into five sections, namely, loss of vacuum, fire condition, failure of the pressure regulator on the pressure building coil, pumping overfill, and rupture disc capacity.

For conservative estimates of the values determined here, the nitrogen is considered as saturated at 44.35 psia. The ASME Code stamped relief valve will maintain the pressure in the inner vessel below 110% of the MAWP (CGA S-1.3 4.9.1.1) during operational emergencies (i.e. loss of vacuum, failure of the pressure regulator on the pressure building coil, and pumping overfill) and within 121% of the MAWP (CGA S-1.3 4.9.1.3) during fire conditions.

These calculations are based on the relief valve set at 40 psig, therefore, the relief can be set as high as the MAWP and still satisfy the requirements of CGA S-1.3 and the Fermilab ES&H manual. Because the relief valve can handle all possible failures, the rupture disc burst pressure is allowed to be as high as 150% of the MAWP (119 psig) per CGA S-1.3 and the Fermilab ES&H manual. The lowest recommended burst pressure is 125% of the relief valve setting based on data from Fike Metal Products.

#### LOSS OF VACUUM

According to paragraph 4.9.1.1 of CGA S-1.3, the minimum required relieving capacity for a loss of vacuum is determined by [5]

$$Q_a = \frac{590 - T}{4 (1660 - T)} G_i U A \quad (1)$$

where

$$G_i = \frac{73.4 (1660 - T)}{L_f C} \sqrt{\frac{Z T}{M}} = 9.36 \quad (2)$$

For  $A = 405 \text{ ft}^2$ , the required stamped capacity of the valve is 12.5 SCFM air. The stamped capacity of the 1-1/2" AGCO set at 40 psig, which serves as the relief valve, is 442 SCFM air and exceeds the required capacity.

#### FIRE CONDITION

The requirements of paragraph 5.3.5 of CGA S-1.3 state that the required relieving capacity for a fire condition is [6]

$$Q_a = G_i U A^{0.82} \quad (3)$$

For this dewar, the required stamped capacity of the relief must be at least 103 SCFM air. The AGCO relief valve exceeds this value.

#### FAILURE OF THE PRESSURE REGULATOR ON THE PRESSURE BUILDING COIL

CGA S-1.3 4.9.1.1 states that for all operational emergencies, the reliefs should provide adequate venting at 110% of the MAWP. If the pressure regulator on the pressure building coil failed in the open position, the flow rate would be determined by the differential driving pressure (head of liquid nitrogen) and the restriction caused by the pressure building loop. For simplification, just the flow caused by the greatest restriction will be considered (the liquid supply piping, fittings, valves, and regulator). If there is 80" of liquid nitrogen above the coil, the differential driving pressure would be

$$\Delta P = \rho_l \frac{g}{g_c} \frac{H}{C_1} \quad (4)$$

and the resulting flow rate would be [3]

$$W = C_2 \pi \sqrt{\frac{\Delta P \rho_l g_c d^4}{8 K}} \quad (5)$$

The value of  $K/d^4$  is calculated for each part of the restriction and added thus obtaining

$$\frac{K}{d^4} = 344.7 \text{ in}^{-4}$$

This leads to a flow rate of 1034 lbm/hr ( $\Delta P = 2.18$  psid) which is converted to 127 SCFM air equivalent by [4]

$$Q_a = \frac{13.1}{60} W \frac{356}{C} \sqrt{\frac{Z T}{M} \frac{28.97}{520}} \quad (6)$$

Since this is below the relieving capacity of the relief valve, the pressure in the dewar will remain below 110% of the MAWP.

#### PUMPING OVERFILL

CGA S-1.3 4.8 states that if the storage container is being filled by pumping equipment in excess of the discharge capacity of the relief devices and capable of producing pressures in excess of the MAWP of the container, precautions should be taken to prevent the development of pressure in the container in excess of 116% of the MAWP for multiple relief valves or 110% of the MAWP for a single relief valve (see CGA S-1.3 4.9.1.1).

The maximum flow rate of delivery is controlled by two factors, the fill line flow resistance and the pumping characteristics of the delivery trailer. The pumping curve for the pumping head was obtained from Liquid Carbonics and a third order polynomial was derived from this curve and is as follows:

$$\Delta P_{\text{pump}} = -1.432595 \cdot 10^{-5} \cdot Q^3 + 5.157343 \cdot 10^{-4} \cdot Q^2 - 4.560995 \cdot 10^{-2} \cdot Q + 222.2336 \quad (7)$$

In order to determine the relieving capacity required by an overfill, the American Petroleum Institute (API) recommends determining the flow area required for the liquid portion of the flow and the area for the vapor portion of the flow separately and then adding these two areas resulting in the minimum orifice area required (API 521-3.17.1).

The mass fraction of the liquid that will become vapor when passing through the relief valve is determined by the equation [4]

$$x = \frac{h_{l1} - h_{l2}}{h_{v2} - h_{l2}} \quad (8)$$

where  $h_{l1} = -42.48$  Btu/lbm (saturated liquid at 44.35 psia)  
 $h_{l2} = -52.37$  Btu/lbm (saturated liquid at 14.7 psia)  
 $h_{v2} = 33.14$  Btu/lbm (saturated vapor at 14.7 psia)

Thus, the mass fraction that vaporizes is 0.1156. The orifice area required is determined by [1]

$$A = \frac{x W}{C K_d K_b P} \sqrt{\frac{Z T}{M}} + \frac{(1-x) Q}{38 K_w K_v K_d K_p} \sqrt{\frac{G_f}{\Delta P}} \quad (9)$$

where the first part is the area required for vapor flow and the second is that required for the liquid flow and

$$W = \rho_l Q C_3 \quad (10)$$

The area of the AGCO relief is 0.503 in<sup>2</sup>.

The flow restrictions used are that of the fill line and its components and the piping between the dewar and the relief valve. Preliminary calculations indicated that the relief valve could not maintain the pressure in the dewar below 110% of the MAWP. Therefore, a flow restricting orifice for the fill line was selected. Refer to Appendix B for a summary of the flow restrictions used in this calculation.

The pressure drop for the piping and components is determined by [3]

$$\Delta P = \frac{\rho_l K}{C_4^2} \frac{8 Q^2}{\pi^2 g_c d^4} \quad (11)$$

For the orifice plate, the set of equations that determine the flow rate is [6]:

$$W = S N D^2 F_a F_m F_c F_p \sqrt{G_f h_w} \quad (12)$$

where

$$S = 0.58925 \beta^2 + 0.2725 \beta^3 - 0.825 \beta^4 + 1.75 \beta^5$$

Solving equations 7 through 12 simultaneously has the following results:

Liquid nitrogen flow rate	77.5	gpm (29330 lbm/hr)
Pressure in delivery truck	30.0	psig
Delivery pump boost in pressure	215.1	psid
Pressure drop over orifice	153.6	psid (4252 in. H <sub>2</sub> O)
Pressure drop over fill line	8.1	psid
Pressure in dewar	83.4	psig (109.4% MAWP)
Pressure drop over vent to relief valve	2.0	psid
Pressure at relief valve	81.4	psig

This shows that the dewar pressure for maximum flow rate of delivery is less than 110% of the MAWP.

#### RUPTURE DISC CAPACITY

The capacity of the rupture disc is obtained through the following equation:

for gas [1]

$$W = A C K_d P \sqrt{\frac{M}{Z T}} \quad (13)$$

and  $Q_a$  from equation (6).

At the burst pressure of 105.33 psig, the gas flow rate is 3024 SCFM air.

Table 1. REQUIRED VENTING CAPACITIES			
Condition	Air Equivalent Flow Rate, $Q_a$ (SCFM air)		
	required	installed	
		safety relief valve	rupture disc
Loss of Vacuum	12.5	442	3024
Fire	103	442	3024
Pressure Building			
Regulator Failure	128	442	3024

## NOMENCLATURE

A	area (in <sup>2</sup> except in (1) and (3) where it is ft <sup>2</sup> )
C	coefficient based on $k = 356$
C <sub>1</sub>	conversion factor = $1728 \text{ in}^3/\text{ft}^3$
C <sub>2</sub>	conversion factor = $300 \text{ (ft/hr)} / \text{(in/s)}$
C <sub>3</sub>	conversion factor = $8.02 \text{ (ft}^3/\text{hr)} / \text{(gal/min)}$
C <sub>4</sub>	conversion factor = $37.4 \text{ (gal/min)} / \text{(ft}^2 \text{ in/sec)}$
d	diameter (inches)
D	fill line pipe size = 1.682 inches
f	fanning friction factor
F <sub>a</sub>	Correction factor for contraction of orifice = 0.9968
F <sub>c</sub>	Reynold's number correction factor = 1
F <sub>m</sub>	Manometer correction factor = 1
F <sub>p</sub>	Correction Factor for the Compressibility of the liquid = 1
g	gravitational acceleration = $32 \text{ ft/s}^2$
g <sub>c</sub>	gravitational constant = $32 \text{ ft/s}^2 \text{ lbm/lbf}$
G <sub>f</sub>	specific gravity at flowing conditions = 0.756
G <sub>i</sub>	gas factor
H	height of LN <sub>2</sub> = 80 in
h <sub>w</sub>	pressure drop expressed in inches H <sub>2</sub> O
k	ratio of specific heats = $C_p/C_v = 1.4$
K	flow resistance = $fL_p/d$
K <sub>b</sub>	correction factor due to back pressure = 1
K <sub>d</sub>	coefficient of discharge = 0.816 for relief valve = 0.62 for rupture disc
K <sub>p</sub>	capacity correction factor = 1
K <sub>perlite</sub>	thermal conductivity of perlite (Btu in/hr ft <sup>2</sup> °F) (0.4 for mean temperature of 100°F and 0.7 for mean temperature of 450°F)
K <sub>w</sub>	correction factor due to back pressure = 1
K <sub>v</sub>	correction factor due to viscosity = 1
L <sub>f</sub>	latent heat at flowing conditions = 78.68 Btu/lbm
L <sub>p</sub>	length of pipe (in)
M	molecular weight = 28
N	constant in equation 12 = 2835
P	pressure (psia)
P <sub>m</sub>	Maximum Allowable Working Pressure (psid)

Q	volumetric flow rate (gpm)
Q <sub>a</sub>	air equivalent flow rate (SCFM)
S	factor in equation 12
t	thickness (inches)
t <sub>ins</sub>	thickness of insulation = 8.75 inches
T	temperature = 158.7 R
U	thermal conductance = $\frac{K_{\text{perlite}}}{t_{\text{ins}}}$
W	mass flow rate (lbm/hr)
Z	compressibility factor = 1
ΔP	differential pressure (psid)
β	ratio of orifice diameter to pipe diameter = 0.316
ρ <sub>l</sub>	density of liquid = 47.19 lbm/ft <sup>3</sup>

## REFERENCES

- [1] "API Recommended Practice 520", Guide for Inspection of Refinery Equipment: Chapter XVI- Pressure Relieving Devices, American Petroleum Institute, Washington D.C., December 1976. appendix C
- [2] ASME Boiler and Pressure Vessel Code Section VIII; Rules for Construction of Pressure Vessels, Division 1, ASME, New York, 1986 edition. part UG
- [3] Crane Co., Flow of Fluids Through Valves, Fittings, and Pipe, Technical Paper No. 410, Crane Co., King of Prussia, PA, 24th printing. p. 3-4
- [4] Kropschot,R.H., Birmingham,B.W., and Mann,D.B., Technology of Liquid Helium, NBS Monograph 111, October 1968. p. 229,288
- [5] "Pressure Relief Device Standards, Part 3- Compressed Gas Storage Containers", Compressed Gas Association, CGA S-1.3, New York, 4th printing, 1980.
- [6] Spink, L.K., Principles and Practice of Flow Meter Engineering, The Foxboro Company, Foxboro, MA, 9th edition, 1978

## APPENDIX B

Calculations of the Flow Restrictions  
for Appendix AGeneral

$\frac{K}{d^4}$  is used as a general flow restriction parameter that can be added regardless of the pipe size of the component. Justification of this can be seen by observing that Crane's technical paper 410 states that in order to add K values, all of the K values must be converted to the same pipe size. This is done by dividing K by the fourth power of its pipe size and multiplying the result by the fourth power of the new pipe size. Since the equations will divide this later term out, I have chosen to remove this redundant step to arrive at the same answer.

The values calculated in this appendix are based on Crane's technical paper 410. The following equations and values are taken from Crane's for calculating  $\frac{K}{d^4}$ :

$$K = \frac{f L}{d}$$

$$\frac{K}{d^4} = \frac{891}{Cv^2}$$

Pipe	f	I.D
1/2" sch.40s	0.027	0.622"
1-1/2" sch.10s	0.020	1.682"
2" sch.10s	0.019	2.157"

Pressure Building Regulator

Item	$\frac{K}{d^4}$
2 - 90° elbows (1/2" sch.40s) (K = 30f)	10.8
3 - tee branch (1/2" sch.40s) (K = 60f)	32.5
100 inches straight pipe (1/2" sch.40s)	29
Pressure Building Regulator (Cv = 3.2)	87
2 - Cryolab Globe Valve (Cv = 3.1)	185.4
Total	344.7

Fill Line Restriction

The calculation for the fill line does not include all of the straight pipe that may be installed. It only includes the minimum needed for a general installation of this dewar. For this particular installation at PS1, the fill line will be up to 10 feet longer. The contributions are as follows:

Item	$\frac{K}{d^4}$
Cryolab Globe Valve (Cv = 30)	0.990
Check Valve (K = 50 f)	0.125
3 - 90° elbows (1-1/2" sch 10s long radius) (K = 14f)	0.105
1 - tee branch (1-1/2" sch 10s) (K = 60f)	0.150
136.5" straight pipe (1-1/2" sch 10s)	0.213
Total	1.583

Vent Piping for Safety Relief Valve

Item	$\frac{K}{d^4}$
<u>Piping Inside Vacuum Jacket</u>	
90° long curve pipe (2" sch.10s) (K = 44f)	0.039
2 - 90° elbows (2" sch.10s long radius) (K = 15f)	0.026
1 - tee branch (2" sch.10s) (K = 60f)	0.053
78 inches straight pipe (2" sch.10s)	0.032
Inside Subtotal	0.150
<u>Piping Outside Vacuum Jacket</u>	
1 - tee branch (2" sch.10s)(K = 60f)	0.053
1 - 90° elbow (2" sch.10s long radius) (K = 15f)	0.013
1 - reducer from 2 to 1-1/2 IPS	0.003
30 inches straight pipe (2" sch.10s)	0.012
1 - tee run (1-1/2" sch.10s) (K = 14f)	0.035
AGCO Safety Selector (Cv = 90)	0.110
12 inches straight pipe (1-1/2" sch.10s)	0.018
Outside Subtotal	0.224
Total for Safety Relief Valve Piping	0.394



# FERMILAB ENGINEERING NOTE

SECTION  
RD/MSD

PROJECT  
PS1

SERIAL - CATEGORY

PAGE  
1 of 1


SUBJECT

## Liquid Nitrogen Dewar #14 at PS1

NAME  
B. Squires

DATE  
01-Sep-92

REVISION DATE



### **3.5b4 – Vacuum Vessel Engineering Note for PS1 Liquid Nitrogen Dewar**

Relief and collapse calculations included.

EXHIBIT A-1

Vacuum Vessel Engineering Note  
(per Fermilab ES&H Manual Chapter 5033)

Prepared By Bruce Squires Date 1-Sept-92 Div/Sec RD/MSD  
Reviewed By Jerry Whelan AD-CRYO Date 11/5/92 Div/Sec AD-CRYO  
Div/Sec Head Richard Date 11/10/92 Div/Sec RD

1. Identification and Verification of Compliance

Fill in the Fermilab Engineering Conformance Label information below:

This vessel conforms to Fermilab ES&H Manual Chapter 5033

Vessel Title Liquid Nitrogen Dewar # 14  
Vessel Number ~~RD 0079~~ RDV 6009  
Vessel Drawing Number N/A  
Internal MAWP ~ 1 psig  
External MAWP > 30 psid  
Working Temperature Range 120 OF \_\_\_\_\_ OF  
Designer/Manufacturer C.E. Howard Corporation  
Date of Manufacture 1961 {CODE: 1959}  
Acceptance Date Sept 1, 1992

Director's signature (or designee) if vessel is for manned area and requires an exception to the provisions of this chapter.

Amendment No.: \_\_\_\_\_ Reviewed By: \_\_\_\_\_ Date: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Laboratory location code PS1  
Laboratory property number \_\_\_\_\_  
Purpose of vessel Contain LN<sub>2</sub> Pressure Vessel in order  
to provide insulation

List all pertinent drawings

Drawing No.:

Location of Original:

N/A  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

2. Design Verification

Provide design calculations in the Note Appendix.

3. System Venting Verification

Can this vessel be pressurized either internally or externally? [ ] Yes [X] No  
If yes, to what pressure? There are no means to internally pressurize this vessel

List all reliefs and settings. Provide a schematic of the relief system components and appropriate calculations or test results to prove that the vessel will not be subjected to pressures greater than 110% beyond the maximum allowable internal or external pressure.

Manufacturer	Relief	Pressure Setting	Flow Rate	Size
_____	<u>Parallel Plate</u>	<u>~0.5 psig</u>	<u>N/A</u>	<u>3" (7.07 in<sup>2</sup>)</u>
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

4. Operating Procedure Section

Is an operating procedure necessary for the safe operation of this vessel?

Yes \_\_\_\_\_ No X (If "Yes", it must be appended)

Is a testing procedure necessary for the safe acceptance testing (proof \_\_\_\_\_ testing) of this vessel? [ ] Yes [X] No

If yes, the written procedure must be approved by the Division Head \_\_\_\_\_ prior to testing and supplied with this Engineering Note.

5. Welding Information

Has the vessel been fabricated in a Fermilab shop? [ ] Yes  No

*If "Yes," append a copy of the welding shop statement of welder qualification.*

6. Exceptional, Existing, Used and Non-Manned Area Vessels

Is this vessel or any part thereof in the above categories?

Yes  No  *Existing*

*If "yes" follow the Engineering Note requirements for documentation and append to note.*

*Reviewer note : Formerly vessel # RD3006 from TPL.*

Calculations on the  
Vacuum Vessel of the Liquid Nitrogen Dewar #14

This appendix shows that the vacuum vessel is adequately relieved and that it meets the specifications of Fermilab ES&H 5033. The calculations are divided into two sections, specifically, relief sizing and vessel collapse pressure.

#### RELIEF SIZING

Fermilab ES&H 5033 states that "The relief calculation should take in account a failure of any pipe or vessel inside the vacuum vessel at the maximum system flow rate of that pipe or vessel." I believe that the intent of this statement is for any credible failure. The only credible failure for this case would be a crack in a pipe which cannot be accurately estimated. The Compressed Gas Association (CGA) has a standard for sizing the relief and this is the criterion which will be used to check on the sizing of this relief.

CGA-341 6.4.2 requires that the discharge area of the relief to be 0.00024 square inches per pound of water capacity of the liquid container (inner vessel). The water capacity of the inner vessel can be estimated by the following equation [1]

$$V = \frac{\pi D_i^2}{4 C_1} \left[ L_c + 1 \frac{1}{3} KD \right] \quad (1)$$

The volume is approximately 2080 gallons which leads to a required discharge area of 4.14 square inches (water density 8.288 lbm/gal.). The relief on this vacuum vessel is a parallel plate with a discharge area of 7.07 square inches. Therefore, the relief surpasses CGA requirements.

#### VESSEL COLLAPSE PRESSURE

The Fermilab Engineering Standard requires that a vacuum vessel have a collapse pressure of at least 30 psid. For the cylindrical portion of the vessel, the collapsing pressure is determined by [2]

$$P_c = \frac{2.6 E \left[ \frac{t_c}{D} \right]^{2.5}}{\frac{L}{D} - 0.45 \sqrt{\frac{t_c}{D}}} \quad (2)$$

and the collapsing pressure of a head is [2]

$$P_c = 0.25 E \left[ \frac{t_h}{R} \right]^2 \quad (3)$$

The Code specifies that the head radius must be no less than the diameter of the cylindrical portion of the vessel. For these calculations, the head radius is assumed to be equal to the diameter of the cylinder. For this vessel, the collapse pressure for the cylinder is 81 psid and that for the head is 64 psid.

In order for the result of equation 2 to hold true, the stiffening rings must meet the required moment of inertia as stated by CGA-341

$$I = \frac{1.05 D^3 L}{E} \quad (4)$$

From this equation, the required moment of inertia is  $0.86 \text{ in}^4$ . Figure 2 shows the dimensions of the stiffening ring. The moment of inertia of this stiffener about its centroid is  $1.86 \text{ in}^4$ . This exceeds the required moment of inertia, therefore the result of equation 2 is valid.




Figure 1. Outer Vessel of the Liquid Nitrogen Storage Dewar #14




Figure 2. Cross sectional dimensions of the stiffening ring.

Liquid Nitrogen Storage Dewar #14				
	Cylinder ID (inches)	Cylinder OD (inches)	Cylinder Thickness (inches)	Head Thickness (inches)
Inner Vessel	---	66.00	---	---
Outer Vessel	83.50	84.00	0.25	0.25

#### NOMENCLATURE

- $C_1$  conversion factor = 231 in<sup>3</sup>/gallon  
 $D$  outside diameter of outer shell = 84 inches  
 $D_i$  inner diameter of inner vessel ~ 65.5 inches  
 $E$  modulus of elasticity =  $29 \times 10^6$  psi  
 $I$  required moment of inertia of the stiffener itself about a centroidal axis parallel to the outer shell axis, in<sup>4</sup>  
 $KD$  depth of the head of the inner vessel ~ 11 inches  
 $L$  largest distance between stiffening ring centers ~ 40 inches  
 (heads are considered as stiffening rings located one third of the head depth from the head tangent line)  
 $L_c$  length of the cylindrical portion of the inner vessel ~ 128 inches  
 $P_c$  collapse pressure, psid  
 $R$  inside dish radius of head = 84 inches  
 $t_c$  thickness of the cylindrical portion of the vacuum jacket = 0.25 inches  
 $t_h$  thickness of the head of the vacuum jacket = 0.25 inches  
 $V$  volume of the vessel, in<sup>3</sup>

#### REFERENCES

- [1] Chicago Bridge and Iron Company, "Tables-Formulas", Bulletin No.594, 1977.  
 [2] "Standard for Insulated Cargo Tank Specification for Cryogenic Liquids", Compressed Gas Association, CGA 341, Arlington Virginia, 3rd edition, 1987.

### **3.5b5 – Pressure Vessel Engineering Note for Bo**

See 4.1a for relief valve calculations and 4.1aa for supporting relief valve calculation documentation.

Relief valve certifications are included at end of pressure vessel engineering note along with the Form U-1A Manufacturer's Data Report for Pressure Vessels.

**PRESSURE VESSEL ENGINEERING NOTE**

**PER CHAPTER 5031**

Prepared by: Terry Tope \_\_\_\_\_  
Preparation date: 4.10.08 \_\_\_\_\_

1. Description and Identification  
Fill in the label information below:

This vessel conforms to Fermilab ES&H Manual Chapter 5031

Vessel Title FLARE microTPC Cryostat \_\_\_\_\_

Vessel Number PPD#10101 \_\_\_\_\_

Vessel Drawing Number D-13109101 \_\_\_\_\_

Maximum Allowable Working Pressures (MAWP):  
Internal Pressure 35 psig \_\_\_\_\_  
External Pressure 15 psig \_\_\_\_\_

Working Temperature Range -320 \_\_\_ °F 100 \_\_\_ °F

Contents Liquid Argon \_\_\_\_\_

Designer/Manufacturer Chart, Inc. \_\_\_\_\_

---

Test Pressure (if tested at Fermi) Acceptance Date: \_\_\_\_\_

\_\_\_\_\_ PSIG, Hydraulic \_\_\_\_\_ Pneumatic \_\_\_\_\_

Accepted as conforming to standard by \_\_\_\_\_

---

of Division/Section \_\_\_\_\_ Date: \_\_\_\_\_

← Obtain from Division/Section Safety Officer

← Document per Chapter 5034 of the Fermilab ES&H Manual

← Actual signature required

NOTE: Any subsequent changes in contents, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review.

Reviewed by: \_\_\_\_\_ Date: \_\_\_\_\_

Director's signature (or designee) if the vessel is for manned areas but doesn't conform to the requirements of the chapter.

\_\_\_\_\_ Date: \_\_\_\_\_

\_\_\_\_\_ Date: \_\_\_\_\_

ES&H Director Concurrence  
Amendment No.:

Reviewed by:

Date:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Lab Property Number(s): 099937 \_\_\_\_\_  
 Lab Location Code: 502 \_\_\_\_\_ (obtain from safety officer)  
 Purpose of Vessel(s): Test contamination effects of proposed LArTPC  
 materials on ultra high purity liquid argon. \_\_\_\_\_

Vessel Capacity/Size: 250 liter\_\_ Diameter: 22 inches Length: 37.5 inches  
 Normal Operating Pressure (OP) 20 psig \_\_\_\_\_  
 MAWP-OP = 15 \_\_\_\_\_ PSI

List the numbers of all pertinent drawings and the location of the originals.

<u>Drawing #</u>	<u>Location of Original</u>
D-13109101 _____	Chart Inc., 1300 Airport Drive, _____ Ball Ground GA 30107 _____
_____	_____
_____	_____
_____	_____


2. Design Verification

Is this vessel designed and built to meet the Code or "In-House Built" requirements?  
 Yes X No \_\_\_\_\_.

If "No" state the standard that was used \_\_\_\_\_.  
 Demonstrate that design calculations of that standard have been made and that other requirements of that standard have been satisfied.  
 Skip to part 3 "system venting verification."

Does the vessel(s) have a U stamp? Yes X No \_\_\_\_\_. If "Yes", complete section 2A; if "No", complete section 2B.

A. Staple photo of U stamp plate below.  
 Copy "U" label details to the side



Copy data here:  
 NAT'L. BD. NO. \_\_\_\_\_  
 168160 \_\_\_\_\_  
 CERTIFIED BY \_\_\_\_\_  
 CHART, INC. \_\_\_\_\_  
 RT-2 \_\_\_\_\_  
 MODEL: DEWAR R \_\_\_\_\_  
 M.A.W.P.: 35 P.S.I. @ 100 °F \_\_\_\_\_  
 M.D.M.T. -320 °F @ 35 P.S.I. \_\_\_\_\_  
 MAEWP 15 psi @ 100 °F \_\_\_\_\_  
 2005 S/N CEGRZ05L101 \_\_\_\_\_  
 DUPLICATE \_\_\_\_\_



3. System Venting Verification Provide the vent system schematic.

Does the venting system follow the Code UG-125 through UG-137?

Yes  No

Does the venting system also follow the Compressed Gas Association Standards S-1.1 and S-1.3?

Yes  No

A "no" response to both of the two preceding questions requires a justification and statement regarding what standards were applied to verify system venting is adequate.

List of reliefs and settings:

<u>Manufacturer</u>	<u>Model #</u>	<u>Set Pressure</u>	<u>Flow Rate</u>	<u>Size</u>
Anderson Greenwood	83SF1216F	35 psig	227 SCFM Ar	1.5" x 2.0"
BS&B (rupture disc)	JRS	55 psig	1066 SCFM Ar	1.5"
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

4. Operating Procedure

Is an operating procedure necessary for the safe operation of this vessel?

Yes  No  (If "Yes", it must be appended)

5. Welding Information

Has the vessel been fabricated in a non-code shop? Yes  No

If "Yes", append a copy of the welding shop statement of welder qualification (Procedure Qualification Record, PQR) which references the Welding Procedure Specification (WPS) used to weld this vessel.

6. Existing, Used and Unmanned Area Vessels

Is this vessel or any part thereof in the above categories?

Yes  No

If "Yes", follow the requirements for an Extended Engineering Note for Existing, Used and Unmanned Area Vessels.

7. Exceptional Vessels

Is this vessel or any part thereof in the above category?

Yes  No

If "Yes", follow the requirements for an Extended Engineering Note for Exceptional Vessels.

**THIS VESSEL CONFORMS TO FERMILAB ES&H MANUAL  
CHAPTER 5031**

Vessel Title \_\_\_\_\_

Vessel Number \_\_\_\_\_

Vessel Drawing Number \_\_\_\_\_

Maximum Allowable Working Pressures (MAWP):

Internal Pressure \_\_\_\_\_

External Pressure \_\_\_\_\_

Working Temperature Range \_\_\_\_\_ °F \_\_\_\_\_ °F

Contents \_\_\_\_\_

Designer \_\_\_\_\_

Test Pressure (if tested at Fermi) \_\_\_\_\_ DATE \_\_\_\_/\_\_\_\_/\_\_\_\_

\_\_\_\_\_ PSIG, Hydraulic \_\_\_\_\_ Pneumatic \_\_\_\_\_

Accepted as conforming to standard by \_\_\_\_\_

Of Division/Section \_\_\_\_\_

NOTE: Any subsequent changes in content, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review and test.

Figure 2. Sample of sticker to be completed and be placed on vessel.

**FORM U-1A MANUFACTURER'S DATA REPORT FOR PRESSURE VESSELS**  
**(Alternative Form for Single Chamber, Completely Shop-Fabricated Vessels Only)**  
**As Required by the Provisions of the ASME Code Rules, Section VIII, Division 1**

1. Manufactured and certified by CHART, Inc., 1300 Airport Drive, Ball Ground GA 30107  
 (Name and address of Manufacturer)
2. Manufactured for STOCK  
 (Name and address of purchaser)
3. Location of installation Unknown  
 (Name and address)
4. Type Vertical / Tank CEGRZ05L101-102 D-13109101 168160-168161 2005  
 (Horiz. or vert., tank) (Mfg.'s serial No.) (CRN) (Drawing No.) (Nat'l. Bd. No.) (Year built)

5. The chemical and physical properties of all parts meet the requirements of material specifications of the ASME BOILER AND PRESSURE VESSEL CODE. The design, construction, and workmanship conform to ASME Rules, Section VIII, Division 1 **2004**

- to A04 N/A Low Temp / UHA-51 (a)  
 Addenda (Date) Code Case Nos. Special Service per UG-120 (d)
6. Shell: SA-240 T304 .090 NOM 0.0 1 ft. 10.24 in. 3 ft. 1.5 in.  
 (Matl. (Spec. No., Grade)) (Nom. Thk. (in.)) (Corr. Allow. (in.)) Dia. I.D. (ft. & in.) Length (overall) (ft. & in.)
7. Seams: TYPE 3 NONE 60 N/A N/A TYPE 3 NONE 1  
 Long. (Welded, Dbl., Sngl., Lap, Butt) R.T. (Spot or Full) Eff. (%) H.T. Temp. (°F) Time (hr) Girth (welded, Dbl., Sngl., Lap, Butt) R.T. (Spot, Partial, or Full) No. of Courses
8. Heads: (a) Matl. N/A (b) Matl. SA-240 T 304  
 (Spec. No., Grade) (Spec. No., Grade)

	Location (top, Bottom, Ends)	Minimum Thickness	Corrosion Allowance	Crown Radius	Knuckle Radius	Elliptical Ratio	Conical Apex Angle	Hemispherical Radius	Flat Diameter	Side to Pressure (Convex or Concave)
(a)	Top	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
(b)	Bottom	0.095	0.0	22"	1.375"	N/A	N/A	N/A	N/A	Concave

If removable, bolts used (describe other fastenings) BOLTS ARE NOT FURNISHED  
 (Matl., Spec. No., Gr., Size, No.)

9. MAWP 35 15 psi at max. temp. 100 100 °F.  
 (internal) (external) (internal) (external)  
 Min. design metal temp. -320 °F at 35 psi. Hydro, pneu., or COMB. test pressure 53 psi.

10. Nozzles, inspection and safety valve openings:

Purpose (Inlet, Outlet, Drain)	No.	Diam. or Size	Type	Matl.	Nom. Thk.	Reinforcement Matl.	How Attached	Location
INLET/ OUTLET	1	22.09" ID	FLANGE	SA240 T304	1"	None	UW-13.2(h)	N/A

11. Supports: Skirt No Lugs N/A Legs N/A Other NONE Attached N/A  
 (Yes or No) (No.) (No.) (Describe) (where and How)

12. Remarks: Manufacturer's Partial Data reports properly identified and signed by Commissioned Inspectors have been furnished for the following items of the report: N/A

(Name of part, item number, Mfg.'s name and identifying stamp)

Vacuum Jacketed Dewar. Low Temperature Service. Design Pressure is 35 PSI.  
Impact test Exempt Per UHA51 (d) (1) (a). Hydro Test Is Vertical For Noncorrosive Service.

**CERTIFICATION OF SHOP COMPLIANCE**

We certify that the statements made in this report are correct and that all details of design, material, construction, and workmanship of this vessel conform to the ASME Code for Pressure Vessels, Section VIII, Division 1. "U" Certificate of Authorization No. 19.262 expires 03/14, 2008.

Date 12/1/05 Co. name CHART, Inc. Signed \_\_\_\_\_  
 (Manufacturer) (Representative)

**CERTIFICATE OF SHOP INSPECTION**

Vessel constructed by CHART, Inc. at Canton, GA  
 I, the undersigned, holding a valid commission issued by the National Board of Boiler and Pressure Vessel Inspectors and/or the State or Province of Georgia and employed by OneBeacon America Insurance Company


have inspected the component described in this Manufacturer's Data Report on 12/1, 2005, and state that, to the best of my Knowledge and belief, the Manufacturer has constructed this pressure vessel in accordance with the ASME Code, Section VIII, Division 1. By signing this certificate neither the inspector nor his employer makes any warranty, expresses or implied, concerning the pressure vessel described in this Manufacturer's Data Report. Furthermore, neither the inspector nor his employer shall be liable in any manner for any personal injury or property damage or a loss of any kind arising from or connected with this inspection.

Date 12/13/05 Signed \_\_\_\_\_ Commissions NB# : 12124A GA #538  
 (Authorized Inspector) (Nat'l Bd. (include endorsements), State, Prov. and No.)

ASME Manufacturer's Certificate of Conformance for Pressure Relief Valves  
Form UV-1 (Section VIII)

1. Manufactured by: Anderson Greenwood Crosby - Stafford, Texas

2. Table of Code symbol stamped items:

ID (Serial No)	Date	NB Cert #	QTY	Type	Size, (NPS)	Set Pressure,psig (Nameplate)	Capacity	Test Fluid	Date	CI Name	CI Signature
07-28910	06/20/07	01089	1	83SF1216-F	1 1/2	00035 PSIG	244 SCFM	AIR	SEE ID#	TRUST	

3. Remarks: L59379.001


CERTIFICATE OF SHOP COMPLIANCE

By the signature of the Certified Individual (CI) noted above, we certify that the statements made in this report are correct and that all details for design, material, construction and workmanship of the pressure relief devices conform with the requirements of Section VIII, Division 1 of the ASME Boiler and Pressure Vessel Code.

UV Certificate of Authorization No. 3793 Expires December 31, 2007

Date: 6/23/07

Signed:



(Responsible Representative)

Name: Anderson Greenwood Crosby - Stafford, Texas  
(Manufacturer)

TYCO VALVES & CONTROLS LP  
STAFFORD DIVISION  
ANDERSON GREENWOOD CROSBY

SALES ORDER NO: L69379.001

F U N C T I O N A L T E S T R E P O R T

DATE PRINTED: 06/20/07

PAGE: 1

CUSTOMER: TYCO VALVES & CONTROLS-S  
PO NUMBER: 1737477-00

SHIP TO CUST: FERMILAB  
PRODUCT NUMBER: 830SSSF12..16..F00035GBBS  
PART NBR: L69379.001

MARKS: 575614

GAUGE NO: *A60-07*

SERIAL NO	TAG	PRIMARY PRESSURE PARTS TEST	BELLOWS OR O-RING TEST	SECONDARY PRESSURE ZONE TEST	ASSY TECH	NAMEPLATE SET <i>35</i>	SPECIFIED RESEAT <i>28</i>	LEAK TEST <i>30</i> TIME <i>1 min.</i>	FINAL TECH
07-28910		<i>ASME</i>		<i>30</i>	<i>Q</i>	<i>36</i>	<i>1 TURN</i>	<i>0</i>	<i>Q</i>

TRACEABILITY REQUIREMENTS - HEAT/CODE NUMBERS FOR TRACEABLE COMPONENTS

SERIAL NO	BODY/CYLINDR	BASE	BONNET	FLANGE IN	FLANGE OUT	NOZZLE	STUB IN	STUB OUT	DISC
07-28910									

CUSTOMER/DATE  
WITNESSED:

UNITS OF MEASURE			TEST MEDIUM		
UNITS	PRES.	VAC.	AIR	H2O	STEAM
PSIG	<i>✓</i>		<i>✓</i>		
"WC					

VERIFIED AND  
Inspected By:  
*[Signature]*  
JUN 23 2007

SDJDE FORMS-GRABAR, FORMAT=FMT2C, MODIFY=CME2, END;

### **3.5c - PAB LN2 Dewar Compliance with Fermilab ES&H 5032.1TA**

#### 4.0 VALVES AND INSTRUMENTATION

##### A) MANDATORY PROVISIONS

- 1.) *Reliable means of measuring the liquid level in the dewar.*  
The dewar is equipped with a full trycock valve (MV-094-N) for measuring liquid level. The dewar is also equipped with a Barton level gauge (DPI-100-N) that has been recently calibrated by the Fermilab PAB Calibration Shop.
- 2.) *Pressure gauge to sense ullage pressure.*  
PI-100-N indicates the dewar pressure.
- 3.) *Fill & withdrawal valve(s).*  
MV-92-N provides fill isolation. MV-100-N allows liquid to flow into PAB while MV-93-N allows the venting of vapor.
- 4.) *Required relief devices.*  
SV-99-N and SV-100-N (75 psig set point) can individually protect the dewar from all overpressure scenarios except for filling. PCV-70-N protects the dewar from over filling by shutting the fill line when the dewar vapor space pressure exceeds 75 psig. The dewar is also equipped with two rupture discs designed to open at 105 psig.
- 5.) *Means, other than the required relief devices, to vent the vessel, i.e., blow down valve.*  
MV-93-N vents the dewar vapor space to ambient as does RV-090-N.
- 6.) *The MAWP of all valves and instruments must be greater than or equal to the maximum pressure to which they can be exposed.*  
The Valve and Instrument list tabulates the maximum pressure for all components. All components have maximum allowable pressures above the various relief device set points.
- 7.) *All valves and instruments which can communicate with cryogenics in trapped volumes must be protected with trapped reliefs.*  
SV-90-N, SV-96-N, SV-97-N, and SV-98-N, relieve the possible trapped volumes.

##### B) STANDARD PRACTICES

- 1.) *Differential pressure liquid level gauge with isolation valves and a calibration checking feature such as a 3 valve manifold.*  
DPI-100-N along with MV-85-N, MV-86-N, and MV-87-N meet this criteria.
- 2.) *Isolation valve for the pressure gauge*

- 3.) *Full trycock valve.*  
MV-94-N is the full trycock valve.
- 4.) *Primary pressure regulation device other than required relief devices.*  
The regulator RV-90-N vents tank pressure in excess of 40 psig.
- 5.) *Vacuum gauge on vessel.*  
MV-91-V isolates a PE-91-V which is a vacuum gauge tube.
- 6.) *Vacuum pumpout valve, capped off to prevent inadvertent opening.*  
MV-90-V isolates the vacuum space and is capped off.
- 7.) *Drain valve on fill line.*  
MV-91-N allows the fill line to be drained.
- 8.) *Pressure building coil.*  
RV-36-N controls the pressure building loop.

### C) SUGGESTED PRACTICES

- 1.) *Isolation valves at both ends of pressure building loop.*  
MV-88-N, MV-89-N, MV-95-N, and MV-96-N isolate the pressure building loop.
- 2.) *Isolation valve for vacuum gauge.*  
MV-91-V isolates the vacuum gauge port.
- 3.) *Top and bottom fill valves.*  
MV-92-N is the bottom fill valve. There is no top fill valve.
- 4.) *Liquid and gas withdrawal valves.*  
MV-97-N/MV-100-N provide liquid withdrawal. Gas withdrawal for use inside PAB will be added at a later date.
- 5.) *Strainer on liquid fill line.*  
There is a strainer present (S-91-N).
- 6.) *Check valve on liquid fill line.*  
Check valve CV-90-N prevents the dewar from draining thru the fill line.
- 7.) *Filters on vacuum pumpout and line gauge.*  
These are not present.

## 5.0 PIPING

### A) MANDATORY PROVISIONS

- 1.) *Standoffs to a carbon steel vacuum jacket must ensure an acceptable temperature of the vessel.*  
Vessel was designed to ASME code and has operated for years without any vacuum jacket issues.
- 2.) *Thermal stresses must be taken into account in designing piping and piping supports.*

The piping attached to the dewar was used successfully at PS1 in its current configuration.

- 3.) *All piping which can be exposed to the vessel pressure must have an MAWP greater than or equal to the vessel MAWP.*  
The dewar piping consists of 3 different sizes of stainless steel pipe, all with a safe working pressure far above the dewar MAWP of 75 psig.
- 4.) *All piping which can be exposed to the tanker delivery pressure must have a MAWP greater than or equal to the tanker delivery pressure or must be adequately protected from overpressure.*  
PCV-70-N shuts off when the tank vapor space pressure reaches 75 psig. The fill line is 1.900 inch OD with 1.682 inch ID stainless steel pipe with a maximum pressure of 2083 psi. The tanker truck can only deliver 400 psig, thus the supply piping is safe.
- 5.) *All piping which can be exposed to cryogenics in trapped volumes must be protected with trapped volume reliefs without an intervening shut-off valve.*  
SV-90-N, SV-96-N, SV-97-N, and SV-98-N relieve the possible trapped volumes.
- 6.) *Any portions of the piping system which were not part of the initial vessel pressure test or were modified since that test must be pressure tested in accordance with the rules of Fermilab Safety Manual section 5034. For purposes of the pressure test, the MAWP of piping is taken as the maximum pressure to which the piping can be exposed consistent with 4.), 5.), and 6.).*  
All piping will be pneumatically pressure tested.
- 7.) *Piping should be in accordance with ANSI B31.3*  
The piping is believed to be in accordance with ANSI B31.3.

## B) STANDARD PRACTICES

- 1.) *The delivery tanker flow rate and pressure should be taken to be 200 gpm and 225 psi, respectively.*  
These values were taken to be 400 gpm and 400 psig based on conversations and a fax from BOC. It is assumed that the Air Products tankers have similar specifications. PCV-70-N protects the dewar from the possibility of tanker over pressure.
- 2.) *All pipe, valves and fittings should be demonstrated free of leaks at the vessel's MAWP.*  
All components will be pressure tested except components that require the dewar itself to be pressurized.

## C) SUGGESTED PRACTICES

- 1.) *Stainless steel is the preferred piping material over copper or aluminum.*  
The piping consists of stainless steel.
- 2.) *Welded connections should be used whenever possible.*  
Welding was used where possible.
- 3.) *Vacuum jacket the withdrawal line whenever possible.*  
The liquid withdrawal line for PAB is vacuum jacketed.

## 6.0 RELIEF DEVICES: PIPING & INSTALLATION

### A) MANDATORY PRACTICES

- 1.) *Consult the ASME, CGA, & API Standards.*  
The vessel reliefs were sized according to these standards.
- 2.) *The liquid container shall be protected by a minimum of two relief devices, installed to remain at ambient temperature during normal operation. Typically these devices would be one relief valve and one burst disc, although two relief valves would be acceptable if all other conditions are met.*  
The dewar has two sets of relief devices, which consist of a relief valve paired with a rupture disc. A diverter valve separates them such that either one pair or both pairs relieve the vessel.
- 3.) *The exhaust of liquid nitrogen reliefs and vents should not impinge on carbon steel vacuum jacket(s) or into areas which may cause harm to people.*  
The relief discharges are directed upwards.
- 4.) *The primary safety relief valves shall be UV stamped and shall meet the applicable requirements of ASME Code Section VIII.*  
Both relief valves are code stamped and were sent out and recertified within the last year.
- 5.) *The design, material, and location of relief devices shall be suitable for their intended service. The primary reliefs shall have direct communication with the vapor space of the container and shall be so installed that the cooling effects of the contents will not prevent their operation. Either SV-99-N & RD-99-N or SV-100-N and RD-100-N are connected to the dewar vapor space at all times. Several feet separates them from LN2 contact, thus they remain warm while not in operation.*
- 6.) *The vent piping shall be designed to prevent accumulation of moisture at the exhaust and seat area of the relief devices, and to avoid build-up of foreign material which might effect relief capacity. The relief valves and rupture discs have flappers that protect them from foreign material.*
- 7.) *The inlet and vent piping of relief devices must provide for proper performance by taking into account the effect of inlet*

*pressure losses and back pressure on the operating characteristics of the valve. The nominal size of the inlet and discharge piping and fittings connecting to the pressure relief devices shall be at least equal to the nominal size of the respective ports of the relief devices. Where they are a number of devices discharging into the same manifold, an analysis must be made of the back pressure effects on relief pressure an capacity.*

See included document that describes relief valve sizing. All of these issues are addressed.

- 8.) *The effects of mechanical (discharge reactive forces) and thermal stresses on relief piping must be examined to assure proper operation of the relief system.*

See included document that describes relief valve sizing. This issue is addressed and found to be negligible.

- 9.) *Relief devices should be designed and installed so that the possibility of tampering will be minimized.*

It would take a wrench to tamper with the dewar reliefs.

## B) SUGGESTED PRACTICES

- 1.) *The relief system should consist of two sets of two relief devices (one relief valve and one burst disk) with a diverter valve (adequately sized) and a test valve on each side for set point checking.*

The relief system consists of two sets of two relief devices with a diverter valve. MV-101-N and MV-99-N allow for relief valve set point testing.

## 7.0 Relief Device: Sizing

### A) MANDATORY PROVISIONS

- 1.) *Relief device sizing must satisfy each of the provisions that follow.*  
Relief devices were sized according to CGA & API standards.
- 2.) *Size the reliefs of the lading vessel for the following failures:*
- a) *Loss of insulating vacuum using the CGA formula.*  
The fire case includes loss of insulating vacuum. The relief valve is adequate for fire with a loss of insulating vacuum, thus it is adequate for loss of insulating vacuum without fire.
  - b) *Fire condition using CGA formula*  
The fire condition requires 122 SCFM AIR and the relief valve can deliver 731 SCFM.
  - c) *Pumping overflow....precautions should be taken to prevent the development of pressure in excess of 116% of the dewars MAWP.*

PCV-70-N shuts off the fill line in 30 ms when the dewar vapor space pressure is equal to 75 psig.

- d) *Regulator failure on pressure building coil. Consider a wide open regulator, pressure drop in the piping and maximum heat influx, look at the maximum flow rates possible with the liquid head as the driving force.*

Using the simple and very conservative assumptions that the only liquid flow restriction is the regulator and all liquid turns to vapor, the pressure building flow rate was found to be 192 SCFM which is far short of the relief valve capacity of 731 SCFM.

- e) *Pressurization from external sources.*

This system is not in communication with any other systems that could over pressurize it.

- 3.) *Marked set pressure for the relief devices on the lading vessel shall be determined as follows:*

The relief valve is set at 75 psig and can handle all conditions including fire at 110% (MAWP + 15 psi) – 15 psi. The stamped rupture disk is set at 105 psig which is less than 150% (MAWP +15 psi) – 15 psi.

- 4.) *Size the reliefs for the vacuum jacket according to the CGA standard.*

The included relief valve sizing document shows that the vacuum relief requirement is 3.7 in<sup>2</sup> which is << than the 7.1 in<sup>2</sup> area available.

- 5.) *Set pressure for the relief devices on the vacuum jacket....should be fully open at a pressure not exceeding the internal design pressure of the outer shell.*

Vacuum relief is a parallel plate without springs. It should open at slightly above atmospheric pressure.

- 6.) *Incorporate entrance and exit losses into pressure drop and capacity calculations.*

The included relief valve sizing document shows that the entrance losses are less than the 3% API recommendation.

- 7.) *Size for gas or liquid flow thru safety devices using API recommendations.*

The included relief valve sizing document shows that for gas flow under sonic conditions, the relief valves are adequately sized. Liquid sizing was not done because there is no credible scenario where the reliefs vent liquid.

- 8.) *Size for flashing conditions using API recommendations:*

Not applicable because a scenario involving liquid relief is not credible.

- 9.) *Trapped volume reliefs should be of adequate capacity to prevent overpressure due to ambient heat input.*

Trapped volume reliefs were sized for fire conditions, thus they can handle ambient conditions.

## 7.0 General

### A) MANDATORY PROVISIONS

- 1.) *All dewars “Out-of-Service” must be locked out to prevent inadvertent filling. The key combination for this lock should be controlled by the responsible party. A sign indicating “Dewar Out of Service – DO NOT FILL” should be prominently displayed.*  
Currently the dewar fill connection has been removed.
- 2.) *All dewars must be labeled “LIQUID NITROGEN” and marked with their dewar number.*  
This provision has been met.
- 3.) *All dewars must be labeled with the MAWP, the dewar capacity, the maximum fill level, and a telephone number which can be called to obtain assistance.*  
A sign will be posted soon.
- 4.) *All valves used during filling must be labeled with descriptive function tags.*  
Tags will be added to the valves soon.
- 5.) *All gas or liquid withdrawal valves must be labeled with descriptive function tags.*  
Tags will be added to the valves soon.
- 6.) *Dewars must be adequately protected from vehicular damage.*  
The dewar is protected by large shielding blocks.
- 7.) *The fill connection must be adequately supported.*  
This provision has been met.
- 8.) *Dewars must be adequately supported and restrained.*  
This provision has been met.

### B) STANDARD PRACTICES

- 1.) *Lettering for 8.0 A) 2.) should be 6” high.*  
The lettering is 6” high.
- 2.) *The liquid level indicator and pressure gauge must be in sight of the fill connection and be “redlined” at the maximum operating values.*  
The liquid level indicator is within sight of the fill connection, and the shut off valve protects from over filling.
- 3.) *A fill procedure should be attached to the dewar in a weatherproof fashion.*  
This will be done in the future.

- 4.) *A flow schematic which includes the normal operating pressure and capacities and settings of relief devices should be attached to the dewar in a weather proof fashion.*  
This will be done in the future once the piping arrangement is approved.
- 5.) *The area at the fill connection and instrumentation used during the filling should be adequately lighted.*  
The dewar is out in the open and adequately lit.
- 6.) *The fill connection should be the CGA standard 1-1/2" 2.4 stub Acme thread.*  
This provision has been met. The fill connection is a stainless steel fitting.
- 7.) *All valves, reliefs, and nozzles should be labeled with valve numbers.*  
Brass tags are tied to most valves and will be added to all valves soon.

### **3.5d – LN2 Dewar Fill Line Pressure Test Documentation**



Date: 3/29/07

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test:  Hydrostatic  Pneumatic

Test Pressure 440 psig Maximum Allowable Working Pressure > 400 psig

**Items to be Tested**

Test to be performed on the PAB liquid nitrogen dewar fill line. Refer to attached sketch. Section to be tested is highlighted in red. See table in sketch for component pressure ratings.

Location of Test PAB Date and Time TBD

**Hazards Involved**

Remote possibility of pipe or component failure releasing the energy of compressed nitrogen. Nitrogen piping has a pressure rating of 1966 psi. Component ratings are in sketch.

**Safety Precautions Taken**

Test area will be roped off. Test administrators will be inside PAB.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

**Results**

Fill line passed pressure test. TERRY TOPE [Signature] 13329N


Witness [Signature] 13747 Dept/Date 4-17-07  
(Safety Officer or Designee)

\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.

Schematic and component ratings for pressure test of PAB LN2 dewar fill line.

**LN2 fill line pressure test components**

Component ID	Manufacturer	Model	Maximum Allowable Working Pressure
PCV-70-N	Messer / Chart	MG97P	600 psig
CV-90-N	Check-All Valve	UN-3-150-SS	3000 psig
SV-90-N	Circle Seal	5120B-4MP	2400 psig
S-091-N	Mueller	1715	550 psig
MV-091-N	Worchester	1/2 C4416P	870 psig
MV-92-N	Worchester	1 1/2 C4416P	870 psig



Components to be pressure tested

1/4" copper tube

### **Pressure Test Procedures for PAB Nitrogen Dewar Fill Line.**

1. CLOSE MV-92-N, MV-91-N.
2. Plug the exhaust of relief valve SV-90-N.
3. Connect a 1/4" copper tube into dewar fill connection using the adaptor to connect to the standard CGA fitting.
4. Run the tube to the safe location inside PAB
5. Connect tube to test manifold.
6. Pressurize system to 25 psi. Valve off supply and observe test pressure gauge. If pressure holds at 25 psi for 10 minutes, proceed to next step. If leaks occur at this step, fix the leaks. Then resume testing at step 7.
7. Gradually increase the pressure to 150 PSI. Valve supply off and make sure pressure does not fall. Fixing any leak above 25 PSI requires the system to be depressurized and the procedure resumed at step 7.
8. Gradually increase the pressure in increments of 50 PSI up to 440 PSI. Pause for 2 minutes at each increment and valve off the supply to make sure the pressure does not fall and indicate a leak. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11
9. At 440 PSI, hold the pressure for 10 minutes.
10. Lower pressure to 100 psig and inspect all joints by the soap bubble method.
11. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11. If no leaks are found, depressurize system and disconnect test apparatus.

## **3.5e – LN2 Transfer Line Pressure Test Documentation**



Date: 6/7/07

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test: [ ] Hydrostatic [X] Pneumatic

Test Pressure 110 psig Maximum Allowable Working Pressure 100 psig

**Items to be Tested**

Test to be performed inside PAB. Refer to attached sketch. Section to be tested is highlighted in red. See table in sketch for component pressure ratings.

Location of Test PAB Date and Time TBD 6/7/07

**Hazards Involved**

Remote possibility of pipe or component failure releasing the energy of compressed nitrogen. Most of the pipe is inside a stainless steel vacuum jacket which would act as containment in the event of a tested component failure. The nitrogen piping is rated for 2568 psi. Component ratings are in spreadsheet.

**Safety Precautions Taken**

Test area will be roped off. Test administrators will be a significant distance from piping.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/


Results  
Passed pressure test. No pressure drop indicated on gauge and no increases in insulating vacuum. Terry Tope Jun 7 13329M

Witness Eric McHugh Dept/Date PD/ES+H 6.07.07  
(Safety Officer or Designee)

\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.


LN2 transfer line pressure test components

Component ID	Manufacturer	Model	Maximum Allowable Working Pressure
MV-100-N	Cryolab	CV8-086-5WPY?2-ED	150 psig
CV-100-N	Fermlab	1/2" check valve	>> 100 psig
MV-119-N	Cryolab	CV8-084-SWTG2	100 psig
PSV-117-N2	Circle Seal	5100-2MP	2400 psig
PSV-118-N2	Circle Seal	5100-2MP	2400 psig
MV-120-N	Cryolab	CV8-086-SWPG2	150 psig
EV-106-N2	Asco	8263G209LT (120 VAC)	100 psig
PT-27-N2	Setra	205-2	100 psig
PI-44-N2	US Gauge	0 - 150 psig	150 psig
PSV-101-N2	Circle Seal	5100-2MP	2400 psig
EV-105-N2	Asco	8263G209LT (120 VAC)	100 psig



Components to be pressure tested

1/4" black poly



## **Pressure Test Procedures for PAB Nitrogen Dewar Fill Line.**

1. CLOSE MV-100-N.
2. OPEN MV-119-N, MV-120-N.
3. Plug the exhaust of relief valves PSV-117-N2, PSV-118-N2, PSV-101-N.
4. Connect a 1/4" copper tube into the hose intended for future LN2 usage.
5. Run the tube to the safe location inside PAB.
6. Connect tube to test manifold.
7. Pressurize system to 25 psi. Valve off supply and observe test pressure gauge. If pressure holds at 25 psi for 10 minutes, proceed to next step. If leaks occur at this step, fix the leaks. Then resume testing at step 7. Monitor insulating vacuum pressure.
8. Gradually increase the pressure to 50 PSI. Valve supply off and make sure pressure does not fall. Fixing any leak above 25 PSI requires the system to be depressurized and the procedure resumed at step 7. Monitor insulating vacuum pressure.
9. Gradually increase the pressure in increments of 10 PSI up to 110 PSI. Pause for 2 minutes at each increment and valve off the supply to make sure the pressure does not fall and indicate a leak. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11. Monitor insulating vacuum pressure.
10. At 110 PSI, hold the pressure for 10 minutes. Monitor insulating vacuum pressure.
11. Lower pressure to 25 psig and inspect all joints by the soap bubble method.
12. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11. If no leaks are found, depressurize system and disconnect test apparatus.

### **3.5f – LAr Transfer Line Pressure Test Documentation**



SUBJECT

NAME

Terry Torre

DATE

5/2/07

REVISION DATE

LAr transfer line pressure test

manifold  $362 \times 10^{-3}$  Torr

mole sieve  $2.61 \times 10^{-2}$  Torr internal  $\leftarrow$  went up, leak! Leak into mole sieve insulating vacuum.  
 $1.12 \times 10^{-2}$  Torr external

Transfer  $7.41 \times 10^{-1}$  Torr

O<sub>2</sub> external  $2.61 \times 10^{-2}$  Torr

Looks like molecular sieve bead was crushed in the seal which caused leak.

Culce  $14.3$  psia internal

$3.58 \times 10^{-2}$  external

is the leak at the conflat?

Tube OD is  $2.375$  and ID is  $2.1875$ "

Area



Date: 5/10/07

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test: [ ] Hydrostatic [X] Pneumatic

Test Pressure 440 psig Maximum Allowable Working Pressure > 400 psig

**Items to be Tested**

Test to be performed on a portion of the PAB liquid argon transfer line that leaked in a previous test. Refer to attached sketch. Section to be tested is highlighted in red. See table in sketch for component pressure ratings.

Location of Test PAB Date and Time TBD

**Hazards Involved**

Remote possibility of pipe or component failure releasing the energy of compressed nitrogen. Argon piping has a pressure rating of 3487 psi for the stainless steel sections and 1113 psi for the copper sections. Component ratings are in sketch.

**Safety Precautions Taken**

Test area will be roped off. Test administrators will be inside PAB.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

Results  
Filter portion held 440 psig. Passed. Did not leak into vacuum like previous test.  
Terry Tope 13329N

Witness [Signature] 13747N Dept/Date PPD/Est H 5.10.07  
(Safety Officer or Designee)


\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.


LAr transfer line pressure test components

Schematic and component ratings for pressure test of PAB LAr transfer line.

Component ID	Manufacturer	Model	Maximum Allowable Working Pressure
PSV-203-Ar	Circle Seal	5100-4MP	2400 psig
MV-204-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-213-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-218-Ar	Swagelok	SS-8BG-V47	1000 psig
PSV-219-Ar	Circle Seal	5100-2MP	2400 psig
MV-217-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-366-V	Swagelok	SS-8BG-V47	1000 psig
MV-461-HAr	Swagelok	SS-8BG-V47	1000 psig
PSV-249-Ar	Circle Seal	5100-2MP	2400 psig
MV-202-Ar	Swagelok	SS-4BG-V51	1000 psig
MV-208-Ar	Swagelok	SS-4BG-V51	1000 psig
MV-365-V	Swagelok	SS-8BG-V47	1000 psig
MV-480-HAr	Swagelok	SS-8BG-V47	1000 psig
PSV-250-Ar	Circle Seal	5100-2MP	2400 psig
MV-239-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-244-Ar	Swagelok	SS-8BG-V47	1000 psig

Terry Topp  
5.4.07





Date: 5/22/07

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test: [ ] Hydrostatic [X] Pneumatic

Test Pressure 440 psig Maximum Allowable Working Pressure > 400 psig

**Items to be Tested**

Test to be performed on the PAB liquid argon transfer line. Refer to attached sketch. Section to be tested is highlighted in red. See table in sketch for component pressure ratings.

Location of Test PAB Date and Time TBD

**Hazards Involved**

Remote possibility of pipe or component failure releasing the energy of compressed nitrogen. Argon piping has a pressure rating of 3487 psi for the stainless steel sections and 1113 psi for the copper sections. Component ratings are in sketch. Most of the piping is inside a vacuum jacket which would act as containment for a failure.

**Safety Precautions Taken**

Test area will be roped off. Test administrators will be inside PAB.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

**Results**

CAr transfer line passed at 440 psig. Internal line did not leak into insulating vacuum spaces  
Terry Tope 13324N [Signature]

Witness [Signature] 13747N Dept/Date PD ES&H 5-22-07  
(Safety Officer or Designee)

\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.


LAr transfer line pressure test components

Schematic and component ratings for pressure test of PAB LAr transfer line.

Component ID	Manufacturer	Model	Maximum Allowable Working Pressure
PSV-203-Ar	Circle Seal	5100-4MP	2400 psig
MV-204-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-213-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-218-Ar	Swagelok	SS-8BG-V47	1000 psig
PSV-219-Ar	Circle Seal	5100-2MP	2400 psig
MV-217-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-366-V	Swagelok	SS-8BG-V47	1000 psig
MV-461-HAr	Swagelok	SS-8BG-V47	1000 psig
PSV-249-Ar	Circle Seal	5100-2MP	2400 psig
MV-202-Ar	Swagelok	SS-4BG-V51	1000 psig
MV-208-Ar	Swagelok	SS-4BG-V51	1000 psig
MV-365-V	Swagelok	SS-8BG-V47	1000 psig
MV-480-HAr	Swagelok	SS-8BG-V47	1000 psig
PSV-250-Ar	Circle Seal	5100-2MP	2400 psig
MV-239-Ar	Swagelok	SS-8BG-V47	1000 psig
MV-244-Ar	Swagelok	SS-8BG-V47	1000 psig

Terry Tope  
3.29.07

Components to be pressure tested



## **Pressure Test Procedures for PAB Argon Transfer Line.**

1. CLOSE MV-204-Ar, MV-218-Ar, MV-365-V, MV-366-V, MV-480-HAr, MV-461-HAr, MV-239-Ar, MV-244-Ar..
2. OPEN MV-213-Ar, MV-217-Ar, MV-202-Ar, MV-208-Ar.
3. Plug the exhaust of relief valves PSV-203-Ar, PSV-219-Ar, PSV-249-Ar, PSV-250-Ar.
4. Connect a 1/4" copper tube into one of the high pressure stockroom dewar connections. Plug the other 3 connections.
5. Run the tube to the safe location inside PAB.
6. Connect tube to test manifold.
7. Pressurize system to 25 psi. Valve off supply and observe test pressure gauge. If pressure holds at 25 psi for 10 minutes, proceed to next step. If leaks occur at this step, fix the leaks. Then resume testing at step 7. Monitor insulating vacuum pressures during entire test.
8. Gradually increase the pressure to 150 PSI. Valve supply off and make sure pressure does not fall. Fixing any leak above 25 PSI requires the system to be depressurized and the procedure resumed at step 7.
9. Gradually increase the pressure in increments of 50 PSI up to 440 PSI. Pause for 2 minutes at each increment and valve off the supply to make sure the pressure does not fall and indicate a leak. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11
10. At 440 PSI, hold the pressure for 10 minutes.
11. Lower pressure to 100 psig and inspect all joints by the soap bubble method.
12. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11. If no leaks are found, depressurize system and disconnect test apparatus.

**3.5g – “Luke” Materials Lock Bellows and Gate Valve Pressure Test**



Date: 6/6/07

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test: [ ] Hydrostatic [X] Pneumatic

Test Pressure 38.5 psig Maximum Allowable Working Pressure Estimated as 35 psig

**Items to be Tested**

Test to be performed on a portion of the PAB FLARE liquid argon materials test station. This includes a modified vacuum gate valve and a welded edge bellows. Determining the internal pressure capability of the bellows is the reason for this test.

Location of Test PAB Date and Time TBD

**Hazards Involved**

Gate valve has been modified to handle internal pressure – analyzed with ASME code (see attached). Bellows is of unknown origin . However with its internal rod support and construction it should be capable of withstanding 35 psig. Most likely hazard is failure of the bellows.

**Safety Precautions Taken**

Test area will be roped off. Test administrators will be a significant distance from pressurized components. This is a low pressure test with a small amount of stored energy. Bellows is weakest link and if it fails it will fail at a welded edge. This will cause the bellows to leak. It will not fail in an explosive manner.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/


Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

Results  
Components passed test. Terry Tope 13329N Jim M  
6/1/07

Witness Eric McHugh Dept/Date PD/ES+H 6.11.07  
(Safety Officer or Designee)

\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.

Schematic and component ratings for pressure test of "Luke" bellows and gate valve.



## **Pressure Test Procedures for “Luke” bellows pressure test**

1. CLOSE MV-254-V and MV-290-Ar.
2. OPEN MV-256-Ar.
3. Plug the exhaust of relief valve PSV-313-Ar with a KF blank off and a pressure retaining ring.
4. Disconnect vent piping from MV-256-Ar and connect a 1/4” black poly tube.
5. Run the tube to the safe location inside PAB.
6. Connect tube to test manifold.
7. Pressurize system to 10 psi. Valve off supply and observe test pressure gauge. If pressure holds at 10 psi for 2 minutes, proceed to next step. If leaks occur at this step, fix the leaks.
8. Gradually increase the pressure in increments of 5 PSI up to 38.5 PSI. Pause for 2 minutes at each increment and valve off the supply to make sure the pressure does not fall and indicate a leak. If leaks are found, depressurize system and fix the leaks. Then repeat previous step.
9. At 38.5 PSI, hold the pressure for 10 minutes.
10. Depressurize system.

MV-254-V

MV-254-V is a Norcal manually operated viton seal vacuum gate valve constructed from 304 stainless steel. The valve attaches to the cryostat using 8 inch conflat flanges. The valve was chosen to create a large aperture for passing materials thru that can be sealed. The valve is not rated by Norcal for positive internal pressure.

The structurally weakest part of the valve appears to be large flat rectangular panel between the conflat flange and the thick end flange that holds the actuating mechanism. To investigate the stress in this part, the section was analyzed as an unstayed flat head per section UG-34 of the ASME code.

The maximum pressure for this valve can be calculated from

$$t = d \sqrt{\frac{ZCP}{SE}} \Rightarrow P = \left(\frac{t}{d}\right)^2 \frac{SE}{ZC} \text{ and } Z = 3.4 - \frac{2.4d}{D} \text{ where}$$

$t =$  minimum required thickness of the flat heat.

$d =$  length of short span, = 6 inches.

$D =$  long span of noncircular heads measured perpendicular to short span, = 7 9/16 inches.

$Z =$  factor of noncircular heads and covers that depends on the ratio of the short span to the long span

$C =$  a factor depending upon the method of attachment of head, = 0.33 from Figure UG-34.

$P =$  internal design pressure, 35 psi.

$S =$  maximum allowable stress value in tension, = 18,800 psi for 304 SS.

$E =$  joint efficiency from Table UW-12, taken as 0.5 to be conservative.

$$Z = 3.4 - \frac{2.4(6)}{\left(7 + \frac{9}{16}\right)} = 1.496, P = \left(\frac{0.125}{6.0}\right)^2 \frac{(18800)0.5}{1.496(0.33)} = 8.3 \text{ psi.}$$

The maximum pressure this valve housing should see is 8.3 psid internal based on the large flat section.

The side of the valve consists of a strip of 1/8 inch thick stainless steel that measures 1.125" ( $d$ ) x 13" ( $D$ ). Applying the above equations gives an estimate of the strength of the maximum pressure this part of the valve body can withstand.

$$Z = 3.4 - \frac{2.4(1.125)}{(13)} = 3.19, P = \left(\frac{0.125}{1.125}\right)^2 \frac{(18800)0.5}{3.19(0.33)} = 110 \text{ psi}$$

The valve body is only pressurized if the valve is open. Otherwise the valve body is sealed off from the vapor space of Luke. When the valve is open, excess pressure is vented thru PSV-313-Ar which is set at 6 psig. However, PSV-313-Ar has less capacity then PSV-210-Ar. To ensure the valve body does not rupture if the gate valve is open when warm material is submerged into

the liquid argon, it is strengthened by encasing the housing in 1/2 inch thick 6061-T6 Aluminum which has an ASME allowable stress of 10,500 psi. Applying the above equation again, an estimate is made for the strength of this housing

$$P = \left(\frac{0.5}{6.0}\right)^2 \frac{(10500)0.5}{1.496(0.33)} = 73.9 \text{ psi. This exceeds the 35 psig relief valve set point.}$$

**3.5h - LN2 Dewar Piping Pressure Test**



Date: 6/15/07

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test: [ ] Hydrostatic [X] Pneumatic

Test Pressure 100 psig Maximum Allowable Working Pressure 400 psig

**Items to be Tested**

Test to be performed on the PAB liquid nitrogen piping. Refer to attached sketch. Section to be tested is highlighted in red. See table in sketch for component pressure ratings. This is mainly a leak check.

Location of Test PAB Date and Time TBD

**Hazards Involved**

Remote possibility of pipe, weld, or component failure releasing the energy of compressed nitrogen. Component ratings are in sketch. Lowest rated component is rated at 400 psig.

**Safety Precautions Taken**

Test area will be roped off.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

**Results**

Witness \_\_\_\_\_ Dept/Date \_\_\_\_\_  
(Safety Officer or Designee)

\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.


Schematic and component ratings for pressure test of PAB LN2 dewar piping.

Component ID	Manufacturer	Model	Maximum Allowable Working Pressure
MV-97-N	Nibco	----	600 psig
MV-107-N	Nibco	----	600 psig
MV-95-N	Nibco	----	600 psig
MV-96-N	Nibco	----	600 psig
SV-96-N	Circle Seal	5159B-4MP-80	2400 psig
RV-36-N	Cash Acme	B	400 psig
SV-97-N	Circle Seal	5159B-4MP-80	2400 psig
MV-88-N	Nibco	----	600 psig
SV-98-N	Circle Seal	5159B-4MP-80	2400 psig
MV-89-N	Nibco	----	600 psig

Break piping union here and pressurize piping thru adaptor. Dewar will not be pressurized.

Components to be pressure tested  
1/2 inch SCH 40 SS rated at 4600 psig

1/4" black poly tube



Bottle Regulator  
Matheson 3020-580  
3000 psig max

Regulator  
Isolation Valve  
Matheson LMM4346P  
3000 psig

Relief valve  
Anderson Greenwood  
83MS46-4  
2000 psig max  
135 psig set point

Test Gauge  
USG vac-0-300 psi  
300 psig max

Vent Valve  
Whitey B-1VM4-F4  
3000 psig

Test Section Isolation valve  
Matheson FT4374  
3000 psig

## **Pressure Test Procedures for PAB Nitrogen Dewar Piping**

1. CLOSE MV-97-N, MV-107-N, and MV-89-N.
2. Plug the exhaust of relief valves SV-96-N, SV-97-N, and SV-98-N.
3. OPEN MV-95-N, MV-96-N, and MV-88-N.
4. Connect a 1/4" black poly tube into liquid withdrawal line after opening piping union and connecting union to compression adaptor.
5. Run the tube to the safe location away from the piping.
6. Connect tube to test manifold.
7. Pressurize system to 25 psi. Valve off supply and observe test pressure gauge. If pressure holds at 25 psi for 5 minutes, proceed to next step. If leaks occur at this step, fix the leaks. Then resume testing at step 7.
8. Gradually increase the pressure in increments of 25 PSI up to 100 PSI. Pause for 2 minutes at each increment and valve off the supply to make sure the pressure does not fall and indicate a leak. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 10.
9. At 100 PSI, hold the pressure for 10 minutes.
10. Lower pressure to 25 psig and inspect all joints by the soap bubble method.
11. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 10. If no leaks are found, depressurize system and disconnect test apparatus.

### **3.5i – “Bo” High Voltage Feed Thru Pressure Test**



Date: 4/23/08

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test:  Hydrostatic  Pneumatic

Test Pressure To failure psig Maximum Allowable Working Pressure 105 psig

**Items to be Tested**

FNAL designed high voltage feed thru. Feed thru will be tested to 105 psig. If it survives at 105 psig, the feed thru will then be tested to FAILURE. See attached sketch.

Location of Test PAB Calibration Shop Date and Time TBD

**Hazards Involved**

Center stainless steel rod or HDPE cylinder could be forced from housing and become projectiles.

**Safety Precautions Taken**

PAB calibration shop will be closed to those not participating in the test. Test personnel will remain 5 feet from HV feed thru. Feed thru will be placed in a bucket and covered with rags to prevent any broken parts from becoming projectiles. Performing hydraulic instead of pneumatic test to limit the stored energy and reduce the hazard. Test personnel will wear eye and ear protection.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/


Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/ 4-24-08

**Results**

No leaks at 105 psig. Leakage started at about 500 psig.  
Part was tested to 1000 psig and only experienced slight leakage.  
No massive failure. Could not detect movement of press fit parts.

Witness Martha Heflin Dept/Date ESH 4/24/08  
(Safety Officer or Designee)

- Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.



Determine the pressure at which this seal fails. Increase pressure slowly in increments of 25 psig up to 105 psig. If the seal holds for 5 minutes at 105 psig, then increase the pressure in increments of 50 psig until failure.

5/8 inch diameter stainless steel rod

HDPE cylinder

1.375 inch OD, 0.035 inch wall, stainless steel tube. Rated for 853 psi.

The 5/8 inch diameter stainless steel rod is shrunk fit into the HDPE cylinder. The HDPE cylinder and rod are then shrunk fit into the outer stainless steel tube. The test will investigate at what point the force created by the pressure overcomes the press fit resistance.

Bucket to contain water leaks

### **3.5j – “Bo” Signal Feed Thru Pressure Test**



Date: 5/14/08

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test:  Hydrostatic  Pneumatic

Test Pressure To failure psig Maximum Allowable Working Pressure 105 psig

**Items to be Tested**

FNAL designed signal feed thru. Feed thru will be tested to 105 psig. If it survives at 105 psig, the feed thru will then be tested to FAILURE.

Location of Test PAB Calibration Shop Date and Time TBD

**Hazards Involved**

Epoxyed section of feed thru could fail and become a projectile. Excluding the epoxy, the flanges are rated for At least 2000 psig.

**Safety Precautions Taken**

PAB calibration shop will be closed to those not participating in the test. Test personnel will remain 5 feet from signal feed thru. Feed thru will be covered with rags to prevent any broken parts from becoming projectiles. Performing hydraulic instead of pneumatic test to limit the stored energy and reduce the hazard. Test personnel will wear eye protection.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

Results  
No leaks @ 105 psig -> Passed 3x test  
1 pin-hole leak @ 400 psig (in the epoxy)  
4 leaks in the epoxy @ 700 psig  
massive leakage above 1000 psig

Witness *James E. Tweed* Dept/Date PPD/5/15/08  
(Safety Officer or Designee)  
(for Martha Heflin)

- Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.

**From:** Martha Heflin <martha@fnal.gov>  
**Subject:** **Re: Another pressure test**  
**Date:** May 15, 2008 9:18:18 AM CDT  
**To:** Terry Tope <tope@fnal.gov>

---

Terry,  
I have reviewed this as well and you may go forward with the test. Jim may serve as the witness and sign the form as my designee.

Martha  
----- Original Message ----- From: "Terry Tope" <tope@fnal.gov>  
To: "Martha Heflin" <martha@fnal.gov>  
Sent: Wednesday, May 14, 2008 5:13 PM  
Subject: Another pressure test

Hi Martha - Attached is a permit for a hydrostatic test I want to perform on a custom feed thru flange fabricated by Fermilab. The test will be very similar to the one you witnessed recently.

Attached is a picture of what will be tested. The blue epoxy is what we plan to test to failure.

Regards,

Terry E Tope  
Fermi National Accelerator Laboratory  
PO Box 500 MS 219  
Batavia IL 60510

p630.840.2666  
f630.840.3694  
tope@fnal.gov

## **3.5k – “Bo” LAr Piping Pressure Test**



Date: 5/14/08

**EXHIBIT B  
Pressure Testing Permit\***

Type of Test:  Hydrostatic  Pneumatic

Test Pressure 440 psig Maximum Allowable Working Pressure 400 psig

**Items to be Tested**

Test to be performed on the PAB liquid argon transfer line to "Bo." Refer to attached sketch. Section to be tested is highlighted in red.

Location of Test PAB Date and Time TBD

**Hazards Involved**

Remote possibility of pipe or component failure releasing the energy of compressed nitrogen. Argon piping has a pressure rating of 2568 to 3487 psi for the stainless steel sections and 1113 psi for the copper sections. Component ratings are in sketch. Most of the piping is inside a vacuum jacket which would act as containment for a failure. All system valves are Swagelock meta bellows valves rated for 1000 psig.

**Safety Precautions Taken**

Test area will be roped off. Test administrators will wear eye protection.

**Special Conditions or Requirements**

Qualified Person and Test Coordinator Terry Tope 5.20.08  
Dept/Date PPD/

Division/Section Safety Officer Martha Heflin  
Dept/Date PPD/

Results Piping held 440 psig. Did not leak into insulating vacuum.


Witness Martha Heflin Dept/Date ESH/5-20-08  
(Safety Officer or Designee)

\* Must be signed by division/section safety officer prior to conducting test. It is the responsibility of the test coordinator to obtain signatures.

Schematic and component ratings for pressure test of PAB "Bo" LAr transfer line.

Terry Toppe  
5.14.08

Components to be pressure tested



Bottle Regulator  
Matheson 3020 series  
3000 psig max

Regulator  
Isolation Valve  
Matheson LMM434BP  
3000 psig

Vent Valve  
Whitey B-1VM4-F4  
3000 psig

Relief valve  
Anderson Greenwood  
83MS46-4  
2000 psig max  
500 psig set point

Test Gauge  
USG 0-600 psi  
600 psig max

1/4" copper tube

## **Pressure Test Procedures for PAB “Bo” Argon Transfer Line.**

1. CLOSE MV-379-Ar, MV-239-Ar, MV-480-HAr, MV-208-Ar, and MV-244-Ar.
2. OPEN MV-365-V.
3. Plug the exhaust of relief valve PSV-250-Ar.
4. Connect a 1/4” copper tube MV-365-V
5. Run the tube to the safe location inside PAB.
6. Connect tube to test manifold.
7. Evacuate the piping and back fill with bottle argon three times. Pressurizing the system to 10 psig each time.
8. Pressurize system to 25 psi. Valve off supply and observe test pressure gauge. If pressure holds at 25 psi for 10 minutes, proceed to next step. If leaks occur at this step, fix the leaks. Then resume testing at step 7. Monitor insulating vacuum pressures during entire test.
9. Gradually increase the pressure to 150 PSI. Valve supply off and make sure pressure does not fall. Fixing any leak above 25 PSI requires the system to be depressurized and the procedure resumed at step 7.
10. Gradually increase the pressure in increments of 50 PSI up to 440 PSI. Pause for 2 minutes at each increment and valve off the supply to make sure the pressure does not fall and indicate a leak. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11
11. At 440 PSI, hold the pressure for 10 minutes.
12. Lower pressure to 100 psig and inspect all joints by the soap bubble method.
13. If leaks are found, depressurize system and fix the leaks. Then repeat steps 7 thru 11. If no leaks are found, depressurize system and disconnect test apparatus.

#### 4.1a - Relief Valve Sizing for the FLARE Materials Test Station and TPC cryostats along with Supporting Documentation

The pressure relief devices for the FLARE Materials Test Station Cryostat and TPC cryostat were sized according to the Compressed Gas Association's CGA S-1.3—1995 document. This document is entitled, "Pressure Relief Device Standards Part 3—Stationary Storage Containers for Compressed Gases." In section 4.1.1 it states, "...each container shall be provided with a primary system of one or more pressure relief devices and a secondary system of one or more pressure relief valves or rupture disks or buckling pin devices."

**These two identical vessels (PPD ID# 10100 and 10101) are each equipped with two pressure relief devices (Luke: PSV-210-Ar and RD-302-Ar, Bo: PSV-377-Ar and RD-376-Ar). The basic vessel geometry is shown in Figure 4.1a.1. The relief valves are set at each vessel's MAWP of 35 psig while the rupture disks are set at 55 psig which is slightly less than 150% of MAWP.**

##### Fire Condition (both Luke and Bo)

First the fire condition is considered as it is more difficult to relieve than any other scenario. To begin the calculation, an estimate of the relief capacity required is computed. This number is then corrected for pressure drop and temperature rise in the line that leads to the reliefs if required. In CGA section 5.3.3 the following equation is used to calculate the minimum required flow capacity

$$Q_a = FG_iUA^{0.82}$$

where:

$U =$  Overall heat transfer coefficient to the liquid,  $\frac{Btu}{hr \cdot ft^2 \cdot ^\circ F}$ .

$F =$  Correction factor for pressure drop and temperature rise in line to relief valve.

$A =$  Average surface area of the inner and outer vessels, 25.90 ft<sup>2</sup> (see Figure 4.1a.2 for key dimensions).

$G_i =$  Gas factor for insulated containers.

$Q_a =$  Flow capacity required at applicable flow rating pressure and 60 °F in cubic feet per minute of free air.

First the overall heat transfer coefficient to the liquid must be computed. For the fire condition it was assumed that the outer vessel is exposed to an environment that is at 1200 °F (922 K) and the vacuum space between the inner and outer vessel has been filled with air at atmospheric pressure (air has a higher thermal conductivity than argon). The inner vessel wall will be at the saturation temperature of liquid argon at the flow rating pressure. The super insulation around the inner vessel is ignored because it may deteriorate in a fire. The relief valve is set at 35 psig. For the fire condition it must be ensured that the pressure does not exceed 121% MAWP. Thus the flow rating pressure is 1.21(35+15) -15, or 45.5 psig. The saturation temperature of liquid argon at 45.5 psig is 185.8 °R (103.2 K).

Several heat transfer mechanisms are considered for the fire condition. Two separate heat transfer paths are modeled. The first path involves convection and radiation from the environment to the vertical sidewalls of the cryostat, conduction thru these sidewalls, convection and radiation thru the annular vacuum space while filled with air, and conduction thru the inner vessel sidewall into the liquid argon. The second path considers convection and radiation to the thick top flange of the cryostat, conduction thru this flange, and radiation from this flange to the liquid argon. Convection from the top flange to the liquid argon is not considered because the venting gas will not flow in a manner that transfers heat to the surface of the cryogen. The vented gas will intercept some of the heat arriving from the top flange before it reaches the liquid surface. This reduction in heat input is ignored due to the difficulty of calculating heat transfer from a multi-dimensional gas flow. This omission is a conservative assumption. The two heat transfer paths are only coupled in that they both transfer heat into the liquid argon. Heat transfer to the bottom of the cryostat was considered negligible because the

bottom of the cryostat is flush with the concrete floor and will not be exposed to fire. All heat transfer equations were solved simultaneously in EES (Engineering Equation Solver) which provided temperature and pressure dependent fluid properties and temperature dependent solid thermal properties.

First the calculations related to path 1 are described. Figure 4.1a.2 helps relate the equations to the cryostat. The details of the EES computation file are available in the appendix. The heat rates given in watts are the exact solution given by EES. The equations listed in this document have rounded values that when computed won't match the listed heat rate exactly.

Radiation heat transfer from the environment to the outer vessel vertical walls was modeled as a small convex object in a large cavity (Equation 13.27 from Incropera and Dewitt) where

$$q_{1-2rad} = \sigma A_2 \varepsilon_2 (T_1^4 - T_2^4) = \frac{5.67 \times 10^{-8} W}{m^2 \cdot K^4} (2.1682 m^2) (0.7) [(922 K)^4 - (867.72 K)^4] = 13402 W.$$

Convective heat transfer to the outer vessel walls was modeled as free convection on a vertical flat plate combining equations 9.24, 9.25, and 9.26, from Incropera and Dewitt

$$q_{1-2conv} = \left\{ 0.825 + \frac{0.387 \left( \frac{g \beta (T_1 - T_2) L^3}{\alpha_{air} \nu_{air}} \right)^{1/6}}{\left[ 1 + \left( \frac{0.492}{Pr} \right)^{9/16} \right]^{8/27}} \right\}^2 \left( \frac{k_{air}}{L_{ext}} \right) A_s (T_1 - T_2)$$

$$q_{1-2conv} = \left\{ 0.825 + \frac{0.387 \left( \frac{9.81 \frac{m}{s^2} \frac{1}{(922 + 867.72) K} (922 - 867.72) K (1.118 m)^3 \right)^{1/6}}{\left[ 1 + \left( \frac{0.492}{0.7049} \right)^{9/16} \right]^{8/27}} \right\}^2 \left( \frac{0.06202 \frac{W}{m \cdot K}}{1.118 m} \right) 2.168 m^2 (922 - 867.72) K = 342 W$$

Conduction thru the thin stainless steel vacuum jacket is included in the model and the thermal resistance it presents is negligible. Conduction is computed from Incropera and Dewitt's equation 3.27 which gives the heat transfer rate for radial conduction in a cylinder

$$q_{2-3cond} = \frac{2\pi L_{ext} k_{ss} (T_2 - T_3)}{\ln\left(\frac{r_3}{r_2}\right)} = \frac{2\pi (1.118 m) \frac{23.544 W}{m \cdot K} (867.718 - 867.126) K}{\ln\left(\frac{0.30877 m}{0.30658 m}\right)} = 13744 W.$$

Radiation exchange between the vacuum jacket and the inner vessel was computed using equation 13.25 from Incropera and Dewitt which applies to concentric cylinders.

$$q_{3-5rad} = - \frac{\sigma A_5 (T_5^4 - T_3^4)}{\frac{1}{\epsilon_5} + \frac{1 - \epsilon_3}{\epsilon_3} \left( \frac{r_5}{r_3} \right)} = \frac{5.67 \times 10^{-8} W}{m^2 \cdot K^4} (1.987 m^2) (867.126^4 - 105.028^4) K^4}{\frac{1}{0.1} + \frac{1 - 0.7}{0.7} \left( \frac{0.2830 m}{0.3066 m} \right)} = 6126 W$$

The convective heat transfer rate across the thin layer of air in the annular space was determined using equation 4.101 from A. F. Mills which gives the three correlations for the Nusselt number (shown below) for large aspect ratio enclosures with heated and cooled walls and recommends using the largest Nusselt number of the three, which for this case is  $Nu_2$ .

$$Nu_1 = 0.0605 Ra_L^{1/3}, Nu_2 = \left\{ 1 + \left[ \frac{0.104 Ra_L^{0.293}}{1 + \left( \frac{6310}{Ra_L} \right)^{1.36}} \right]^3 \right\}^{1/3}, Nu_3 = 0.242 \left( \frac{Ra_L}{\frac{H}{L}} \right)^{0.272}$$

Combining the standard relationships for Nusselt number, Rayleigh number, and the convective heat transfer rate equation yields

$$q_{3-5conv} = \left\{ 1 + \left[ \frac{0.104 \left( \frac{g\beta(T_5 - T_3)L_{annular}^3}{\alpha_{air} \nu_{air}} \right)^{0.293}}{1 + \left( \frac{6310}{\left( \frac{g\beta(T_5 - T_3)L_{annular}^3}{\alpha_{air} \nu_{air}} \right)} \right)^{1.36}} \right]^3 \right\}^{1/3} \left( \frac{k_{air}}{L_{annular}} \right) A_5 (T_5 - T_3)$$

which results in the following when the numbers are plugged in.

$$q_{3-5conv} = \left[ 1 + \frac{0.104 \left( \frac{9.81 \frac{m}{s^2}}{(867.126 + 105.028) K} \frac{1}{2} (867.126 - 105.028) K (0.0236217 m)^3 \right)^{0.293}}{\left( 0.000051899 \frac{m^2}{sec} \right) \left( 0.000036148 \frac{m^2}{sec} \right)} \right]^{1/3} \left( \frac{0.03864 \frac{W}{m \cdot K}}{0.0236217 m} \right) 1.9869 m^2 (867.126 - 105.028) K = 7618 W$$

$$1 + \frac{6310}{\left( \frac{9.81 \frac{m}{s^2}}{(867.126 + 105.028) K} \frac{1}{2} (867.126 - 105.028) K (0.0236217 m)^3 \right)^{1.36}} \left( 0.000051899 \frac{m^2}{sec} \right) \left( 0.000036148 \frac{m^2}{sec} \right)}$$

Conduction thru the thin stainless steel inner vessel wall is included in the model and the thermal resistance is negligible. Conduction is computed from Incropera and Dewitt's equation 3.27

$$q_{5-6cond} = \frac{2\pi L_{ext} k_{ss} (T_5 - T_6)}{\ln\left(\frac{r_6}{r_5}\right)} = \frac{2\pi (1.1176 m) \frac{9.3404 W}{m \cdot K} (105.0282 - 103.2336) K}{\ln\left(\frac{0.282956 m}{0.280543 m}\right)} = 13744 W$$

The second heat transfer path starts with radiation and convective heat transfer to the top flange of the cryostat. The hardware attached to the top of the flange is ignored. Although the attached hardware increases the surface area of the flange, the contact resistances at the flanged attachment points and the thermal resistance associated with conduction thru the thin walls of the stainless steel tubes that support the flanges greatly limit additional heat input into the flange.

Radiation heat transfer to the top and sides of the flange was modeled as a small convex object in a large cavity (Equation 13.27 from Incropera and Dewitt) where

$$q_{1-11rad} = \sigma A_{11} \epsilon_{11} (T_1^4 - T_{11}^4) = \frac{5.67 \times 10^{-8} W}{m^2 \cdot K^4} (0.5225 m^2) (0.7) \left[ (922 K)^4 - (844.236 K)^4 \right] = 4452 W$$

Convective heat transfer to the top flange is modeled as the upper surface of a cooled plate using equation 9.32 from Incropera and Dewitt which results in the following when the Rayleigh number and Nusslet number are plugged into the convective heat transfer equation.

$$q_{1-11conv} = 0.27 \left( \frac{g\beta(T_1 - T_{11})L_{top}^3}{\alpha_{air}v_{air}} \right)^{1/4} \left( \frac{k_{air}}{L_{top}} \right) A_{11} (T_1 - T_{11})$$

$$q_{1-11conv} = 0.27 \left( \frac{9.81 \frac{m}{s^2} \frac{1}{(922 + 844.236)K} (922 - 844.236)K (0.2381m)^3}{2 \left( 0.0001376 \frac{m^2}{sec} \right) \left( 0.00009689 \frac{m^2}{sec} \right)} \right)^{1/4} \left( \frac{0.06143 \frac{W}{m \cdot K}}{0.2381m} \right) 0.5225m^2 (922 - 844.236)K = 86.57$$

The radiation and convective heat loads are then conducted thru the top flange which was modeled as 1D conduction using the entire cross-sectional area of the flange

$$q_{11-10cond} = \frac{k_{ss} A_{10} (T_{11} - T_{10})}{L_{10}} = \frac{23.082W}{m \cdot K} \frac{(0.3832m^2)(844.236 - 824.687)K}{0.0381m} = 4538W$$

The heat then radiates from the top flange to the liquid argon. Heat input will cause vapor to be generated which will flow out the relief valve. At the high rate of vapor generation during a fire, a convection cell transferring heat from the underside of the flange to the liquid surface will not form. Instead, vapor leaving the cryostat will remove heat from the flange as it exits. The vapor being relieved intercepts heat before it reaches the liquid argon. Due to the difficulty of modeling heat transfer that results from a three dimensional gas flow, this interception of heat is ignored which is the conservative approach.

Radiation from the top flange to the liquid argon is modeled as exchange between two parallel planes using Incropera and Dewitt equation 13.24 where

$$q_{10-12rad} = \frac{A_{12} \sigma (T_{10}^4 - T_{12}^4)}{\frac{1}{\epsilon_{10}} + \frac{1}{\epsilon_{12}} - 1} = \frac{0.2473m^2 \frac{5.67 \times 10^{-8}W}{m^2 \cdot K^4} (824.687^4 - 103.234^4)K^4}{\frac{1}{0.7} + \frac{1}{1.0} - 1} = 4538W$$

The combined heat load from both paths is 13744 + 4538 = 18282 W. For the CGA calculation this must be converted to an overall heat transfer coefficient to the liquid.

$$h = \frac{q}{A\Delta T} = \frac{18282W}{2.408m^2(922 - 103.234)K} \times \frac{1}{1W} \frac{1J}{sec} \times \frac{1Btu}{1055.06J} \times \frac{3600sec}{hr} \times \frac{1m^2}{10.7639ft^2} \times \frac{1K}{1.8R} = 1.633 \frac{Btu}{hr \cdot ft^2 \cdot ^\circ F}$$

To calculate the initial estimate of the relief capacity needed, a gas factor,  $G_i$ , must be computed. When the flow rating pressure is less than 40% of the critical pressure ( $\frac{60.2psia}{705.4psia} \cdot 100 = 8.5\%$ ), the following is used to compute  $G_i$ .

$$G_i = \frac{73.4(1660 - T)}{CL} \sqrt{\frac{ZT}{M}}$$

where

$L =$  Latent heat of product at flow rating pressure,  $63.33 \frac{Btu}{lb_m}$  for saturated conditions at 60.2 psia.

$C =$  Constant for vapor related to ratio of specific heats ( $k=c_p/c_v$ ) at standard conditions.  $k = 1.67$  for Argon at 60 °F and 14.696 psia which corresponds to  $C = 378$ .

$Z =$  Compressibility factor for saturated vapor at 60.2 psia

$$Z = \frac{Pv}{RT}, \quad Z = \frac{60.2(0.7531)144}{\frac{1545}{39.948}(185.8)} = 0.909.$$

$T =$  Flow rating temperature, 185.8 °R.

$M =$  Molecular weight of gas, 39.948.

$v =$  specific volume, saturated vapor at flow rating pressure of 60.2 psia,  $0.7531 \frac{ft^3}{lb_m}$ .

$$G_i \text{ is calculated to be } \frac{73.4(1660 - 185.8)}{378 \cdot 63.33} \sqrt{\frac{0.909 \cdot 185.8}{39.948}} = 9.30.$$

The uncorrected volumetric flow rate was found to be

$$Q_{ae} = 1.0 \cdot 9.30 \cdot 1.633 \cdot 25.90^{0.82} = 219 \frac{ft^3}{min} \text{ of free air}$$

The relief valve is attached to the cryostat thru piping of length less than 2 feet, thus the correction factor F does not have to be calculated according to CGA section 5.1.4

The primary relief on both cryostats is an Anderson Greenwood Type 81 with the F orifice. Anderson Greenwood

provides the following sizing formula  $A = \frac{V\sqrt{MTZ}}{6.32CKP_1}$  where

$A =$  required orifice area, in<sup>2</sup>.

$V =$  required capacity, 219 SCFM for free air.

$M =$  molecular weight of gas, 29 for air (The CGA formula converts the required argon mass flow rate to air).

$T =$  relief temperature, 520 °R for air at standard conditions.

$Z =$  compressibility factor, 1.0

$C =$  gas constant based on ratio of specific heats, 356 for air

$K =$  nozzle coefficient, 0.816 (derived from manufacturer testing)

$P_1 =$  inlet flowing pressure, psia =  $1.21 \times (35 + 15) - 15 + 14.7 = 60.2$  psia

$$A = \frac{219\sqrt{29 \cdot 520 \cdot 1.0}}{6.32 \cdot 356 \cdot 0.816 \cdot 60.2} = 0.243 \text{ in}^2$$

The “F” size Anderson Greenwood relief valves (PSV-210-Ar and PSV-377-Ar) have an orifice of 0.307 in<sup>2</sup> which is larger than the required 0.243 in<sup>2</sup> and thus the relief valves are adequate for the fire condition.

#### Loss of Vacuum Condition (both Luke and Bo)

Because the fire condition includes atmospheric air in the vacuum space, the fire calculation also indicates the relief capacity is more than adequate for an operational loss of insulating vacuum.

#### Vapor Generation Due to Internal Heaters (both Luke and Bo)

There are three heaters in the Material Test Station cryostat that can provide heat input into the liquid argon. Two of the heaters are 250 W, and the third heater is 1500 W. If operated together, they could provide 2000 W of heat into the liquid argon. This is nine times less than the 18282 W considered for the fire condition. The TPC cryostat contains one 250 W pressure building heater. Thus both of the cryostats are adequately relieved when vapor generation from their respective internal electrical heaters are considered.

#### Vapor Generation Due to the Materials Lock (Luke only)

The Material Test Station cryostat has a unique feature that will allow the insertion of room temperature materials into the liquid argon. Figure 4 details this feature referred to as the materials lock. The room temperature sample will be placed into a basket that resides in an 8 inch conflat cross. While in the cross, the basket is separated from the cryostat argon vapor space by a gate valve. The cross can either be purged with argon or evacuated before the gate valve is opened. This prevents the transfer of atmospheric contamination into the ultra-pure liquid argon in the cryostat. To lower a sample into the cryostat, the gate valve is opened and a rod attached to the top of the basket moves the basket downward. The rod is moved vertically by a screw and stepper motor combination. The basket is dropped onto a platform that is attached to a second screw and stepper motor combination. The rod then retracts and the gate valve is closed. As the platform lowers the sample into the liquid, both the sample and material basket will generate vapor. Typically the platform would be lowered at a rate that limits the vapor generation to a rate that can be matched by the nitrogen heat exchanger so the argon space is closed. If the nitrogen heat exchanger is overpowered, then excess vapor is vented thru a pneumatic valve (EP-205-Ar). PSV-313-Ar set at 10 psig will vent the material lock if the gate valve is open. As a last resort, the excess vapor will vent thru the cryostat relief valve (PSV-210-Ar). Thus a limit must be imposed on the size of test samples so that the relief valve cannot be over powered.

A paper entitled “Nucleate Boiling of Nitrogen, Argon, and Carbon Monoxide From Atmospheric to Near the Critical Pressure” by C. Johler and E. L. Park published in Advances in Cryogenic Engineering Volume 15 contains experimental critical heat flux data for liquid argon. From the paper it appears that the critical heat flux for argon does not exceed 100 W / in<sup>2</sup>. The critical heat flux value for liquid argon is an upper limit for heat input into the liquid.

The material basket was fabricated from sixteen 1/8 inch diameter 304 SS rods, each with a length of 16.5 inches. The surface area of these rods is then  $\pi \times 0.125 \times 16.5 \times 16 = 103.7$  in<sup>2</sup>. The volume of the rods is  $(\pi / 4) \times 0.125^2 \times 16.5 \times 16 = 3.240$  in<sup>3</sup>.

A conical strip of metal at the bottom of the basket has a surface area estimated as  $\pi \times 4.9 \times 0.75 \times 2 = 23.1$  in<sup>2</sup> (this includes both sides of the strip). The volume of the strip is estimated as  $(\pi / 4) \times (4.9^2 - 4.7125^2) \times 0.1 = 0.142$  in<sup>3</sup>.

The surface area of the cylinder at the top of the basket is  $\pi \times 1 \times 1 + (\pi / 4) \times 1^2 \times 2 = 4.71 \text{ in}^2$ . Its volume is estimated as  $(\pi / 4) \times 1^2 \times 1 = 0.785 \text{ in}^3$ .

The small disk at the bottom of the basket has a surface area of  $(\pi / 4) \times 1.5^2 \times 2 = 3.53 \text{ in}^2$  (including both sides). Its volume is  $(\pi / 4) \times 1.5^2 \times 0.1 = 0.177 \text{ in}^3$ .

The surface area of the horizontal strips that make up the door are estimated as  $(\pi / 4) \times (5.5^2 - 5.25^2) \times 2 \times 2 + \pi \times 5.5 \times 0.125 \times 2 + \pi \times 5.25 \times 0.125 \times 2 = 16.89 \text{ in}^2$ . The strips have an approximate volume of  $(\pi / 4) \times (5.5^2 - 5.25^2) \times 0.125 \times 2 = 0.528 \text{ in}^3$ .

The platform the basket rests on has a surface area of  $(\pi / 4) \times (8^2 - 4.5^2) \times 2 + \pi \times 8 \times 0.375 + \pi \times 4.5 \times 0.375 = 83.4 \text{ in}^2$ . The estimated volume of the platform is  $(\pi / 4) \times (8^2 - 4.5^2) \times 0.375 = 12.885 \text{ in}^3$ .

The 3 bearings and drive mechanism that ride with the platform have a surface area estimated as  $(\pi / 4) \times (2.16^2 - 0.5^2) \times 2 \times 4 + \pi \times 2.16 \times 1 \times 4 = 54.9 \text{ in}^2$ . The volume of these components is  $(\pi / 4) \times (2.16^2 - 0.5^2) \times 1 \times 4 = 13.872 \text{ in}^3$ .

Thus the total surface area is  $290.2 \text{ in}^2$ . The total volume of the components that can move in and out of the liquid is  $31.629 \text{ in}^3$  of SS 304.

The density of SS 304 is  $0.28 \text{ lb} / \text{in}^3$ . The amount of stainless steel contained in the moving parts is then  $31.629 \text{ in}^3 \times 0.28 \text{ lb} / \text{in}^3 = 8.86 \text{ lb}$ . SS 304 cooled from 300 K to 87 K rejects about  $37,143 \text{ J} / \text{lb}$ . Thus the moving parts will input  $8.86 \text{ lb} \times 37143 \text{ J} / \text{lb} = 329,087 \text{ J}$  into the liquid argon.

The latent heat of argon is about  $73,420 \text{ J} / \text{lb}$ . Thus  $329,087 \text{ J} / 73,420 \text{ J} / \text{lb} = 4.48 \text{ lb}$  of saturated vapor produced by the warm components entering the liquid. At the 35 psig MAWP of the vessel, the density of vapor is  $1.11 \text{ lb} / \text{ft}^3$ . The volume of vapor produced at MAWP is then  $4.48 \text{ lb} / 1.11 \text{ lb} / \text{ft}^3 = 4.04 \text{ ft}^3$  or 114.4 liters. In a 250 liter vessel with little vapor space, this heat input can significantly increase the vapor pressure and must be relieved. If the parts could sustain critical heat flux, it would take

$$\frac{329,087 \text{ J}}{1} \times \frac{1}{290.2 \text{ in}^2} \times \frac{\text{in}^2}{100 \text{ W}} \times \frac{1 \text{ W}}{\frac{1 \text{ J}}{1 \text{ S}}} = 11.34 \text{ sec}$$

to produce the vapor.

The capacity of the relief valve PSV-210-Ar for cold argon vapor can be calculated in the following manner

$$W = \frac{ACKP_1 \sqrt{M}}{\sqrt{TZ}} \text{ where}$$

A = orifice area of relief valve,  $0.307 \text{ in}^2$ .

W = maximum capacity,  $\text{lb} / \text{hr}$

M = molecular weight of gas, 40 for argon

T = relief temperature,  $183.57 \text{ }^\circ\text{R}$  for saturated argon vapor venting at 54.7 psia (110% MAWP)

Z = compressibility factor, 1.0

C = gas constant based on ratio of specific heats, 378 for argon

K = nozzle coefficient, 0.816 (derived from manufacturer testing)

$P_1 =$  inlet flowing pressure, psia =  $1.10 \times (35 + 15) - 15 + 14.7 = 54.7$  psia

The capacity of the relief valve when venting cold vapor is found to be

$$W = \frac{0.307 \cdot 378 \cdot 0.816 \cdot 54.7 \sqrt{40}}{\sqrt{183.57 \cdot 1.0}} = 2418 \frac{lb}{hr}$$

The latent heat of saturated liquid argon at the relieving pressure of 54.7 psia is 63.88 Btu / lbm. The mass flow rate is multiplied by the latent heat and converted to Watts as follows

$$2418 \frac{lb}{hr} \times 63.88 \frac{Btu}{lb} \times \frac{1055.06J}{Btu} \times \frac{1hr}{3600sec} = 45269 \text{ Watts}$$

Thus the maximum heat input into the cryostat that can be relieved as cold vapor is 45,269 W. 45,269 W divided by the 100 W per square inch critical heat flux yields 452.7 square inches of surface area. The material basket, the platform it rides on, and the associated hardware that moves in and out of the liquid has a surface area of 290.2 in<sup>2</sup>. Thus material samples with a surface area of less than 452.7 – 286.7 = 162.5 square inches cannot overwhelm the relief valve. A procedure will be developed for material insertion. The procedure will require the signature of two people who state that they have measured the surface area of the material and that it is less than 162.5 in<sup>2</sup>. In the future a material basket with less surface area may be constructed. However, the total surface area of 452.7 square inches for the combined material basket and test sample will not be exceeded.

#### Filling of the Cryostats (both Luke and Bo)

Both cryostats are filled from FNAL stock room high pressure liquid argon dewars. The reliefs on these 160 liter dewars are set at 350 psig. The flow path from the argon dewars to the cryostats has several restrictions such as valves and filters. Normal filling operation involves cooling down the transfer line by venting the argon just before the cryostat. Once liquid appears at the vent, the flow is then directed into the cryostat. To simplify the calculations, it is assumed that liquid at 350 psig exits the stockroom dewars and enters the cryostat at 35 psig. Once in the warm cryostat the liquid is assumed to completely vaporize and exit as room temperature gas. This is a very conservative calculation because the flashing due to the reduction in pressure from 350 psig to 35 psig will result in a large amount of vapor generation. The amount of vapor generated during this constant enthalpy pressure reduction can be calculated as

$$x = \frac{m_{vapor}}{m_{liquid} + m_{vapor}} = \frac{h_{350 \text{ psig saturated liquid}} - h_{35 \text{ psig saturated liquid}}}{h_{35 \text{ psig saturated gas}} - h_{35 \text{ psig saturated liquid}}} = \frac{-211.8 - (-257.4)}{-107.6 - (-257.4)} = 0.304$$

where the enthalpies are in kJ/kg. Thus, ignoring any heat input into the transfer line, the vapor will be 30% of the total mass flow. The area occupied by the vapor is therefore substantial and will lead to the actual mass flow rate being much smaller than the calculated liquid only flow rate.

Figure 4.1a.3 describes the flow resistance of the valves, fittings, and tubing in the LAr transfer line. The calculations are for the flow path from the supply dewars to Luke. To get liquid into Bo from the stock room dewars takes an additional 13 feet of piping. The restriction provided by this additional length of piping means that the flow rate into Bo will be less than that achieved during the filling of Luke. The flow resistance offered by the orifice and filters is described below. All equations were solved in the EES simultaneous equation solver which computed the mass flow rate based upon the sum of the resistances and the known inlet and outlet pressures. The pressure drop is divided into two parts. The 1<sup>st</sup> part is the pressure drop across the orifice at the beginning of the transfer line. The 2<sup>nd</sup> part of the pressure drop corresponds to the loss across the sum of the flow resistances in the transfer line.

The pressure drop across the orifice is calculated from Crane equation 3-19

$$W = 1891d_{orifice}^2 C \sqrt{(P_1 - P_2) \rho_{LAr}}$$

where

$W$  = the mass flow rate thru the transfer line when filling Luke in lb/hr, calculated as 1436.6 lb / hr.

$d_{orifice}$  = diameter of the orifice, selected to be 0.122 in.

$C$  = flow coefficient for orifices and nozzles corrected for velocity of approach, 0.61 based on page A-20 of Crane and Reynolds number. The Reynolds number was calculated from  $Re = 6.31 \frac{W}{d_1 \mu}$  where  $\mu$  = the absolute viscosity of liquid argon at the orifice inlet condition, 0.07513 centipoise.  $Re = 6.31 \frac{1436.6}{0.305 \cdot .07513} = 395596$

$\rho_{LAr}$  = density of saturated liquid argon at orifice inlet pressure, 63.39 lb / ft<sup>3</sup>

$P_1$  = orifice inlet pressure, 364.7 psia.

$P_2$  = orifice outlet pressure, calculated as 254.9 psia

There are two filters in the system that create flow resistance. One filter is a molecular sieve while the other filter is an oxygen filter. The filter materials are loaded into identical housings. To calculate an equivalent flow resistance for each filter, the pressure drop equation for each filter was set equal to the pressure drop equation for discharge of fluid thru pipe. The filter pressure drop equation is taken from Union Carbide Molecular Sieve Literature which is available in the appendix. The pipe pressure drop equation used to calculate resistance coefficients ( $K_{filter}$ ) for each filter is Crane 410 equation 3-19.

$$\Delta P_{filter} = \frac{f_T C_t G^2 L}{\rho_{filter} D_p} = \Delta P_{pipe} = \left( \frac{W}{1891 d_1^2} \right)^2 \frac{K_{filter}}{\rho_{filter}} \Rightarrow K_{filter} = \frac{f_T C_t G^2 L}{\rho_{filter} D_p} \left( \frac{W}{1891 d_1^2} \right)^2,$$

where

$f_T$  = friction factor determined from the modified Reynolds's number of  $Re_{mod} = \frac{D_p G}{\mu_{filter}}$  and plot in the Union Carbide literature .

$C_t$  = pressure drop coefficient determined from plot in Union Carbide literature for external void fraction of 0.37,  $3.6 \times 10^{-10}$ .

$G$  = superficial mass velocity,  $G = \frac{W}{A_{filter}} = \frac{1436.6 \frac{lb}{hr}}{0.0261 ft^2} = 55042 \frac{lb}{hr \cdot ft^2}$

$A_{filter}$  = cross-sectional area of the filter, 0.0261 ft<sup>2</sup> (2.1875 in. ID).

$\mu_{filter}$  = liquid argon viscosity, 0.2894 lb/(ft\*hr) (saturated liquid at 152.3 psia)

$D_p$  = effective particle diameter of filter material,  $D_p = 0.003693$  ft for oxygen,  $D_p = 0.00666$  f. for molecular sieve.

$L$  = length of filter bed, 2.33 ft.

$\rho_{filter}$  = density liquid argon, 73.94 lb / ft<sup>3</sup> (saturated liquid argon at 152.3 psia)

$K_{filter}$  = resistance coefficient for filter

The modified Reynolds number for each filter is

$$Re_{mod,oxygen} = \frac{(.003693 \text{ ft})}{0.2894 \frac{\text{lb}}{\text{ft} \cdot \text{hr}}} \frac{55042 \text{ lb}}{\text{hr} \cdot \text{ft}^2} = 702.3, \quad Re_{mod,molecular \text{ sieve}} = \frac{(.00666 \text{ ft})}{0.2894 \frac{\text{lb}}{\text{ft} \cdot \text{hr}}} \frac{55042 \text{ lb}}{\text{hr} \cdot \text{ft}^2} = 1267.$$

Based on the modified Reynolds numbers,  $f_T$  is about 1.0 for both filters. The equivalent resistance coefficients are then computed as follows

$$K_{filter,oxygen} = \frac{1.0(3.6 \times 10^{-10})55042^2(2.33)}{73.94(.003693)} \frac{73.94}{\left(\frac{1436.3}{1891(0.305)^2}\right)^2} = 10.32, \quad K_{filter,molecular \text{ sieve}} = \frac{1.0(3.6 \times 10^{-10})55042^2(2.33)}{73.94(.00666)} \frac{73.94}{\left(\frac{1436.3}{1891(0.305)^2}\right)^2} = 5.72.$$

The total resistance of the flow path from the point immediately downstream of the orifice to the liquid discharge point in the cryostat is then  $K_{total} = K_{elbows} + K_{tees} + K_{pipe} + K_{enlarge} + K_{contract} + K_{exit} + K_{bends} + K_{valves} + K_{oxygen} + K_{molecular \text{ sieve}} = 7.68 + 2.56 + 49.73 + 1.92 + 0.98 + 1.0 + 12.02 + 135.5 + 10.32 + 5.72 = 227.4$ .

The pressure drop due to the various components of the transfer line was found using Crane equation 3-19

$$W = 1891 d_1^2 \sqrt{\frac{(P_2 - P_3) \rho_{filter}}{K_{total}}} = 1891 (0.305)^2 \sqrt{\frac{(254.9 - 49.7) 73.94}{227.4}} = 1437 \frac{\text{lb}}{\text{hr}}.$$

Thus the total mass flow rate into the cryostat from a 350 psig argon source is 1437 lb/hr. This is a very conservative upper limit because 30% of the mass flow will be vapor which will greatly reduce the total mass flow rate. Added to this already conservative calculation is the assumption that the vapor generated by the liquid vaporized by a warm cryostat vents thru the relief valve at room temperature.

Anderson Greenwood provides the following sizing formula to determine the required orifice area  $A$  when the vapor mass flow rate is known:

$$A = \frac{W \sqrt{TZ}}{CKP_1 \sqrt{M}} \text{ where}$$

$A$  = required orifice area, in<sup>2</sup>.

$W$  = required capacity, 1437 lb/hr (maximum liquid flow rate thru transfer line)

$M$  = molecular weight of gas, 40 for argon

$T$  = relief temperature, 520 °R for air at standard conditions.

Z = compressibility factor, 1.0

C = gas constant based on ratio of specific heats, 378 for argon

K = nozzle coefficient, 0.816 (derived from manufacturer testing)

$P_1$  = inlet flowing pressure, psia =  $1.10 \times (35 + 15) - 15 + 14.7 = 54.7$  psia

The required orifice area is therefore  $A = \frac{1437\sqrt{520 \cdot 1.0}}{378 \cdot 0.816 \cdot 54.7\sqrt{40}} = 0.307 \text{ in}^2$ .

The “F” size Anderson Greenwood relief has an orifice of 0.307 in<sup>2</sup> which is equal to the required 0.307 in<sup>2</sup> and thus the relief valve is adequate for the filling condition described by this very conservative calculation.

If the cryostat is full of liquid and liquid is forced out the relief valve, then Anderson Greenwood recommends the following sizing formula for determining liquid capacity.

$$A = \frac{V_L \sqrt{G}}{38KK_pK_wK_v\sqrt{P_A - P_B}} \text{ where}$$

A = required orifice area, in<sup>2</sup>.

K = nozzle coefficient, 0.816 (derived from manufacturer testing).

$P_A$  = inlet flowing pressure, psig =  $1.10 \times (35 + 15) - 15 = 40$  psig.

$P_b$  = back pressure, 0 psig.

$V_L$  = required capacity, GPM. Density of saturated liquid argon at inlet pressure of 40 psig is 81.18 lb / ft<sup>3</sup>.

$$\text{Converting units yields } 1437 \frac{\text{lb}}{\text{hr}} \times \frac{\text{ft}^3}{81.18 \text{ lb}} \times \frac{1 \text{ hr}}{60 \text{ min}} \times \frac{7.48052 \text{ gal}}{\text{ft}^3} = 2.20 \frac{\text{gal}}{\text{min}}$$

$$G = \text{Specific gravity, } G = \frac{\rho_{LAr}}{\rho_{H2O}} = \frac{81.18 \frac{\text{lb}}{\text{ft}^3}}{62.38 \frac{\text{lb}}{\text{ft}^3}} = 1.30.$$

$K_w$  = back pressure correction factor, 1.0.

$K_v$  = viscosity correction factor, based on plot from AgCo literature and Reynolds number R.

$$R = \frac{V_L(2800G)}{\mu\sqrt{A}} \text{ where } \mu = 0.1757 \text{ cp for liquid argon saturated at 40 psig and } A = 0.307 \text{ in}^2 \text{ for the relief valve}$$

$$\text{orifice area. Thus } R = \frac{2.2(2800 \cdot 1.30)}{0.1757\sqrt{0.307}} = 82259 \text{ and from plot } K_v = 1.0$$

$K_p$  = overpressure correction factor, 1.0.

The required orifice area for relieving liquid from the cryostat during filling is then

$$A = \frac{2.2\sqrt{1.30}}{38(0.816)1.0(1.0)1.0\sqrt{40-0}} = 0.0128 \text{ in}^2 \text{ and the selected relief valve orifice area is adequate.}$$

#### Introduction of bleed up and contamination gas (both Luke and Bo)

As part of the contamination study program, gas phase impurities will be introduced into the Material Test Station cryostat. Typically, certified bottles of gas will be purchased from vendors such as 100 ppm nitrogen in argon. A sample bottle of known size will be pressurized to a known pressure and then the gas will be introduced into the cryostat. Two high purity bottle regulators have been purchased for this application. One is a Parker Veriflow 735 bottle regulator with a  $C_v$  of 0.04. The other is a Matheson 9460 series with a  $C_v$  of 0.05.

For room temperature argon gas with a small amount of contamination, the flow capacity of the relief valve is computed using the equation supplied by Anderson Greenwood:

$$V = \frac{6.32ACKP_1}{\sqrt{MTZ}} \text{ where}$$

$A$  = orifice area, 0.307 in<sup>2</sup>.

$V$  = relief valve capacity, SCFM argon

$M$  = molecular weight of gas, 40 for argon

$T$  = relief temperature, 520 °R for argon at standard conditions.

$Z$  = compressibility factor, 1.0

$C$  = gas constant based on ratio of specific heats, 378 for argon

$K$  = nozzle coefficient, 0.816 (derived from manufacturer testing)

$P_1$  = inlet flowing pressure, psia = 1.10 x (35 + 15) - 15 + 14.7 = 54.7 psia

$$V = \frac{6.32(0.307)378(0.816)54.7}{\sqrt{40 \cdot 520 \cdot 1.0}} = 227 \text{ SCFM argon}$$

The maximum flow from the regulator with the larger  $C_v$  is computed using the equation recommended by Swagelock for high pressure drop flow:

$$q = 0.471N_2C_vP_1\sqrt{\frac{1}{G_gT_1}} \text{ where}$$

$N_2$  = constant with value of 22.67 for units of psia, °R, and SCFM

$C_v$  = flow coefficient, 0.05.

$P_1$  = regulator inlet pressure, 3000 psia

$G_g$  = gas specific gravity, 1.38 for argon

$T_1$  = gas temperature, 520 °R

$$q = 0.471(22.67)0.05(3000)\sqrt{\frac{1}{(1.38)520}} = 59.8 \text{ SCFM argon.}$$

Thus the cryostat relief valve capacity of 227 SCFM argon is nearly 4 times that of the high purity regulator capacity of 59.8 SCFM argon.

Under certain conditions, it will be desired to bleed up either cryostat with argon gas. This would be done with the inert gas regulator available in the FNAL stock room, the Victor VTS450B, has a maximum flow rate of 1750 SCFH air which is 29.2 SCFM. This air flow rate, converted to argon using the method found in ASME mandatory Appendix 11, is equivalent to 36.4 SCFM argon. Thus the cryostat cannot be over pressurized using a typical stockroom bottle regulator.

#### RD-302-Ar and RD-376-Ar

RD-302-Ar and RD-376-Ar are identical rupture disks with 55 psig set points attached to both Luke and Bo. ASME coded relief valves PSV-210-Ar and PSV-377-Ar have capacity for all relief scenarios. RD-302-Ar and RD-376-Ar are not ASME coded rupture disc because of purity concerns. Fully welded rupture discs cannot be ASME coded. A rupture disc holder has an o-ring seal that will allow oxygen diffusion into the ultra pure argon. RD-302-Ar and RD-376-Ar have a 10% burst tolerance such that the burst pressure range is 49.5 to 55 psig. The capacity of RD-302-Ar and RD-376-Ar is calculated per ASME Section VIII

$$W = K_d CAP \sqrt{\frac{M}{TZ}} \text{ where}$$

$W$  = rated flow capacity, lb/hr.

$K_d$  = coefficient of discharge (0.62 for rupture disc devices).

$C$  = constant based on the ratio of specific heats, 378 for argon.

$A$  = minimum net flow area, rupture disc size is for 1.5 inch pipe but will use ID of 1.5 inch tube that rupture disc is mounted on to be conservative.  $A = \left(\frac{\pi}{4}\right)1.37^2 = 1.47 \text{ in}^2$ .

$P$  = inlet pressure, 69.7 psia.

$M$  = Molecular weight, 40 for argon.

$T$  = absolute temperature, 530 R.

$Z$  = compressibility factor, use 1.0 to be conservative.

The rupture disc capacity is then

$$W = (0.62)378(1.47)69.7\sqrt{\frac{40}{530(1.0)}} = 6615 \frac{\text{lb}}{\text{hr}}$$

which converts to SCFM argon as

$$6615 \frac{\text{lb}}{\text{hr}} \times \frac{1 \text{ hr}}{60 \text{ min}} \times \frac{\text{ft}^3}{0.1034 \text{ lb}} = 1066 \frac{\text{ft}^3}{\text{min}}$$

### Vent Pressure Drop for PSV-210-Ar (Luke ASME coded relief)

Previously in this document, the maximum capacity of PSV-210-Ar was found to be 227 SCFM argon. PSV-210-Ar vents outside PAB thru a tube with a 2 inch internal diameter. It is assumed that the inlet pressure of the vent pipe is the pressure rise above atmospheric pressure required for 227 SCFM of argon to flow thru the vent.

It is unlikely the system can supply 227 SCFM of warm argon gas. The filling calculation that matches the relief valve capacity of 227 SCFM argon ignores the mass flow reduction due to vapor generation so it is very conservative.

The vent piping run has a length of 18 feet with two elbows one tee. Crane 410 offers the following equation identified as 3-20 for the discharge of fluid thru valves, fittings, and pipe for compressible flow:

$$q'_m = 412 \frac{Yd^2}{S_g} \sqrt{\frac{\Delta P \rho_1}{K}} \text{ which can be re-arranged as } \Delta P = \left( \frac{q'_m S_g}{412 Y d^2} \right)^2 \frac{K}{\rho_1} \text{ where}$$

$q'_m$  = 227 SCFM, rate of argon flow in cubic feet per minute at std. conditions (14.7 psia and 60 F)

$Y$  = 0.97, net expansion factor for compressible flow thru orifices, nozzles, or pipe. Estimated using charts on page A-22 in Crane 410.

$d$  = 2.0 inches, internal diameter of vent piping.

$S_g$  = 1.379, specific gravity of argon relative to air = the ratio of the molecular weight of argon to that of air (39.95/28.97).

$\Delta P$  = psi, pressure drop thru vent piping.

$\rho_1$  = 0.1142 lb/ft<sup>3</sup>, density of argon at inlet of vent tubing.

$K$  =  $K_{elbows} + K_{tee} + K_{pipe} + K_{exit}$ , resistance coefficient for flow thru the exhaust piping which consists of 2 elbows, 1 tee, straight pipe, and the resistance due to the pipe exit.

$f_T$  = 0.019, friction factor in zone of complete turbulence for 2 inch internal diameter pipe.

$$K_{elbows} = 2 \times 30 \times f_T = 2 \times 30 \times 0.019 = 1.14.$$

$$K_{tee} = 20 \times f_T = 20 \times 0.019 = 0.38.$$

The Reynolds number is calculated from

$$Re = \frac{0.482q'_h S_g}{d\mu} \text{ where}$$

$q'_h$  = 13,620 SCFH, rate of flow, in cubic feet per hour at standard conditions (14.7 psia and 60 F).

$\mu$  = 0.02211 centipoise, dynamic viscosity of argon.

$$\text{The Reynolds number is then } Re = \frac{0.482(13620)1.379}{(2)0.02211} = 204724.$$

$f$  = 0.021, friction factor estimated from Reynolds number and plot on page A-25 of Crane 410.

$L$  = 216 inches, length of pipe.

$$K_{pipe} = f \frac{L}{d} = 0.021 \frac{216}{2} = 2.268, \text{ resistance due to straight pipe.}$$

$K_{exit}$  = 1.0, resistance of the pipe exit.

Thus the total resistance is  $K = 1.14 + 0.38 + 2.268 + 1.0 = 4.788$ .

The pressure drop for 227 SCFM of argon thru the vent piping is then

$$\Delta P = \left( \frac{227(1.379)}{412(0.97)2^2} \right)^2 \frac{4.788}{0.1167} = 1.573 \text{ psi which is a negligible fraction of the available pressure.}$$

### Vent Pressure Drop for PSV-377-Ar (Bo ASME coded relief)

Previously in this document, the maximum capacity of PSV-377-Ar was found to be 227 SCFM argon. PSV-377-Ar vents outside PAB thru a pipe with a 2.635 inch internal diameter (2.5 in. SCH 10). It is assumed that the inlet pressure of the vent pipe is the pressure rise above atmospheric pressure required for 227 SCFM of argon to flow thru the vent.

It is unlikely the system can supply 227 SCFM of warm argon gas. The filling calculation that matches the relief valve capacity of 227 SCFM argon ignores the mass flow reduction due to vapor generation so it is very conservative.

The vent piping run has a length of 31 feet with five elbows one tee. Crane 410 offers the following equation identified as 3-20 for the discharge of fluid thru valves, fittings, and pipe for compressible flow:

$$q'_m = 412 \frac{Yd^2}{S_g} \sqrt{\frac{\Delta P \rho_1}{K}} \text{ which can be re-arranged as } \Delta P = \left( \frac{q'_m S_g}{412 Y d^2} \right)^2 \frac{K}{\rho_1} \text{ where}$$

$q'_m$  = 227 SCFM, rate of argon flow in cubic feet per minute at std. conditions (14.7 psia and 60 F)

$Y$  = 0.97, net expansion factor for compressible flow thru orifices, nozzles, or pipe. Estimated using charts on page A-22 in Crane 410.

$d$  = 2.635 inches, internal diameter of vent piping.

$S_g$  = 1.379, specific gravity of argon relative to air = the ratio of the molecular weight of argon to that of air (39.95/28.97).

$\Delta P$  = psi, pressure drop thru vent piping.

$\rho_1$  = 0.1142 lb/ft<sup>3</sup>, density of argon at inlet of vent tubing.

$K$  =  $K_{elbows} + K_{tee} + K_{pipe} + K_{exit}$ , resistance coefficient for flow thru the exhaust piping which consists of 5 elbows, 1 tee, straight pipe, and the resistance due to the pipe exit.

$f_T$  = 0.021, friction factor in zone of complete turbulence for 2.635 inch internal diameter pipe.

$$K_{elbows} = 5 \times 30 \times f_T = 5 \times 30 \times 0.021 = 3.15.$$

$$K_{tee} = 20 \times f_T = 20 \times 0.021 = 0.42.$$

The Reynolds number is calculated from

$$Re = \frac{0.482q'_h S_g}{d\mu} \text{ where}$$

$q'_h$  = 13,620 SCFH, rate of flow, in cubic feet per hour at standard conditions (14.7 psia and 60 F).

$\mu$  = 0.02211 centipoise, dynamic viscosity of argon.

$$\text{The Reynolds number is then } Re = \frac{0.482(13620)1.379}{(2.635)0.02211} = 155389.$$

$f$  = 0.021, friction factor estimated from Reynolds number and plot on page A-25 of Crane 410.

$L$  = 372 inches, length of pipe.

$$K_{pipe} = f \frac{L}{d} = 0.021 \frac{372}{2.635} = 2.965, \text{ resistance due to straight pipe.}$$

$K_{exit}$  = 1.0, resistance of the pipe exit.


Thus the total resistance is  $K = 3.15 + 0.42 + 2.965 + 1.0 = 7.535$ .

The pressure drop for 227 SCFM of argon thru the vent piping is then

$$\Delta P = \left( \frac{227(1.379)}{412(0.97)2.635^2} \right)^2 \frac{7.535}{0.1167} = 0.822 \text{ psi which is a negligible fraction of the available pressure.}$$

#### **CVI-138-V (Luke) and CVI-382-V (Bo)**

These vacuum pumpout ports provide the insulating vacuum space relief for both cryostats. The spring has been removed from each pumpout to lower the relief pressure. The grooves for the retaining clips have been filled with epoxy to prevent a spring from being re-installed. Thus it is basically a small parallel plate relief held shut by the vacuum pressure differential. This CVI model V-1046-31 vacuum pumpout port has a throat area of 1.23 in<sup>2</sup>. According to the CGA, the area of a vacuum relief in sq. in. should be 0.00024 x wc where wc is the water capacity in pounds of the vessel. The water capacity of each vessel is about 66 gallons based on their 250 liter volume. The density of water is about 8.34 lb/gal. Thus the required relief area is 0.00024 x 66 x 8.34 = 0.132 in<sup>2</sup>. Since the CVI pumpout throat area is much larger than the required relief area, the cryostat vacuum spaces are adequately relieved.



$$\begin{aligned} \text{External surface area} &= \pi \times 24.31 \times 44 + \pi \times 27.5 \times 2.5 + \pi / 4 \times 27.5^2 + \pi / 4 \times (27.5^2 - 24.31^2) = 4300 \text{ in}^2 = 29.86 \text{ ft}^2 = 2.777 \text{ m}^2 \\ \text{Internal surface area} &= \pi \times 22.09 \times 40 + \pi / 4 \times 22.09^2 = 3159 \text{ in}^2 = 21.94 \text{ ft}^2 = 2.038 \text{ m}^2 \\ \text{Average surface area} &= 3729 \text{ in}^2 = 25.90 \text{ ft}^2 = 2.408 \text{ m}^2 \end{aligned}$$

Figure 4.1a.1: Dimensions and capacities of the Materials Test Station Cryostat and the TPC cryostat





Figure 4.1a.2: Heat transfer mechanisms during fire for both Luke and Bo.



Note: The TPC cryostat (Bo) is filled thru the same path as Luke. Bo has about 13 feet of additional piping such that Bo's maximum filling rate will be less than that of Luke. Thus using this maximum filling rate calculation is conservative for Bo.

Figure 4.1a.3: Filling of material test station cryostat (Luke)

# AirLock





Figure 4.1a.4: Material lock details.

## **4.1aa – Supporting Documentation for Relief Valve Calculations**

TABLE 13.3 Special Diffuse, Gray, Two-Surface Enclosures

Large (Infinite) Parallel Planes




$$A_1 = A_2 = A$$

$$F_{12} = 1$$

$$q_{12} = \frac{A\sigma(T_1^4 - T_2^4)}{\frac{1}{\epsilon_1} + \frac{1}{\epsilon_2} - 1} \quad (13.24)$$

Long (Infinite) Concentric Cylinders




$$\frac{A_1}{A_2} = \frac{r_1}{r_2}$$

$$F_{12} = 1$$

$$q_{12} = \frac{\sigma A_1 (T_1^4 - T_2^4)}{\frac{1}{\epsilon_1} + \frac{1 - \epsilon_2}{\epsilon_2} \left(\frac{r_1}{r_2}\right)} \quad (13.25)$$

Concentric Spheres




$$\frac{A_1}{A_2} = \frac{r_1^2}{r_2^2}$$

$$F_{12} = 1$$

$$q_{12} = \frac{\sigma A_1 (T_1^4 - T_2^4)}{\frac{1}{\epsilon_1} + \frac{1 - \epsilon_2}{\epsilon_2} \left(\frac{r_1}{r_2}\right)^2} \quad (13.26)$$

Small Convex Object in a Large Cavity



$$\frac{A_1}{A_2} \approx 0$$

$$F_{12} = 1$$


$$q_{12} = \sigma A_1 \epsilon_1 (T_1^4 - T_2^4) \quad (13.27)$$

tween surfaces 1 and 2 is given by Equation 13.24. However, with the radiation shield, additional resistances are present, as shown in Figure 13.12b, and the heat transfer rate is reduced. Note that the emissivity associated with one side of the shield ( $\epsilon_{3,1}$ ) may differ from that associated with the opposite side ( $\epsilon_{3,2}$ ) and the radiosities will always differ. Summing the resistances and recognizing that  $F_{13} = F_{32} = 1$ , it follows that

$$q_{12} = \frac{A_1 \sigma (T_1^4 - T_2^4)}{\frac{1}{\epsilon_1} + \frac{1}{\epsilon_2} + \frac{1 - \epsilon_{3,1}}{\epsilon_{3,1}} + \frac{1 - \epsilon_{3,2}}{\epsilon_{3,2}}} \quad (13.28)$$

Note that the resistances associated with the radiation shield become very large when the emissivities  $\epsilon_{3,1}$  and  $\epsilon_{3,2}$  are very small.

Equation 13.28 may be used to determine the net heat transfer rate if  $T_1$  and  $T_2$  are known. From knowledge of  $q_{12}$  and the fact that  $q_{12} = q_{13} = q_{32}$ , the value of  $T_3$  may then be determined by expressing Equation 13.24 for  $q_{13}$  or  $q_{32}$ .



**FIGURE 9.8**  
Buoyancy-driven flows on horizontal cold ( $T_s < T_\infty$ ) and hot ( $T_s > T_\infty$ ) plates: (a) top surface of cold plate, (b) bottom surface of cold plate, (c) top surface of hot plate, and (d) bottom surface of hot plate.

surface facing downward (Figure 9.8d), the tendency of the fluid to descend and ascend, respectively, is impeded by the plate. The flow must move horizontally before it can descend or ascend from the edges of the plate, and convection heat transfer is somewhat ineffective. In contrast, for a cold surface facing downward (Figure 9.8b) and a hot surface facing upward (Figure 9.8c), flow is driven by descending and ascending parcels of fluid, respectively. Conservation of mass dictates that cold (warm) fluid descending (ascending) from a surface be replaced by ascending (descending) warmer (cooler) fluid from the ambient, and heat transfer is much more effective.

Although correlations suggested by McAdams [5] are widely used for horizontal plates, improved accuracy may be obtained by altering the form of the characteristic length on which the correlations are based [18, 19]. In particular with the characteristic length defined as

$$L \equiv \frac{A_s}{P} \quad (9.29)$$

where  $A_s$  and  $P$  are the plate surface area and perimeter, respectively, recommended correlations for the average Nusselt number are

**Upper Surface of Heated Plate or Lower Surface of Cooled Plate:**

$$\overline{Nu}_L = 0.54 Ra_L^{1/4} \quad (10^5 \leq Ra_L \leq 10^7) \quad (9.30)$$

$$\overline{Nu}_L = 0.15 Ra_L^{1/3} \quad (10^7 \leq Ra_L \leq 10^{11}) \quad (9.31)$$

**Lower Surface of Heated Plate or Upper Surface of Cooled Plate:**

$$\overline{Nu}_L = 0.27 Ra_L^{1/4} \quad (10^5 \leq Ra_L \leq 10^{10}) \quad (9.32)$$

is based on the characteristic length  $L$  of the geometry. Typically,  $n = \frac{1}{4}$  and  $\frac{1}{3}$  for laminar and turbulent flows, respectively. For turbulent flow it then follows that  $\bar{h}_L$  is independent of  $L$ . Note that all properties are evaluated at the film temperature,  $T_f \equiv (T_s + T_\infty)/2$ .

### 9.6.1 The Vertical Plate

Expressions of the form given by Equation 9.24 have been developed for the vertical plate [5–7] and are plotted in Figure 9.6. The coefficient  $C$  and the exponent  $n$  depend on the Rayleigh number range, and for Rayleigh numbers less than  $10^4$ , the Nusselt number should be obtained directly from the figure.

A correlation that may be applied over the *entire* range of  $Ra_L$  has been recommended by Churchill and Chu [8] and is of the-form

$$\bar{Nu}_L = \left\{ 0.825 + \frac{0.387 Ra_L^{1/6}}{[1 + (0.492/Pr)^{9/16}]^{8/27}} \right\}^2 \quad (9.26)$$

Although Equation 9.26 is suitable for most engineering calculations, slightly better accuracy may be obtained for laminar flow by using [8]

$$\bar{Nu}_L = 0.68 + \frac{0.670 Ra_L^{1/4}}{[1 + (0.492/Pr)^{9/16}]^{4/9}} \quad Ra_L \leq 10^9 \quad (9.27)$$

It is important to recognize that the foregoing results have been obtained for an isothermal plate (constant  $T_s$ ). If the surface condition is, instead, one of uniform heat flux (constant  $q_s''$ ), the temperature difference ( $T_s - T_\infty$ ) will vary with  $x$ , increasing from a value of zero at the leading edge. An approximate procedure for determining this variation may be based on results [8, 9] showing




FIGURE 9.6  
Nusselt number for free convection heat transfer from a vertical plate [5–7].

**Analysis:** For the quiescent air, Equation 9.12 gives

$$Gr_L = \frac{g\beta(T_s - T_\infty)L^3}{\nu^2}$$

$$= \frac{9.8 \text{ m/s}^2 \times (3.12 \times 10^{-3} \text{ K}^{-1})(70 - 25)^\circ\text{C}(0.25 \text{ m})^3}{(17.95 \times 10^{-6} \text{ m}^2/\text{s})^2} = 6.69 \times 10^7$$

Hence  $Ra_L = Gr_L Pr = 4.68 \times 10^7$  and, from Equation 9.23, the free convection boundary layer is laminar. The analysis of Section 9.4 is therefore applicable. From the results of Figure 9.4, it follows that, for  $Pr = 0.7$ ,  $\eta \approx 6.0$  at the edge of the boundary layer, that is, at  $y = \delta$ . Hence

$$\delta_L \approx \frac{6L}{(Gr_L/4)^{1/4}} = \frac{6(0.25 \text{ m})}{(1.67 \times 10^7)^{1/4}} = 0.024 \text{ m}$$

For airflow at  $u_\infty = 5 \text{ m/s}$

$$Re_L = \frac{u_\infty L}{\nu} = \frac{(5 \text{ m/s}) \times 0.25 \text{ m}}{17.95 \times 10^{-6} \text{ m}^2/\text{s}} = 6.97 \times 10^4$$

and the boundary layer is laminar. Hence from Equation 7.19

$$\delta_L \approx \frac{5L}{Re_L^{1/2}} = \frac{5(0.25 \text{ m})}{(6.97 \times 10^4)^{1/2}} = 0.0047 \text{ m}$$

**Comments:**

1. Boundary layer thicknesses are typically larger for free convection than for forced convection.
2.  $(Gr_L/Re_L^2) = 0.014 \ll 1$ , and the assumption of negligible buoyancy effects for  $u_\infty = 5 \text{ m/s}$  is justified.

## 9.6

### Empirical Correlations: External Free Convection Flows

In this section we summarize empirical correlations that have been developed for common *immersed* (external flow) geometries. The correlations are suitable for most engineering calculations and are generally of the form

$$\overline{Nu}_L = \frac{hL}{k} = C Ra_L^n \quad (9.24)$$

where the Rayleigh number,

$$Ra_L = Gr_L Pr = \frac{g\beta(T_s - T_\infty)L^3}{\nu\alpha} \quad (9.25)$$




FIGURE 3.6 Hollow cylinder with convective surface conditions.

from Equation 3.24 that the conduction *heat transfer rate*  $q_r$  (not the heat flux  $q_r''$ ) is a constant in the radial direction.

We may determine the temperature distribution in the cylinder by solving Equation 3.23 and applying appropriate boundary conditions. Assuming the value of  $k$  to be constant, Equation 3.23 may be integrated twice to obtain the general solution

$$T(r) = C_1 \ln r + C_2 \tag{3.25}$$

To obtain the constants of integration  $C_1$  and  $C_2$ , we introduce the following boundary conditions:

$$T(r_1) = T_{s,1} \quad \text{and} \quad T(r_2) = T_{s,2}$$

Applying these conditions to the general solution, we then obtain

$$T_{s,1} = C_1 \ln r_1 + C_2 \quad \text{and} \quad T_{s,2} = C_1 \ln r_2 + C_2$$

Solving for  $C_1$  and  $C_2$  and substituting into the general solution, we then obtain

$$T(r) = \frac{T_{s,1} - T_{s,2}}{\ln(r_1/r_2)} \ln\left(\frac{r}{r_2}\right) + T_{s,2} \tag{3.26}$$

Note that the temperature distribution associated with radial conduction through a cylindrical wall is logarithmic, not linear, as it is for the plane wall under the same conditions. The logarithmic distribution is sketched in the insert of Figure 3.6.

If the temperature distribution, Equation 3.26, is now used with Fourier's law, Equation 3.24, we obtain the following expression for the heat transfer rate:

$$q_r = \frac{2\pi Lk(T_{s,1} - T_{s,2})}{\ln(r_2/r_1)} \tag{3.27}$$

From this result it is evident that, for radial conduction in a cylindrical wall, the thermal resistance is of the form

For liquids of moderate Prandtl number, such as water, Eq. (4.98) can also be used for  $Ra < 10^5$ . For higher Rayleigh numbers, the Globe and Dropkin correlation [34] may be used for horizontal layers:

$$\overline{Nu}_L = 0.069Ra_L^{1/3}Pr^{0.074}; \quad 3 \times 10^5 < Ra_L < 7 \times 10^9 \quad (4.102)$$

Also, for horizontal layers of air, that is,  $\theta = 0^\circ$ , the range of validity of Eq. (4.98) extends to  $Ra_L = 10^8$ .

Data are available in the literature for inclined layers of small aspect ratio but have not been correlated in a satisfactory manner.

In vertical cavities of small aspect ratio, with the horizontal surfaces insulated, as shown in Fig. 4.38, the following correlations due to Berkovsky and Polevikov [35] may be used for fluids of any Prandtl number.

1.  $2 < H/L < 10$ :

$$\overline{Nu}_L = 0.22 \left( \frac{Pr}{0.2 + Pr} Ra_L \right)^{0.28} \left( \frac{H}{L} \right)^{-1/4}; \quad Ra_L < 10^{10} \quad (4.103a)$$

2.  $1 < H/L < 2$ :

$$\overline{Nu}_L = 0.18 \left( \frac{Pr}{0.2 + Pr} Ra_L \right)^{0.29}; \quad 10^3 < \frac{Pr}{0.2 + Pr} Ra_L \quad (4.103b)$$

The flow and convective heat transfer in small-aspect-ratio cavities can depend on the temperature variation along the separating walls and, hence, on conduction in the walls and on radiation exchange within the cavity.




Figure 4.38 Schematic of a small-aspect-ratio vertical enclosure.

### Concentric Cylinders and Spheres

Figure 4.39 shows isotherms for natural convection between concentric cylinders, with the inner cylinder heated and the outer cylinder cooled. The correlations recommended by Raithby and Hollands [36] for natural convection between concentric

... the layer is by

limit of  $\overline{Nu}_L = 1$ ,  
 ted that a horizontal  
 of  $(T_H - T_C)$ . In  
 cellular convection

h number increases,  
 until finally the flow  
 d contained between  
 occurs for any  $Ra_L >$   
 $Ra_L < 10^3$ . As the  
 l cells are formed. At  
 oundary layer flowing  
 hile the fluid in the  
 al rows of horizontal  
 core finally becomes

h number are charac-  
 es. Thus, it would be  
 d over wide Rayleigh  
 ; are usually valid for  
 omplex. Thus, only a

gineering importance.  
 ds and coworkers for

$$+ \left[ \left( \frac{Ra_L \cos \theta}{5830} \right)^{1/3} - 1 \right] \quad (4.98)$$

, it must be set equal




Figure 4.37 Schematic of a large-aspect-ratio inclined enclosure. The angle  $\theta$  is measured from the horizontal.

2.  $\theta = 60^\circ$  [33]:

$$\overline{Nu}_{L60^\circ} = \max \{ Nu_1, Nu_2 \} \quad (4.99)$$

where

$$Nu_1 = \left\{ 1 + \left[ \frac{0.0936 Ra_L^{0.314}}{1 + \{ 0.5 / [1 + (Ra_L / 3160)^{20.6}]^{0.1} \}} \right]^7 \right\}^{1/7}$$

$$Nu_2 = \left( 0.104 + \frac{0.175}{H/L} \right) Ra_L^{0.283}$$

and is valid for  $0 < Ra_L < 10^7$ .

3.  $60^\circ < \theta < 90^\circ$  [33]:

$$\overline{Nu}_L = \left( \frac{90 - \theta}{30} \right) \overline{Nu}_{L60^\circ} + \left( \frac{\theta - 60}{30} \right) \overline{Nu}_{L90^\circ} \quad (4.100)$$

4.  $\theta = 90^\circ$  [33]:

$$\overline{Nu}_{L90^\circ} = \max \{ Nu_1, Nu_2, Nu_3 \} \quad (4.101)$$

where

$$Nu_1 = 0.0605 Ra_L^{1/3}$$

$$Nu_2 = \left\{ 1 + \left[ \frac{0.104 Ra_L^{0.293}}{1 + (6310 / Ra_L)^{1.36}} \right]^3 \right\}^{1/3}$$

$$Nu_3 = 0.242 \left( \frac{Ra_L}{H/L} \right)^{0.272}$$

and is valid for  $10^3 < Ra_L < 10^7$ ; for  $Ra_L \leq 10^3$ ,  $\overline{Nu}_{L90^\circ} \approx 1$ .

required for the fluid to become unstable, then heat transfer across the layer is by conduction only, and from Eq. (1.9),

$$\dot{Q} = \frac{kA}{L}(T_H - T_C)$$

or

$$\bar{h}_c = \frac{k}{L}, \quad \overline{\text{Nu}}_L = 1$$

Thus, correlations for the Nusselt number always have a lower limit of  $\overline{\text{Nu}}_L = 1$ , corresponding to pure conduction. In Section 4.2.1, it was indicated that a horizontal layer heated from below becomes unstable at a critical value of  $(T_H - T_C)$ . In dimensionless form, the criterion for instability and the onset of cellular convection is a critical value of the Rayleigh number,

$$\text{Ra}_L = \frac{g\beta(T_H - T_C)L^3}{\nu\alpha} = 1708$$

As the temperature difference  $(T_H - T_C)$  and, hence, the Rayleigh number increases, there are transitions to increasingly more complex flow patterns until finally the flow in the core is turbulent. In the case of a vertical layer of fluid contained between parallel plates maintained at different temperatures, circulation occurs for any  $\text{Ra}_L > 0$ ; however, heat transfer is essentially by pure conduction for  $\text{Ra}_L < 10^3$ . As the Rayleigh number is increased, the circulating flow develops and cells are formed. At  $\text{Ra}_L \approx 10^4$  the flow changes to a boundary layer type with a boundary layer flowing upward on the hot wall and downward on the cold wall, while the fluid in the core region remains relatively stationary. At  $\text{Ra}_L \approx 10^5$ , vertical rows of horizontal vortices develop in the core; and at  $\text{Ra}_L \approx 10^6$ , the flow in the core finally becomes turbulent.

The marked changes in flow pattern with changes in Rayleigh number are characteristic of internal natural convection in all shapes of enclosures. Thus, it would be unreasonable to seek a single simple correlation formula valid over wide Rayleigh and Prandtl number ranges. Simple power law-type formulas are usually valid for small ranges of  $\text{Ra}$ ; more general formulas are usually quite complex. Thus, only a few configurations will be considered here.

Heat transfer across thin air layers is of considerable engineering importance. Referring to Fig. 4.37, correlations recommended by Hollands and coworkers for aspect ratios of  $H/L > 10$  are as follows.

1.  $0 \leq \theta < 60^\circ$  [32]:

$$\overline{\text{Nu}}_L = 1 + 1.44 \left[ 1 - \frac{1708}{\text{Ra}_L \cos \theta} \right] \left\{ 1 - \frac{1708(\sin 1.8\theta)^{1.6}}{\text{Ra}_L \cos \theta} \right\} + \left[ \left( \frac{\text{Ra}_L \cos \theta}{5830} \right)^{1/3} - 1 \right] \quad (4.98)$$

where if either of the terms in square brackets is negative, it must be set equal to zero. Equation (4.98) is valid for  $0 < \text{Ra}_L < 10^5$ .

For  $L = \pi D/2 = 0.47$  m,

$$\overline{Nu}_L = 0.52(Gr_L Pr)^{1/4} = (0.52) \left( \frac{(1/400)(200)(9.81)(0.47)^3(0.69)}{(25.5 \times 10^{-6})^2} \right)^{1/4} = 79.3$$

$$\overline{h}_c = \left( \frac{k}{L} \right) Nu_L = \left( \frac{0.0331}{0.47} \right) 79.3 = 5.58 \text{ W/m}^2 \text{ K}$$

**Comments**


1. The more approximate Eq. (4.91) gives a value of  $\overline{h}_c$  that is 18% higher than that from Eq. (4.87).
2. Use CONV to check  $\overline{h}_c$ .

**4.4.2 Internal Natural Flows**

Figure 4.36 shows a selection of enclosures in which natural convection is of engineering concern—for example, in flat-plate solar collectors, wall cavities, and window glazing. The horizontal layer heated from below was discussed in Section 4.2.1, where an appropriate definition of the convective heat transfer coefficient was shown to be

$$\overline{h}_c = \frac{\dot{Q}/A}{T_H - T_C}$$

The length parameter commonly used to define the Nusselt number is the plate spacing  $L$ . If the temperature difference ( $T_H - T_C$ ) is less than the critical value



**Figure 4.36** Enclosures. (a) A double wall with an air gap. (b) Double window glazing. (c) A flat-plate solar collector with a partition to suppress natural convection. (d) Sterilization of beer by condensing steam.

## Sizing

### Physical Properties

Gas or Vapor	M Molecular Weight	k Specific Heat Ratio	C Gas Constant
Acetone	58.08	1.12	329
Acetylene (Ethyne)	26.04	1.26	343
Air	28.97	1.40	356
Ammonia, Anhydrous	17.03	1.31	348
Argon	39.95	1.67	378
Benzene (Benzol or Benzole)	78.11	1.12	329
Boron Trifluoride	67.82	1.20	337
Butadiene-1,3 (Divinyl)	54.09	1.12	329
Butane-n (Normal Butane)	58.12	1.09	326
Butylene (1-Butene)	56.11	1.11	328
Carbon Dioxide	44.01	1.29	346
Carbon Disulfide (C. Bisulfide)	76.13	1.21	33
Carbon Monoxide	28.01	1.40	356
Carbon Tetrachloride	153.82	1.11	328
Chlorine	70.91	1.36	353
Chloromethane (Methyl Chloride)	50.49	1.28	345
Cyclohexane	84.16	1.09	326
Cyclopropane (Trimethylene)	42.08	1.11	328
Decane-n	142.29	1.04	320
Diethylene Glycol (DEG)	106.17	1.07	323
Dimethyl Ether (Methyl Ether)	46.07	1.11	328
Dowtherm A	165.00	1.05	321
Dowtherm E	147.00	1.00	315
Ethane	30.07	1.19	336
Ethyl Alcohol (Ethanol)	46.07	1.13	330
Ethylene (Ethene)	28.05	1.24	341
Ethylene Glycol	62.07	1.09	326
Ethylene Oxide	44.05	1.21	338
Fluorocarbons:			
12, Dichlorodifluoromethane	120.93	1.14	331
13, Chlorotrifluoromethane	104.47	1.17	334
13B1, Bromotrifluoromethane	148.93	1.14	331
22, Chlorodifluoromethane	86.48	1.18	335
115, Chloropentafluoroethane	154.48	1.08	324
Glycerine (Glycerin or Glycerol)	92.10	1.06	322
Helium	4.00	1.67	378
Heptane	100.21	1.05	321

### Sizing – Determining $K_v$ and $K_w$

#### English Units

$$R = \frac{V_L (2,800 G)}{\mu \sqrt{A}}$$

or

$$R = \frac{12,700 V_L}{U \sqrt{A}}$$

#### Metric Units

$$R = \frac{31,313 V_L G}{\mu \sqrt{A}}$$

#### Determining $K_v$

$V_L$  = Flow rate at the flowing temperature, in U.S. gpm [ $m^3/h$ ]

$G$  = Specific gravity of liquid at flowing temperature referred to water = 1.00 at 70°F [21°C]

$\mu$  = Absolute viscosity at the flowing temperature, in centipoises



$A$  = Effective discharge area, in square inches [ $cm^2$ ] (from manufacturer's standard orifice areas)

$U$  = Viscosity at the flowing temperature, in Saybolt Universal seconds

After the value of  $R$  is determined, the factor  $K_v$  is obtained from the graph. Factor  $K_v$  is applied to correct the 'preliminary required discharge area.' If the corrected area exceeds the 'chosen standard orifice area,' the calculations should be repeated using the next larger standard orifice size.

#### Determining $K_w$

See graph at right.



$$\text{Percentage Back Pressure} = \frac{\text{Back Pressure, psig [barg]}}{\text{Set Pressure, psig [barg]}} + 100$$

**Anderson, Greenwood & Co.**  
 Premium Performance Direct Spring Valves - Series 60 and 80

**Preliminary Selection Guide**

Valve Type	Applications			Seat Type	Body Material			Set Pressure		Relieving Temperature		Balanced for Back Pressure
	Gas/Vapor	Liquid	Gas/Liquid Thermal Relief		Brass	CS	SS	psig	[barg]	°F	[°C]	
81	X		X	Plastic	X	X	X	50 to 10,000	[3.45 to 689.5]	-423°F to 500°F	[-253°C to 260°C]	N
81P		X	X	Plastic	X	X	X	50 to 6,000	[3.45 to 413.7]	-40°F to 400°F	[-40°C to 205°C]	Y
83	X		X	O-ring	X	X	X	20 to 10,000	[1.40 to 689.5]	-40°F to 550°F	[-40°C to 288°C]	N
83F	X		X	O-ring			X	15 to 500	[1.03 to 34.5]	-40°F to 550°F	[-40°C to 288°C]	N
86				Plastic	X	X	X	50 to 720	[3.45 to 49.6]	-423°F to 515°F	[-253°C to 268°C]	N
61	X		X	Plastic	X			30 to 500	[2.07 to 34.5]	-320°F to 400°F	[-196°C to 205°C]	N
63B	X		X	O-ring	X			37 to 531	[2.55 to 36.6]	-40°F to 400°F	[-40°C to 205°C]	N

**Note**

1. Minimum and maximum set pressures may not be available in all orifice sizes (see pages 19 - 22).

**Sizing – How to Size a Valve**

Pressure relief valves are selected on the basis of their ability to meet an expected relieving condition and flowing a sufficient amount of fluid to prevent excessive pressure increase. This means that the size of the valve orifices must be calculated taking the required flow, lading fluid properties, and other factors into consideration.

To select the minimum required orifice area that will flow the required capacity of the system you wish to protect, please refer to the following information, which appears in this section:

1. Sizing formulas

2. Physical properties of the fluid to be relieved
3. Capacities of different orifice areas at different pressures
4. Conversion tables to aid calculations

Once you have determined the required orifice area for your service conditions, refer to Ordering, pages 54 through 83, to select a specific valve model number.

**Orifice Areas and Nozzle Coefficient**

The orifice areas and nozzle coefficients for all Series 80 valves are tabulated in the table below.

These values are derived from the values certified by the National Board of Boiler and Pressure Vessel Inspectors, in accordance with Section VIII, Division 1 of the ASME Pressure Vessel Code.

**Verification of Sizing**

Orifice area calculations are made and/or verified whenever sufficient data is provided. If no data is furnished, the size selection responsibility will remain totally with the purchaser.

**Nozzle Coefficient and Available Orifice Sizes, in<sup>2</sup> [cm<sup>2</sup>]**

Valve Type	0.049 [0.316] (-4)	0.077 [0.497] (-5)	0.110 [0.710] (-6)	0.150 [0.968] (-7)	0.196 [1.265] (-8 or E)	0.307 [1.981] (F)	0.503 [3.245] (G)	0.785 [5.065] (H)	1.287 [8.303] (J)
81	0.816	X	X		X	X	X	X	X
81P	0.720	X			X		X		X
83	0.816	X	X		X	X	X	X	X
83F	0.998				X		X		X
86	0.816	X			X		X		
61	0.877		X						
63B	0.847	X		X					

## Sizing – English Sizing Formulas

Vapors or Gases (capacity in SCFM)<sup>1</sup>

$$A = \frac{V \sqrt{MTZ}}{6.32 CKP_1}$$

Vapors or Gases (capacity in lbs/h)<sup>1</sup>

$$A = \frac{W \sqrt{TZ}}{CKP_1 \sqrt{M}}$$

Steam (capacity in lb/h)<sup>1</sup>

$$A = \frac{W}{51.5 K P_1 K_s}$$

Liquids (capacity in gpm)

$$A = \frac{V_L \sqrt{G}}{38 K K_p K_w K_v \sqrt{P_A - P_B}}$$

### English Sizing Formulas

Orifice area calculations are made and/or verified whenever sufficient data is provided. If no data is furnished, the size selection responsibility will remain totally with the purchaser.

V = Required capacity, SCFM

W = Required capacity, lb/h

V<sub>L</sub> = Required capacity, gpm

G = Specific gravity of liquid at flowing temperature referred to water = 1.00 at 70°F (see Physical Properties on pages 12 - 14)

M = Molecular weight of vapor or gas (M = 29 x G, see Physical Properties on pages 10 - 11)

T = Relief temperature, °R (°R = °F + 460)

Z = Compressibility factor (if unknown, assume Z = 1.0)

k = Specific heat ratio  $k = \frac{C_p}{C_v}$

C = Gas constant based on k (if unknown, assume C = 315; see Physical Properties on pages 10 - 11; also see page 8)

K = Nozzle coefficient for 90 percent of actual capacity, derived from National Board Certified Testing (see page 4)

P<sub>1</sub> = Inlet flowing pressure, psia = Set pressure - inlet pressure loss + allowable overpressure + 14.7

P<sub>A</sub> = Inlet flowing pressure, psig = Set pressure - inlet pressure loss + allowable overpressure

P<sub>B</sub> = Back pressure - psig

K<sub>p</sub> = Overpressure correction factor, 1.0


K<sub>w</sub> = Back pressure correction factor (see page 7)

K<sub>v</sub> = Viscosity correction factor (see page 7)


K<sub>s</sub> = Superheat correction factor (for saturated steam, K<sub>s</sub> = 1.0, refer to Table on page 9)

### Note

1. As is accepted industry practice, back pressure for conventional (unbalanced) gas or steam valves should not exceed 10 percent.



# Model 9460 and 9470 Series ULTRA-LINE® Dual-Stage Ultra High-Purity Stainless Steel Regulator with Tied Diaphragms



### Description

Ultra high-purity stainless steel regulators for use with semiconductor applications.

### Applications

- All semiconductor industry applications requiring precise pressure control.

### Design Features/Components

- Available in two choices of materials: 316L stainless steel with 316 stainless steel internals (Model 9460 Series), or 316L stainless steel with Hastelloy C-22 internals (Model 9470 Series).
- Dual tied seat design ensures regulator closure under extreme conditions
- 2" inlet and delivery pressure gauges
- Autogeneous butt-welded connections
- The seats are the only non-metallic components in the process stream
- Standard 10-15 Ra surface finish
- Sealed and ventable bonnets
- Helium leak tested to  $1 \times 10^{-9}$  scc/sec
- Assembled, tested and packaged in a Class 100 clean area

### Materials of Construction

	Model 9460 Series	Model 9470 Series
Gauges:	316L stainless steel	316L stainless steel
Body:	316L stainless steel	316L stainless steel
Bonnets:	Nickel plated brass	Nickel plated brass
Diaphragms:	316 stainless steel	Hastelloy C-22
Seats:	Kel-F 81	Kel-F 81
Linkages:	316 stainless steel	Hastelloy C-22
Springs:	316 stainless steel	Hastelloy C-22
Seals:	Metal to metal	Metal to metal

### Specifications

Maximum Inlet Pressure:	3000 psig (20,700)
Maximum Flow Rate:	5 SCFM (150 SLPM)
(At 3000 psig Inlet, N <sub>2</sub> )	
Flow Capacity (Cv):	0.05
Operating Temperature:	-40°F to 160°F (-40°C to 71°C)
Porting:	1/4" VCR compatible
Shipping Weight:	5 lbs

### Ordering Information

All of the Model 9460 and 9470 Series are shipped double bagged under purified Argon. All gauges used are 100% Helium leak tested and have female 1/4" VCR compatible connections.

Model Number	Delivery Pressure Range	Delivery Pressure Gauge	Inlet Pressure Gauge
<b>316L Stainless Steel Regulators</b>			
9463-4-V4FM	0-30 psig	30" vac-0-60 psig	0-3000 psig
9463-4-V4MM	0-30 psig	30" vac-0-60 psig	0-3000 psig
9467-4-V4FM	0-100 psig	30" vac-0-200 psig	0-3000 psig
9467-4-V4MM	0-100 psig	30" vac-0-200 psig	0-3000 psig
<b>316L Stainless Steel Regulators with Hastelloy C-22 Internal Parts</b>			
9473-4-V4FM	0-30 psig	30" vac-0-60 psig	0-3000 psig
9473-4-V4MM	0-30 psig	30" vac-0-60 psig	0-3000 psig
9477-4-V4FM	0-100 psig	30" vac-0-200 psig	0-3000 psig
9477-4-V4MM	0-100 psig	30" vac-0-200 psig	0-3000 psig

Inlet/Outlet:  
F = Female M = Male

\$1250  
5 days



Mo  
Dua

Descrip  
Economi  
corrosive

Applica  
Pressu  
hydrog  
bromic

Design I  
Direct  
control  
Nickel  
halogen

Orderi

Model I  
B15-CG  
B15A-C  
B15B-C  
B15C-C  
B15F-67  
B16-CG  
B16A-C  
B16B-C  
H15-CG  
H15A-C  
H15B-C  
H15C-C

Note: Sor

ACC 15

N

G-4

# NUCLEATE BOILING OF NITROGEN, ARGON, AND CARBON MONOXIDE FROM ATMOSPHERIC TO NEAR THE CRITICAL PRESSURE

C. Jöhler\* and E. L. Park, Jr.

University of Missouri at Rolla, Rolla, Missouri

## INTRODUCTION

The nucleate-boiling region is of great importance to the engineer because in this region large quantities of heat can be removed with relatively low temperature differences. This study was initiated to study the boiling behavior of carbon monoxide and to compare carbon monoxide's nucleate-boiling behavior to the boiling behavior of other cryogenic fluids (nitrogen and argon).

## PREVIOUS WORK

Previous work will be reviewed only briefly since a more complete coverage is given elsewhere [1].

The nucleate-boiling region is characterized by bubbles originating from active sites called nuclei. Many authors [2-12] have presented work which indicate that nucleation sites are small imperfections in the heat transfer surface and that the nucleate-boiling heat transfer is a strong function of the surface conditions. Although several investigators [2,6,13] have studied bubble dynamics and frequency of release of bubbles, the correlation of these variables has not resulted in a general equation which will predict nucleate-boiling behavior.

The maximum heat-flux point of the nucleate-boiling curve has proven to be an area of great interest. Many attempts have been made to develop a correlating equation for predicting the maximum heat flux, but such equations have been used with only limited success.

By defining a universal bubble-departure velocity near the critical heat flux, Rohsenow and Griffith [14] developed the following equation:

$$\frac{(Q/A)_{\max}}{\rho_r L} = 143 \left( \frac{\rho_L - \rho_v}{\rho_r} \right)^{0.6} \quad (1)$$

Kutateladze [15] derived a similar equation independently by the use of dimensional analysis.

\*Present address: Shell Oil Company, Wood River, Illinois.

Equation (2) w:  
two-phase flow inv  
(

On the other ha  
organic liquids, deve

Applying thermodyn  
and Schrock [18] of  
parachor.

To eliminate th  
equation with a red

$$\left( \frac{(Q/A)_{\max}}{(Q/A)_{\max}} \right)_{P_r}$$

## EQUIP

The experimen  
heating element, an  
equipment has been

The procedure  
Before filling the au  
internal condenser t  
available in the gase  
the gas flow through  
nitrogen through the  
liquid level was reac  
nitrogen, liquid nitro  
vented to the atmosp

When the liquid  
atmosphere and the  
through the internal  
supplied to the heating  
power was increased  
observed. The power w  
temperature. This proce  
time the heater was e

With the liquid p  
supplied to the heatir  
after steady state wa  
condenser. The powe  
recorded. Intermitt  
temperature was che  
procedure was contin  
had been completed,  
value. The previous  
nucleate-boiling curv

Equation (2) was developed by Zuber [16] based on Helmholtz's instability for two-phase flow involving liquid and vapor.

$$\frac{(Q/A)_{\max}}{\rho_r L} = \frac{\pi}{24} \left( \sigma g \frac{\rho_L - \rho_v}{\rho_v^2} g_c \right)^{1/4} \left( \frac{\rho_L}{\rho_L + \rho_v} \right)^{1/2} \quad (2)$$

On the other hand, Cichelli and Bonilla [17], using experimental data from many organic liquids, developed an empirical equation of the form

$$\frac{(Q/A)_{\max}}{P_r} = \alpha f(P_r) \quad (3)$$

Applying thermodynamic similarity and the Clausius-Clapeyron equation, Lienhard and Schrock [18] obtained an equation similar to (3), involving the definition of a parachor.

To eliminate the effect of surface variables, Cobb and Park [19] developed an equation with a reduced pressure of 0.1.

$$\begin{aligned} \frac{(Q/A)_{\max}}{(Q/A)_{\max} P_r = 0.1} &= 1.70 - 3.90 T_r - 0.048 T_r^2 + 2.41 T_r^3 + 7.58 T_r^4 \\ &+ 5.20 T_r^5 - 12.88 T_r^6 \end{aligned} \quad (4)$$

### EQUIPMENT AND EXPERIMENTAL PROCEDURE

The experimental equipment includes a pressure and condensing system, a heating element, an electrical system, and a temperature measuring system. Since the equipment has been described in detail previously [1,19] it will not be repeated.

The procedure followed during the data acquisition is briefly described below. Before filling the autoclave, liquid nitrogen was allowed to circulate through the internal condenser to aid in cooling the vessel. Carbon monoxide and argon were available in the gaseous state and were condensed inside the autoclave by regulating the gas flow through the fill line and into the vessel. Continued circulation of liquid nitrogen through the internal condenser caused the gas to condense, until the required liquid level was reached within the autoclave. However, to fill the autoclave with nitrogen, liquid nitrogen was charged through the fill line and into the vessel and was vented to the atmosphere.

When the liquid level was approximately 7 in., the vessel was closed to the atmosphere and the system pressure controlled by monitoring the nitrogen flow through the internal condenser. When the desired pressure was reached, power was supplied to the heating element. To achieve proper aging of the heat transfer surface, power was increased until a transition from nucleate boiling to film boiling was observed. The power was then turned off, and the heater allowed to cool to saturation temperature. This procedure of entering the film-boiling region was repeated each time the heater was exposed to the atmosphere.

With the liquid pool at the desired saturation temperature, power was once again supplied to the heating element. Temperature, amperage, and voltage were recorded after steady state was achieved by adjusting the nitrogen flow rate in the internal condenser. The power level was then raised and the next nucleate-boiling point was recorded. Intermittently between points, the thermocouple recording the pool temperature was checked to observe any change in the saturation temperature. This procedure was continued until the burnout point was attained. Once a pressure run had been completed, the power was turned off and the pressure was adjusted to a new value. The previous steps were repeated at each pressure, until all of the desired nucleate-boiling curves for the specific liquid were recorded.

Table I. Heat Transfer Surfaces


Surface No.	Heater No.	Characteristics of the surface
1	1	electroplated with gold—unaltered
2	2	electroplated with gold—unaltered
3	2	surface No. 2 —boiled in tap water for 24 hr
4	2	surface No. 3 —polished with a soft cloth wheel

To check for reproducible results, the boiling curve at a reduced pressure of 0.1 was always the first and last boiling curve to be studied for a given liquid. The reduced pressure of 0.1 was chosen because of the desire to carefully examine the correlation developed previously by Cobb and Park [19].

The critical heat flux was defined by a rapid increase in temperature difference  $\Delta T$ . This rapidly rising  $\Delta T$  was observed, for most runs, to occur as soon as the power was increased from the previous setting. Only in a few instances was the  $\Delta T$  found to rise suddenly after the power setting had remained constant for several minutes. In the latter case, the last power setting was recorded as the critical heat flux; for the former case, the critical heat flux was recorded as an average of the last two power settings. The above procedure resulted in the following errors. The combined product errors of current and voltage for measuring heat fluxes are  $\pm 0.125\%$ , which is approximately equal to  $\pm 50$  Btu/hr-ft<sup>2</sup> for the large heat fluxes obtained in this investigation. Temperature could be read to  $\pm 0.001$  mV, equivalent to a temperature accuracy of  $\pm 0.1^\circ\text{F}$ . Temperature differences deviated, on the average, by less than  $1^\circ\text{F}$  for corresponding heat fluxes.

RESULTS

During the course of taking experimental boiling heat transfer data, four different heat transfer surfaces were used. Table I is a summary of the various gold heat transfer surfaces employed. Two heaters were necessary because of the failure of the heating



$$Pr = \frac{P}{P_c}$$

$$P_c = 33.5 \text{ atm}$$

$$= 492.3 \text{ psi}$$

Fig. 1. Nucleate-boiling curves for liquid nitrogen on heat transfer surface No. 1.

Max at 34.2 psig =  $1.8 \times 10^4$  Btu  
 hr-ft<sup>2</sup>

Pr	P (psia)	P psig
.1	49.2	34.2
.3	147.7	
.5	246.1	
.8	393.8	
.86	423.4	

$$\frac{1 \text{ BTU}}{\text{hr ft}^2} \times \frac{1055.06 \text{ J}}{1 \text{ BTU}} \times \frac{1 \text{ hr}}{3600 \text{ sec}} \times \frac{10.76 \text{ ft}^2}{1 \text{ m}^2} = 3.15 \frac{\text{W}}{\text{m}^2} = \frac{1 \text{ m}^2}{1550.003 \text{ in}^2}$$

$$= .00203 \frac{\text{W}}{\text{in}^2}$$

Fig. 2. Nucleate-boiling liquid nitrogen on heat transfer surface No. 2.

element within heat reduced after this fail

Figures 1 through reduced pressures nitrogen and liquid boiling curves became their greatest value nucleate-boiling characterized by abbreviation No. 2 yielded S-shaped and liquid carbon n

Critical Heat Flux and

All critical flux and Park [19] maximum reference value, the critical heat flux through

Fig. 3. Nucleate-boiling liquid argon on heat transfer surface No. 2.




Fig. 2. Nucleate-boiling curves for liquid nitrogen on heat transfer surface No. 2.

duced pressure of 0.1  
liquid. The reduced  
mine the correlation  
temperature difference  $\Delta T$ .  
on as the power was  
the  $\Delta T$  found to rise  
eral minutes. In the  
flux; for the former  
two power settings.  
ed product errors of  
hich is approximately  
n this investigation.  
perature accuracy of  
y less than 1°F for

element within heater No. 1. An entirely new heater and heating surface were introduced after this failure; however, both heaters were of the same design.

Figures 1 through 4 present a number of the nucleate-boiling curves at several reduced pressures for individual boiling surfaces. The boiling curves for liquid nitrogen and liquid argon followed the same general pattern. The slopes of the boiling curves became larger with increasing pressure, and the critical heat fluxes had their greatest values at reduced pressures ranging from 0.3 to 0.5. In contrast, the nucleate-boiling curves obtained with liquid carbon monoxide (Fig. 4) were characterized by abbreviated nucleate-boiling regions and low critical heat fluxes. Surface No. 2 yielded S-shaped boiling curves when boiling with liquid nitrogen, liquid argon, and liquid carbon monoxide.

DISCUSSION

Critical Heat Flux and Maximum Temperature Difference Correlations

All critical flux data for nitrogen and argon were correlated by using the Cobb and Park [19] maximum heat flux correlation. By using the reduced pressure of 0.1 as a reference value, the correlation eliminates the effect of heat transfer surface on the critical heat flux throughout a series of pressure runs. It must be emphasized that the

$$P_c = \frac{P}{P_c} \quad P_{c,ref} = 70.54 \text{ psia}$$

$$P_r = 0.1, \quad P = 70.54 \text{ psia}$$

$$40.8 \text{ W/in}^2$$

$$20.4 \text{ W/in}^2$$




Fig. 3. Nucleate-boiling curves for liquid argon on heat transfer surface No. 2.

nucleate-boiling curves for  
rogen on heat transfer  
o. 1.

FERMILAB DATA:

K	$\Delta T$	Q/A	
	°F	W/cm <sup>2</sup>	Btu/hr-ft <sup>2</sup>
1	1.8	0.3	951.8
7	12.6	1.3	4,124.4
10	18	1.7	5,393.4

$$h_i = 330 \text{ Btu/hr-ft}^2 \cdot \text{OR}, \quad 0.75 \frac{\text{W}}{\text{cm}^2}$$




Fig. 4. Nucleate-boiling curves for liquid carbon monoxide on heat transfer surface No. 2.

heat-transfer surface should remain constant during a series of pressure runs for the correlation to be utilized.

An average error of 6.18% with a standard deviation of 18.2% was obtained when sixteen liquid nitrogen and liquid argon critical heat fluxes were compared to the Cobb and Park equation in Fig. 5.

The series of nitrogen runs with heating surface No. 1 deviates noticeably from the Cobb and Park equation at reduced pressure of 0.3 and 0.5. This deviation may be due to a change in the heat transfer surface during boiling.

Figure 6 compares the correlations of Zuber [16], Kutateladze [15], Rohsenow and Griffith [14], Lienhard and Schrock [18], and Cichelli and Bonilla [17] with the maximum heat flux data of this investigation. It is seen that only the equations of Zuber and Kutateladze predict values of the right order of magnitude. These two latter correlations were also compared with the argon data of this investigation.




Fig. 5. Cobb and Park maximum heat flux correlation.

Fig. 6. Maximum heat flux for liquid nitrogen.

However, it was four times higher than the argon data.

#### Heat Transfer Surface

Four different nucleate-boiling runs were conducted under the condition of the heat transfer surface. The nucleate-boiling curve with surfaces 1 and 2 has a slope twice the slope of the boiling curve from surface 3 is also twice the slope of the boiling curve from surface 4 is highly porous. The curves initially have a slope of 1. The critical heat flux is approximately 1.5 times the critical heat flux of surface 3.

Fig. 7. Nucleate-boiling curves for liquid nitrogen on different heat transfer surfaces at 0.1  $P_r$ .




Fig. 6. Maximum heat flux correlations for liquid nitrogen.

However, it was found that all the above equations deviated several hundred percent from the argon data.

#### Heat Transfer Surface Effects on Nucleate Boiling

Four different heat transfer surfaces were utilized during the experimental nucleate-boiling runs, as indicated in Table I. Figure 7 illustrates the effect of the condition of the heat transfer surface on the shape and slope of liquid nitrogen nucleate-boiling curves. Relatively smooth nucleate-boiling curves are associated with surfaces 1 and 4, but the slope of the surface 1 boiling curve is approximately twice the slope of the boiling curve exhibited by surface 4. The boiling curve obtained from surface 3 is also of greater slope than the surface 4 curve; as stated in Table I, surface 4 is highly polished and smoother than surface 3. Surface 2 and 3 boiling curves initially have similar slopes, but their shapes and slopes differ greatly as the critical heat flux is approached.




Fig. 7. Nucleate-boiling curves for liquid nitrogen on different heat transfer surfaces at  $0.1 P_c$ .

nucleate-boiling curves for carbon monoxide on heat transfer surface No. 2.

pressure runs for the

18.2% was obtained. These results were compared to

data obtained from other investigators. This deviation may

be due to differences in surface conditions. The deviation may be due to differences in surface conditions. The deviation may be due to differences in surface conditions.

sum heat flux correlation.

The S-shaped curve associated with surface 2 is particularly unusual. S-shaped curves have been reported by several authors: Tang and Rotem [20], Rallis and Jawurck [21], Van Stralen [22], and Zuber [23]; however, the observation of such curves is relatively infrequent. Orell [24] gives further insight into the S-shaped curve by relating its appearance to a sudden increase in the nucleation site density.

Many authors—Stermen and Vilemas [26], Kosky [25], and Cobb and Park [19]—have indicated the importance of the state of the heat transfer surface on the critical heat flux. Different pressure runs were reproduced to be sure that the heating surface had not changed during boiling. Eight boiling curves were duplicated at various pressures on unaltered heat transfer surfaces. Reproduction of the critical heat flux never deviated by more than 7%, and the average deviation for the eight critical fluxes reproduced was 3%. An inherent error of 3% was calculated for this heater arrangement.

In contrast, the five nitrogen reduced-pressure runs duplicated on surfaces 1 and 2 produced an average deviation of 17.5% among corresponding maximum heat fluxes. Similarly, a deviation of 24.0% was found between atmospheric critical heat fluxes on surfaces 1 and 3 while the maximum heat flux was decreased by 16.4% by polishing surface number 3.

Of the eight boiling curves duplicated on unaltered surfaces, five were not exposed to the atmosphere between checks for reproducibility and three were exposed. This exposure did not affect duplication of the maximum heat flux but did affect the reproducibility of the maximum temperature difference. The reproducibility of the maximum  $\Delta T$  on the five unexposed surfaces never deviated by more than 7.2%, with an average deviation of 4.6%. The maximum  $\Delta T$  on the three exposed surfaces varied with an average deviation of 19.9%.

### Nucleate Boiling of Carbon Monoxide

Nucleate boiling of liquid carbon monoxide gave unusual results when compared to the experimental data of nitrogen and argon. Three boiling curves were duplicated at a reduced pressure of 0.1 and the average critical heat flux deviation was 11.3% for the same boiling surfaces. This high deviation might be accounted for by change in the heat transfer surface caused by carbon monoxide or by the unique behavior of the carbon monoxide critical heat flux as discussed below.

The critical heat fluxes of liquid argon and liquid nitrogen were defined by a sudden rise in surface temperature signaling the beginning of film boiling. In contrast, the pressure runs of liquid carbon monoxide, above the reduced pressure of 0.1, entered partial film boiling at relatively low heat fluxes. This partial film boiling was characterized by a slow increase in temperature difference with time at a constant heat flux. After several minutes had elapsed, the last  $\Delta T$  was recorded before a rapid increase in surface temperature marked the initiation of fully developed film boiling. The last  $\Delta T$  which was recorded in each run varied randomly in the range of 20 to 50°F with different pressure runs.

Lyon, Kosky, and Harman [27] experienced the same phenomena of partial film boiling for liquid oxygen at higher pressures using a platinum surface. This behavior was attributed to the attainment of film boiling for a small section of the test element. It is apparent that a variation of pressure causes a change in the normal mechanisms of nucleate boiling for liquid oxygen and liquid carbon monoxide; adsorption of the oxygen molecule on the boiling surface at higher pressures may be an explanation.

The carbon monoxide nucleate-boiling runs were all obtained while boiling from heat transfer surface No. 2. This is the same surface that exhibited the S-shaped

boiling curves for effects other than with liquid carbon source of the unique from different heat

The heat flux flux for carbon monoxide coupled increasing pressure

A family of nitrogen, liquid argon fluxes for these liquid 176 and 130% large fluxes of liquid carbon

1. In contrast liquid carbon at reduced pressure
2. When compared wide range fluxes of liquid magnitude,
3. Of the critical to be the maximum nitrogen and
4. Each boiling with respect
5. For a given various reduced different heat
6. Exposure of heat flux on by an average

The authors would like to thank the National Science Foundation

$A$  = area  
 $g$  = acceleration  
 $g_c$  = conversion factor  
 $L$  = latent heat of vaporization  
 $P$  = pressure  
 $Q$  = rate of heat transfer  
 $T$  = temperature  
 $\Delta T$  = temperature difference

#### Greek Symbols

$\sigma$  = surface tension  
 $\rho$  = density

y unusual. S-shaped  
em [20], Rallis and  
observation of such  
to the S-shaped curve  
site density.

Cobb and Park [19]—  
urface on the critical  
t the heating surface  
uplicated at various  
the critical heat flux  
or the eight critical  
lated for this heater

ed on surfaces 1 and 2  
maximum heat fluxes.  
ic critical heat fluxes  
y 16.4% by polishing

aces, five were not  
ility and three were  
num heat flux but did  
The reproducibility  
by more than 7.2%,  
ree exposed surfaces

ults when compared  
ves were duplicated  
ation was 11.3% for  
ed for by change in  
ique behavior of the

n were defined by a  
boiling. In contrast,  
ed pressure of 0.1,  
tial film boiling was  
ne at a constant heat  
rded before a rapid  
veloped film boiling.  
n the range of 20 to

omena of partial film  
rface. This behavior  
n of the test element.  
normal mechanisms  
e: adsorption of the  
v be an explanation.  
d while boiling from  
hibited the S-shaped

boiling curves for liquid nitrogen and liquid argon. It may be possible that surface effects other than oxygen adsorption caused the premature film boiling observed with liquid carbon monoxide, and that these same unknown surface effects are the source of the unique S-shaped boiling curves. Nucleate boiling of carbon monoxide from different heat transfer surfaces should provide a definite answer to this question.

The heat flux that initiated partial film boiling was defined as the critical heat flux for carbon monoxide. Figure 4 shows the low critical heat fluxes of carbon monoxide coupled with the gradual disappearance of the nucleate boiling region with increasing pressure.

A family of nucleate-boiling pressure runs was made on surface No. 2 for liquid nitrogen, liquid argon, and liquid carbon monoxide. Comparison of the critical heat fluxes for these liquids shows that the argon and nitrogen critical heat fluxes average 176 and 130% larger in magnitude, respectively, when compared to the critical heat fluxes of liquid carbon monoxide.

### CONCLUSIONS

1. In contrast to liquid nitrogen and liquid argon, the critical heat fluxes of liquid carbon monoxide are defined by the appearance of partial film boiling at reduced pressures ranging from 0.3 to near the critical pressure.
2. When compared to the critical heat fluxes of liquid carbon monoxide over a wide range of reduced pressures and for a given surface, the critical heat fluxes of liquid argon and liquid nitrogen average 176 and 130% larger in magnitude, respectively.
- 3. Of the critical heat flux correlations tested, the Cobb and Parke equation appears to be the most accurate for the correlation of the critical heat fluxes of liquid nitrogen and liquid argon.
- 4. Each boiling heat transfer surface has its own characteristic boiling curve with respect to both shape and slope.
- 5. For a given surface, the critical heat flux can be reproduced to within 3% at various reduced pressures; however, it may vary as much as 25% among different heat transfer surfaces.
- 6. Exposure of the heat-transfer surface to the atmosphere affects the critical heat flux only slightly, but does alter the maximum temperature difference by an average of 20%.

### ACKNOWLEDGMENTS

The authors would like to acknowledge The American Chemical Society Petroleum Research Fund and the National Science Foundation which provided financial assistance during this investigation.

### NOTATION

$A$  = area  
 $g$  = acceleration due to gravity  
 $g_c$  = conversion factor in Newton's law of motion  
 $L$  = latent heat of vaporization  
 $P$  = pressure  
 $Q$  = rate of heat transfer  
 $T$  = temperature  
 $\Delta T$  = temperature difference ( $T_{\text{surface}} - T_{\text{liquid}}$ )

#### Greek Symbols

$\sigma$  = surface tension  
 $\rho$  = density

## Subscripts

$L$  = refers to the liquid

$r$  = refers to reduced property

$v$  = refers to the vapor

max = refers to the point where the maximum heat flux occurs

## REFERENCES

1. C. Johler, M. S. Thesis, University of Missouri, Rolla, Mo. (1969).
2. M. Jakob, *Heat Transfer, Vol. 1*, John Wiley and Sons, New York (1949).
3. S. G. Bankoff, *AIChE J.*, **4**:24 (1958).
4. S. G. Bankoff, *Chem. Eng. Progr. Symp. Ser.*, **55**:87 (1959).
5. P. J. Griffith and J. D. Wallis, *Chem. Eng. Progr. Symp. Ser.*, **56**:49 (1960).
6. V. E. Denny, Ph.D. Dissertation, University of Minnesota, Minneapolis, Minn. (1961).
7. H. B. Clark, P. S. Streng, and J. W. Westwater, *Chem. Eng. Progr. Symp. Ser.*, **55**:103 (1959).
8. Y. Heled and A. Orell, *Int. J. Heat Mass Transfer*, **10**:553 (1967).
9. R. F. Gaertner and J. W. Westwater, *Chem. Eng. Progr. Symp. Ser.*, **56**:39 (1960).
10. C. Wei and G. W. Preckshot, *Chem. Eng. Science*, **19**:838 (1964).
11. C. Corty and A. S. Foust, *Chem. Eng. Progr. Symp. Ser.*, **51**:1 (1955).
12. H. M. Kurihara and J. E. Myers, *AIChE J.*, **6**:83 (1960).
13. K. K. Nangia and W. Y. Chon, *AIChE J.*, **13**:872 (1967).
14. W. M. Rohsenow and P. Griffith, *Chem. Eng. Progr. Symp. Ser.*, **52**:47 (1956).
15. S. S. Kutateladze, *Izv. Akad. Nauk SSSR OTD Tekh. Nauk*, **2**(4):342 (1951).
16. N. Zuber, *Trans. ASME*, **80**:711 (1958).
17. M. T. Cichelli and C. F. Bonilla, *Trans. AIChE*, **41**:755 (1945).
18. J. H. Lienhard and V. E. Schrock, *J. Heat Transfer*, **85**:261 (1963).
19. C. B. Cobb and E. L. Park, *Chem. Eng. Progr. Symp. Ser.*, **65**:188 (1969).
20. S. I. Tang and Z. Rotem, *Can. J. Chem. Eng.*, **43**:355 (1965).
21. C. J. Rallis and H. H. Jawurek, *Int. J. Heat Mass Transfer*, **7**:1051 (1964).
22. S. J. Van Stralen, *Br. Chem. Eng.*, **6**:834 (1961).
23. N. Zuber, *Appl. Mech. Rev.*, **17**:655 (1965).
24. A. Orell, *Int. J. Mass Heat Transfer*, **10**:967 (1967).
25. P. G. Kosky, Ph.D. Dissertation, University of California, Berkeley, Calif. (1965).
26. L. S. Sterman and Y. U. Vilemas, *Int. J. Heat Mass Transfer*, **11**:347 (1968).
27. D. N. Lyon, P. G. Kosky, and B. N. Harman, in: *Advances in Cryogenic Engineering, Vol. 9*, Plenum Press, New York (1963), p. 77.

## DISCUSSION

*Question* by R. F. Barron, Louisiana Polytechnic Institute: In determining the peak nucleate heat flux, did you make runs in which this point was approached from the film-boiling region (i.e., by decreasing the heater temperature)? If so, was the S-shaped curve obtained in the decreasing-temperature runs?

*Answer* by author: No, the peak nucleate heat flux was not approached from the film-boiling region. Because of the instability of the unstable film-boiling region it is impossible to approach the peak nucleate heat flux from the film side.

*Question* by K. J. Baumeister, NASA Lewis Research Center: Can the correlation for  $(Q/A)_{\max}$  be used for ordinary fluids like water, benzene, etc.?

*Answer* by author: The correlation was derived for fluids which follow the law of corresponding states (A, N<sub>2</sub>, O<sub>2</sub>, CO, Kr, Xe, etc.). Therefore, it should be restricted to these fluids. It is felt that if a third parameter, say  $Z_c$ , were introduced into the correlation it would be valid over a wide range of fluids.

*Question* by K. J. Baumeister, NASA Lewis Research Center: Why did you normalize equation (4) at  $P_r = 0.1$ ? Could another value of  $P_r$  be used?

*Answer* by author: A reduced pressure of 0.1 was picked because there was an abundance of reliable data at this point; therefore, the reference value could be determined accurately. Any value of reduced pressure could have been used as the reference value. Other values for the reference reduced pressure give similar correlations.

TR.  
LI  
S

The following is a periodic step in Joule liquid nitrogen at a influence of heat-generation departure from nucleate conditions are analyzed time for several power are compared with the

Previous studies on heat transfer, transient boiling have obtained experimental cryogenic fluids. NASA data available prior to Bewilogua *et al.* [3] are


A variety of transient primarily with water transient boiling as a and Miller [8] and Houchin and Lienhard effects associated with transient pool boiling.

The latest in a series presented by Mikic and relating to the nucleate correlation.



# QUANTUM 735TDR & NPR735

## Dimensional Drawing

All dimensions are reference and nominal.



## Flow Curves



These tests were performed using Nitrogen at ambient conditions.

## Ordering Information

73530 W 4P V3 10 FS M M M M PM

### BASIC SERIES

73530 = 0-30 psig  
735100 = 0-100 psig  
NPR73530 = -25 in Hg-0-30 psig

### MATERIALS

W = Welded 316L Stainless Steel  
H = Hastelloy C-22®\*

### PORTING

2P = 2 Ports  
3P = 3 Ports  
4P = 4 Ports  
5P = 5 Ports  
7P = 7 Ports

### REGULATOR OUTLET GAUGE

V3 = -30 in Hg-0-30 psig  
L = -30 in Hg-0-60 psig  
V1 = -30 in Hg-0-100 psig  
X = No Gauge

\* Includes body, diaphragm, compression member, poppet, and spring.  
\*\* Includes diaphragm compression member, poppet, and spring.

Hastelloy® C-22 is a registered trademark of Haynes International, Inc.  
Vespe® is a registered trademark of DuPont Company.  
Incone® is a registered trademark of Inco Alloys International

### OPTIONAL FEATURES

PM = Panel Mount  
TH = Hastelloy C-22® Trim\*\*  
VESP = Vespe® Seat  
(Recommended for Nitrous Oxide - N<sub>2</sub>O Serviced)  
3.4 = FS Fittings 3.4" Face to Face

### PORT CONFIGURATION

M = Male  
F = Female  
I = Internal Female Face Seal




### PORT STYLE


FS = 1/4" Face Seal  
TS = Tube Stubs

### REGULATOR INLET GAUGE

10 = 0-1000 psig  
20 = 0-2000 psig  
30 = 0-3000 psig  
40 = 0-4000 psig  
X = No Gauge

## Porting Configurations





# UNION CARBIDE MOLECULAR SIEVES

## FIXED-BED PRESSURE DROP CALCULATIONS



## WORKING EQUATION

The Ergun equation<sup>(a)</sup> for the calculation of pressure drop in adsorbent beds is in good agreement with numerous pressure drop measurements made in Union Carbide laboratories and on commercial adsorption units for both gas phase and liquid phase operation.

Use the following modified form of the equation to calculate pressure drop through Molecular Sieve beds:

$$\frac{\Delta P}{L} = \frac{f_t C_t G^2}{\rho D_p}$$

where:

$C_t$  = pressure drop coefficient (ft) (sq hr)/(sq in)

$D_p$  = effective particle diameter<sup>(b)</sup>, ft.

$f_t$  = friction factor

$G$  = superficial mass velocity, lb/(hr) (sq ft)

$L$  = distance from bed entrance, ft. (bed depth)

$\Delta P$  = pressure drop, psi

$\rho$  = fluid density, lb/cu ft.

$\Delta P/L$  is the pressure drop per unit length of bed in psi/ft.

The friction factor,  $f_t$  is determined from the accompanying graph (page 3) which has  $f_t$  plotted as a function of modified Reynold's number.

$$\text{Modified Re} = D_p G / \mu$$

$\mu$  = fluid viscosity, lb/(hr) (ft)

[multiply centipoise by 2.42 to obtain lb/(hr) (ft)]


The pressure drop coefficient,  $C_t$ , is determined from the graph (page 3) which has  $C_t$  plotted as a function of external void fraction,  $\epsilon$ .

The suggested values for  $\epsilon$  and  $D_p$  for various sizes of LINDE Molecular Sieve are:

	$\epsilon$	$D_p$
1/8-inch pellets	0.37	0.0122 ft.
1/16-inch pellets	0.37	0.0061 ft.
14x30 mesh granules	0.37	0.0033 ft.

(a) Ergun, S., Chem Engr Prog, 48, 78 (1952)

(b)  $D_p = \frac{D_c}{(2/3) + (1/3)(D_c/L_c)}$  where  $D_c$  is the particle diameter and  $L_c$  is the particle length



## EXAMPLE

Determine the pressure drop through an 8 ft. diameter by 10 ft. deep bed of LINDE Molecular Sieve 1/16-inch pellets drying 55 MMSCFD of gas at 50°F and 420 psig. The gas has a molecular weight of 25, a viscosity of 0.010 cp, and a density of 2.0 lb/cu.ft. at operating conditions.

$$G = \frac{55 \times 10^6 \text{ SCFD}}{24 \text{ hrs/day}} \frac{25 \text{ lbs/mol}}{379 \text{ SCF/mol}} \frac{1}{\pi (8)^2 / 4 \text{ sq. ft.}} = 3000 \text{ lb/(hr) (sq.ft.)}$$

$$\text{Modified Re} = D_p G / \mu = \frac{(0.0061) (3000)}{(2.42) (0.010)} = 756$$

$$f_t \text{ (from figure)} = 1.07$$

$$C_t \text{ (from figure for } \epsilon \text{ of 0.37)} = 3.6 \times 10^{-10}$$

$$\frac{\Delta P}{L} = \frac{(1.07) (3.6) (3000)^2 (10^{-10})}{(2.0) (0.0061)} = 0.28 \text{ psi/ft.}$$

For a bed depth of 10 ft.

$$\Delta P = (0.28) (10) = 2.8 \text{ psi}$$




FIGURE 191  
 PRESSURE DROP THROUGH PACKED COLUMNS  
 6 INCHES OR MORE IN DIAMETER  
 (COURTESY OF THE LINDE CO.)

fig 1





# VTS 450 Series / Two Stage Heavy Duty

**UL** Listed  
 Conforms to  
**CGA E-4**



**VTS 450**

## APPLICATION & USES

### VTS 450 Series

- Medium to high capacity gas service
- Precise and constant outlet pressure
- Two stage design
- Manifold models available. See page 19, Section A

**Dimensions:** 8" W x 8" H x 7-3/8" D  
 (20 cm x 20 cm x 19 cm)

**Weight:** ..... 7 lb. 6 oz. (3.67 kg)

## DESIGN/CONSTRUCTION

- Forged brass body and housing cap
- 2-1/2" gauges brass
- Stem type seat mechanism
- Diaphragm - 2", 3-1/4" (Stainless Steel)
- Delrin® cap bushing for smooth adjustments
- External self reseating relief valve  
 Not designed to protect downstream apparatus  
 (No relief valve is needed on VTS 460 and VTS 461 series regulators)
- Sintered inlet filter

## PERFORMANCE

Maximum Inlet .....3000 PSIG

Delivery Range .....See chart

## SPECIFICATIONS MATERIALS

Body .....Forged Brass

Diaphragm..... Stainless Steel

Housing Cap .....Forged Brass

Inlet Filter.....Bronze

**NOTE:** Regulators will deliver at least the stated upper range and in some cases may exceed the stated upper range.

## SAMPLE ORDERING INFORMATION

Model No.	Delivery Range	CGA Inlet Connection
<b>VTS 450</b>	<b>D</b>	<b>540</b>

Gas Service	Model No.	Delivery Range (PSIG)	Part No.
Air, Oxygen, Inert Gas	VTS 450 A-580 <sup>04</sup>	2-15	0781-3907
	VTS 450 B-540	2-40	0781-3904
	VTS 450 B-580 <sup>04</sup>	2-40	0781-3908
	VTS 450 D-540	5-125	0781-3905
	VTS 450 D-580 <sup>04</sup>	5-125	0781-3909
	VTS 450 D-590 <sup>05</sup>	5-125	0781-3916
	VTS 450 E-346	10-200	0781-4014
	VTS 450 E-540	10-200	0781-3906
Methane, Hydrogen	VTS 452 B-350	2-40	0781-3959
	VTS 452 D-350	5-125	0781-3963
	VTS 452 E-350	10-200	0781-3964
CO <sub>2</sub> & N <sub>2</sub> O	VTS 453 D-320 <sup>04</sup>	5-125	0781-3974
Acetylene	VTS 460 A-300	2-15	0781-3983
	VTS 460 A-510	2-15	0781-3984
L.P. Gas	VTS 461 B-510	2-40	0781-3993
	VTS 461 D-510	5-125	0781-3994

### Delivery Range Key

**A** 2-15 PSIG, **B** 2-40 PSIG, **D** 5-125 PSIG, **E** 10-200 PSIG

### Outlet Connections: Cylinder Type

9/16" - 18 (M)

<sup>04</sup> = 5/8" - 18 (F) RH


<sup>05</sup> = 5/8" - 18 (F) LH

Flow Chart: Section A, Page 41




# Regulator Flow Data (SCFH)

## SR 700/Single Stage - Extra Heavy Duty




Reference: SR 700 Series - Section A, Page 6

## VTS 700/Two Stage - Extra Heavy Duty




Reference: VTS 700 Series - Section A, Page 7

## SR 450/Single Stage - Heavy Duty




Reference: SR 450 Series - Section A, Page 8

## VTS 450/Two Stage - Heavy Duty




Reference: VTS 450 Series - Section A, Page 9

## VGS 450/Gaugeless Regulator - Heavy



Reference: VGS 450 Series - Section A, Page 10

## VGT 450/Gaugeless Two Stage Regulator Heavy Duty



Reference: VGT 450 Series - Section A, Page 10

#### 4.1b - Relief Valve Sizing for piping associated with the FLARE Materials Test Station and TPC Cryostats

##### PSV-101-N2

PSV-101-N2 is a trapped volume relief on the LN2 transfer line inside PAB. PSV-101-N2 has a 100 psig set point which is higher than the 75 psig set point of the liquid nitrogen supply dewar relief. Thus the section of piping PSV-101-N2 protects cannot be pressurized by any operational condition except heat input into a trapped volume. PSV-101-N2 is sized to relieve the potential trapped volume between MV-120-N, EV-106-N2, and EV-105-N2. This is approximately 25 ft. of ½ in. diameter stainless steel tube vacuum jacketed by 1.5 in. SCH 10 stainless steel pipe. To size the trapped volume relief, half of the pipe is assumed to be engulfed in fire. For the calculations it is assumed that the vacuum space is filled with air. The vacuum jacket pipe wall temperature is set to the fire temperature of 1200 °F and the inner tube wall temperature is set at 101.6 K which is the liquid nitrogen saturation temperature at 110% of the 100 psig relief valve set point. Both radiation exchange between the concentric tubes and conduction thru the air gap provide heat input to vaporize the LN2 as shown in Figure 1. It is assumed that the LN2 vents as a room temperature gas.




Figure 1: Heat transfer equations for trapped volume relief sizing

The total heat input into the liquid nitrogen is

$$q_{\text{total}} = \frac{5.67 \times 10^{-8} \frac{W}{m^2 \cdot K^4} (\pi \times 0.0127m \times 3.81m)(101.6^4 - 922^4)K^4}{\frac{1}{0.1} + \frac{1 - 0.7}{0.7} \left(\frac{0.0127m}{0.04272m}\right)} + \frac{2\pi \times 3.81m \times 0.04031 \frac{W}{m \cdot K} (101.6 - 922)K}{\ln\left(\frac{0.04272m}{\frac{2}{0.0127m}}\right)} = 1267W = 1267 \frac{J}{\text{sec}}$$

If the density of air is assumed to equal that of nitrogen, then the volumetric flow rate is

$$SCFM_{\text{air}} = 1267 \frac{J}{\text{sec}} \times \frac{1}{156966} \frac{kg}{J} \times \frac{2.205}{1} \frac{lb}{kg} \times \frac{60 \text{ sec}}{1 \text{ min}} \times \frac{1}{0.07491} \frac{ft^3}{lb} = 14.24 \frac{ft^3}{\text{min}}$$

The capacity of this Circle Seal 5100 series 2MP relief at 10% overpressure for its 100 psig set point is 25 SCFM which is adequate for this case.

**PSV-117-N2**

PSV-117-N2 is a relief attached to the outlet of MV-119-N. MV-119-N is a branch isolation valve for future expansion of the LN2 transfer line. PSV-117-N2 is in place to prevent the unlikely event that a small liquid leak thru MV-119-N could result in vapor generated at a rate that could not escape back thru the liquid leak path. The 25 SCFM capacity of this Circle Seal 5100 series 2MP relief set at 100 psig should be adequate for this unlikely scenario.

**PSV-118-N2**

PSV-118-N2 is a trapped volume relief on the LN2 transfer line. PSV-118-N2 has a 100 psig set point which is higher than the 75 psig set points of the liquid nitrogen dewar reliefs. Thus PSV-101-N2 must be sized to relieve a potential trapped volume between MV-100-N, MV-119-N, and MV-120-N – not for any operational condition. CV-100-N has a tiny hole thru the center which allows the trapped volume to extend to MV-100-N. This is approximately 40 ft. of vacuum jacketed ½ in. diameter stainless steel tube. The section of pipe protected is both inside and outside PAB. To size the trapped volume relief, half of the pipe is assumed to be engulfed in fire using the method outlined in Figure 1 with a piping length of 6.096 m instead of 3.81 m.

The total heat input into the liquid nitrogen is

$$q_{total} = \frac{5.67 \times 10^{-8} \frac{W}{m^2 \cdot K^4} (\pi \times 0.0127m \times 6.096m) (101.6^4 - 922^4) K^4}{\frac{1}{0.1} + \frac{1-0.7}{0.7} \left( \frac{0.0127m}{0.04272m} \right)} + \frac{2\pi \times 6.096m \times 0.04031 \frac{W}{m \cdot K} (101.6 - 922) K}{\ln \left( \frac{\frac{0.04272m}{2}}{\frac{0.0127m}{2}} \right)} = 2028W = 2028 \frac{J}{sec}$$

If the density of air is assumed to equal that of nitrogen, then the volumetric flow rate is

$$SCFM_{air} = 2028 \frac{J}{sec} \times \frac{1}{156966} \frac{kg}{J} \times \frac{2.205 lb}{1 kg} \times \frac{60 sec}{1 min} \times \frac{1}{0.07491} \frac{ft^3}{lb} = 22.79 \frac{ft^3}{min}$$

For PSV-118-N2, the required relief capacity was computed to be 22.79 SCFM. The capacity of this Circle Seal 5100 series 2MP relief at 10% overpressure for a 100 psig set point is 25 SCFM which is adequate for this case.

**PSV-203-Ar**

PSV-203-Ar is a trapped volume relief on the LAr source manifold. PSV-203-Ar has a 400 psig set point which is higher than the 350 psig set points of the FNAL stockroom high pressure 160 liter liquid argon dewars that supply the system. Thus PSV-203-Ar is sized to relieve a potential trapped volume between MV-204-Ar and MV-213-Ar, not for any




Figure 2: Heat transfer equations for trapped volume relief sizing for PSV-203-Ar

operational condition. This is approximately 10 ft. of 3/8 in. diameter stainless steel tube surrounded by a 1.5 inch tube vacuum jacket. To size the trapped volume relief, this short pipe is assumed to be engulfed in fire using the method outlined in Figure 2.

The total heat input into the liquid argon is

$$q_{total} = \frac{5.67 \times 10^{-8} \frac{W}{m^2 \cdot K^4} (\pi \times 0.009525m \times 3.048m) (139.8^4 - 922^4) K^4}{\frac{1}{0.1} + \frac{1-0.7}{0.7} \left( \frac{0.009525m}{0.03632m} \right)} + \frac{2\pi \times 3.048m \times 0.04153 \frac{W}{m \cdot K} (139.8 - 922) K}{\ln \left( \frac{\frac{0.03632m}{2}}{\frac{0.009525m}{2}} \right)} = 834W = 834 \frac{J}{sec}$$

The argon mass flow rate,  $W_{Ar}$ , must be converted into an equivalent volumetric flow rate for Air to compare to the manufacturer's tabulated relief valve capacity.

$$W_{Ar} = q_{total} \times \frac{1}{latent\ heat_{Ar}} = 834 \frac{J}{sec} \times \frac{1}{85166 \frac{J}{kg}} \times \frac{2.205 \frac{lb}{kg}}{1} \times \frac{3600 \frac{sec}{hr}}{1} = 77.74 \frac{lb}{hr}$$

ASME Section VIII Appendix 11 contains a method to convert relief valve capacity from one vapor to another that utilizes the following equations for this case

$$W_{Ar} = C_{Ar} (KAP) \sqrt{\frac{M_{Ar}}{T_{Ar}}} \text{ and } W_{Air} = C_{Air} (KAP) \sqrt{\frac{M_{Air}}{T_{Air}}} \text{ where}$$

$W_{Ar}$  = mass flow rate of argon, 77.74 lb/hr

$W_{Air}$  = mass flow rate of air, to be solved for

$C_{Ar}$  = constant based on the specific heats of argon, 378

$C_{Air}$  = constant based on the specific heats of air, 356

$KAP$  = set of factors specific to the relief valve, to be solved for

$M_{Ar}$  = molecular weight of argon, 39.9

$M_{Air}$  = molecular weight of air, 28.9

$T_{Ar}$  = temperature of argon being relieved, 520 °R.

$T_{Air}$  = temperature of air being relieved, 520 °R.

$$\text{Solving for KAP yields } (KAP) = \frac{W_{Ar}}{C_{Ar} \sqrt{\frac{M_{Ar}}{T_{Ar}}}} = \frac{77.74}{378 \sqrt{\frac{39.9}{520}}} = 0.7424. \text{ The equivalent mass flow rate of air is}$$

$$\text{then computed as } W_{Air} = 356(0.7424) \sqrt{\frac{28.9}{520}} = 62.31 \frac{lb}{hr}$$

rate is divided by the density of air at STP.

$$SCFM_{air} = \frac{62.31 \text{ lb}}{1 \text{ hr}} \times \frac{1 \text{ hr}}{60 \text{ min}} \frac{1 \text{ ft}^3}{0.07491 \text{ lb}} = 13.86 \frac{\text{ft}^3}{\text{min}}$$

PSV-203-Ar is a Circle Seal 5100-4MP which has a capacity of 270 SCFM at 10% over pressure beyond its 400 psig cracking pressure which is adequate for this case.

### **PSV-219-Ar**

PSV-219-Ar is a trapped volume relief that protects the piping between MV-213-Ar and MV-217-Ar. Most of this section of piping is inside the inner vessel of a cryostat designed to hold helium. During normal operation both the inner vessel and the insulating vacuum space are under vacuum. This section of piping contains a molecular sieve filter that is wrapped with heating tape for regeneration purposes. The heating tape has a total power of 1,000 W. The piping in the cryostat is protected from fire by the stainless steel inner vessel wall and the vacuum jacket wall. The piping section is relatively small compared to the space available in the cryostat. Even if the vacuum failed in both spaces during a fire, heat input into the piping would be much slower than calculated for the more typical vacuum jacketed piping associated with relief valves such as PSV-101-N2. Thus it seems reasonable to size PSV-219-Ar for a heater malfunction.

The argon mass flow rate,  $W_{Ar}$ , must be calculated from the heat input and then converted into an equivalent volumetric flow rate for Air to compare to the manufacturer's tabulated relief valve capacity as it was for PSV-203-Ar.

$$W_{Ar} = q_{total} \times \frac{1}{\text{latent heat}_{Ar}} = 1000 \frac{J}{\text{sec}} \times \frac{1 \text{ kg}}{85166 \text{ J}} \times \frac{2.205 \text{ lb}}{1 \text{ kg}} \times \frac{3600 \text{ sec}}{1 \text{ hr}} = 93.21 \frac{\text{lb}}{\text{hr}}$$

$$\text{Solving for KAP yields } (KAP) = \frac{W_{Ar}}{C_{Ar} \sqrt{\frac{M_{Ar}}{T_{Ar}}}} = \frac{93.21}{378 \sqrt{\frac{39.9}{520}}} = 0.8902. \text{ The equivalent mass flow rate of air is}$$

$$\text{then computed as } W_{Air} = 356(0.8902) \sqrt{\frac{28.9}{520}} = 74.71 \frac{\text{lb}}{\text{hr}}. \text{ To convert the air mass flow rate into SCFM, the mass flow}$$

rate is divided by the density of air at STP.

$$SCFM_{air} = \frac{74.71 \text{ lb}}{1 \text{ hr}} \times \frac{1 \text{ hr}}{60 \text{ min}} \frac{1 \text{ ft}^3}{0.07491 \text{ lb}} = 16.62 \frac{\text{ft}^3}{\text{min}}$$

PSV-219-Ar is a Circle Seal 5100-2MP which has a capacity of 80 SCFM at 10% over pressure beyond its 400 psig cracking pressure which is adequate for this case.

### **PSV-249-Ar**

PSV-249-Ar is a trapped volume relief that protects the section of the LAr transfer line between MV-208-Ar and MV-217-Ar. MV-202-Ar is not accessible when the system is cold. MV-202-Ar is only used to isolate the filter if it is removed from the piping and cryostat that provides its insulating vacuum. PSV-219-Ar is set to relieve at 400 psig which is above the 350 psig set point of the argon supply dewars. Thus PSV-219-Ar is sized to relieve heat input into a trapped volume. This section of piping includes an oxygen filter wrapped with a 1000 W heating tape for filter regeneration and a 250 W regeneration gas pre-heater. The tubing consists of about 12 feet of 3/8 in. tube surrounded by a 4 inch vacuum jacket. Figure 3 details the parameters for calculating heat input into the piping during a fire.




Figure 3: Heat transfer equations for trapped volume relief sizing for PSV-249-Ar

The heat input due to fire is

$$q_{total} = \frac{5.67 \times 10^{-8} \frac{W}{m^2 \cdot K^4} (\pi \times 0.009525m \times 3.658m) (139.8^4 - 922^4) K^4}{\frac{1}{0.1} + \frac{1-0.7}{0.7} \left( \frac{0.009525m}{0.1016m} \right)} + \frac{2\pi \times 3.658m \times 0.04153 \frac{W}{m \cdot K} (139.8 - 922) K}{\ln \left( \frac{\frac{0.1016m}{2}}{\frac{0.009525m}{2}} \right)} = 762W = 762 \frac{J}{sec}$$

If the 1250 W of heater capacity is added to the fire heat input, the total heat input is 2012 W. The argon mass flow rate,  $W_{Ar}$ , must be calculated from the heat input and then converted into an equivalent volumetric flow rate for Air to compare to the manufacturer's tabulated relief valve capacity.

$$W_{Ar} = q_{total} \times \frac{1}{latent\ heat_{Ar}} = 2012 \frac{J}{sec} \times \frac{1}{85166 \frac{J}{kg}} \times \frac{2.205 \frac{lb}{kg}}{1} \times \frac{3600 \frac{sec}{hr}}{1} = 187.53 \frac{lb}{hr}$$

Solving for KAP yields  $(KAP) = \frac{W_{Ar}}{C_{Ar} \sqrt{\frac{M_{Ar}}{T_{Ar}}}} = \frac{187.53}{378 \sqrt{\frac{39.9}{520}}} = 1.791$ . The equivalent mass flow rate of air is

then computed as  $W_{Air} = 356(1.791) \sqrt{\frac{28.9}{520}} = 150.31 \frac{lb}{hr}$ . To convert the air mass flow rate into SCFM, the mass flow

rate is divided by the density of air at STP.

$$SCFM_{air} = \frac{150.31 \frac{lb}{hr}}{1} \times \frac{1 \frac{hr}}{60 \text{ min}} \frac{1}{0.07491 \frac{lb}{ft^3}} = 33.44 \frac{ft^3}{min}$$

PSV-249-Ar is a Circle Seal 5100-2MP which has a capacity of 80 SCFM at 10% over pressure beyond its 400 psig cracking pressure which is adequate for this case.

### PSV-250-Ar

PSV-250-Ar is a trapped volume relief that protects the section of the LAr transfer line between MV-208-Ar and MV-244-Ar. PSV-250-Ar is set to relieve at 400 psig which is above the 350 psig set point of the argon supply dewars. Thus PSV-250-Ar is sized to relieve heat input into a trapped volume. The tubing consists of about 10 feet of 3/8 in. tube surrounded by a 4 inch vacuum jacket. Figure 3 details the parameters for calculating heat input into the piping during a fire except that the piping is a bit shorter at 10 feet in length.

The heat input due to fire is

$$q_{total} = \frac{5.67 \times 10^{-8} \frac{W}{m^2 \cdot K^4} (\pi \times 0.009525m \times 3.048m) (139.8^4 - 922^4) K^4}{\frac{1}{0.1} + \frac{1-0.7}{0.7} \left( \frac{0.009525m}{0.1016m} \right)} + \frac{2\pi \times 3.048m \times 0.04153 \frac{W}{m \cdot K} (139.8 - 922) K}{\ln \left( \frac{\frac{0.1016m}{2}}{\frac{0.009525m}{2}} \right)} = 635W = 635 \frac{J}{sec}$$

The argon mass flow rate,  $W_{Ar}$ , must be calculated from the heat input and then converted into an equivalent volumetric flow rate for Air to compare to the manufacturer's tabulated relief valve capacity.

$$W_{Ar} = q_{total} \times \frac{1}{latent\ heat_{Ar}} = 635 \frac{J}{sec} \times \frac{1}{85166 \frac{J}{kg}} \times \frac{2.205 \frac{lb}{kg}}{1} \times \frac{3600 \frac{sec}{hr}}{1} = 59.19 \frac{lb}{hr}$$

Solving for KAP yields  $(KAP) = \frac{W_{Ar}}{C_{Ar} \sqrt{\frac{M_{Ar}}{T_{Ar}}}} = \frac{59.19}{378 \sqrt{\frac{39.9}{520}}} = 0.565$ . The equivalent mass flow rate of air is

then computed as  $W_{Air} = 356(0.565) \sqrt{\frac{28.9}{520}} = 47.42 \frac{lb}{hr}$ . To convert the air mass flow rate into SCFM, the mass flow

rate is divided by the density of air at STP.

$$SCFM_{air} = \frac{47.42 \frac{lb}{hr}}{1} \times \frac{1 \frac{hr}}{60 \text{ min}} \times \frac{1 \text{ ft}^3}{0.07491 \frac{lb}{ft^3}} = 10.55 \frac{\text{ft}^3}{\text{min}}$$

PSV-250-Ar is a Circle Seal 5100-2MP which has a capacity of 80 SCFM at 10% over pressure beyond its 400 psig cracking pressure which is adequate for this case.

### PSV-156-Ar

PSV-156-Ar is a trapped volume relief that protects the vapor pump in Luke in the event that it is isolated from the cryostat. The 45 psig set point was chosen to protect the bellows in the cold valve EP-308-Ar. PSV-156-Ar is sized to vent the vapor that could be generated by the two heaters inside the vapor pump. Combined, these two heaters can provide 1750 W of heat input into LAr.

The argon mass flow rate,  $W_{Ar}$ , must be calculated from the heat input and then converted into an equivalent volumetric flow rate for Air to compare to the manufacturer's tabulated relief valve capacity.

$$W_{Ar} = q_{total} \times \frac{1}{latent\ heat_{Ar}} = 1750 \frac{J}{sec} \times \frac{1}{85166 \frac{J}{kg}} \times \frac{2.205 \frac{lb}{kg}}{1} \times \frac{3600 \frac{sec}{hr}}{1} = 163.11 \frac{lb}{hr}$$

Solving for KAP yields  $(KAP) = \frac{W_{Ar}}{C_{Ar} \sqrt{\frac{M_{Ar}}{T_{Ar}}}} = \frac{163.11}{378 \sqrt{\frac{39.9}{520}}} = 1.558$ . The equivalent mass flow rate of air is

then computed as  $W_{Air} = 356(1.558) \sqrt{\frac{28.9}{520}} = 130.76 \frac{lb}{hr}$ . To convert the air mass flow rate into SCFM, the mass flow rate is divided by the density of air at STP.

$$SCFM_{air} = \frac{130.76 \text{ lb}}{1} \times \frac{1}{hr} \times \frac{1}{60 \text{ min}} \times \frac{1}{0.07491 \text{ lb}} \frac{ft^3}{lb} = 29.09 \frac{ft^3}{min}$$

PSV-156-Ar is a Circle Seal 5100-4MP which has a capacity of 37 SCFM at 10% over pressure beyond its 45 psig cracking pressure which is adequate for this case.

### **SV-96-N**

SV-96-N relieves a potential trapped volume between RV-036-N and MV-096-N. These valves are located outside PAB on the liquid nitrogen dewar pressure building loop. This section of piping is 14 inches of ½" SCH 10 SS pipe.

CGA Standard 1.3 paragraph 5.3.2 gives an equation for the minimum required total capacity of the pressure relief devices at a flow rating pressure of 121 percent of the MAWP of an uninsulated cryogenic container exposed to fire:

$$Q_a = FG_u A^{0.82}$$

where

$Q_a$  = Flow capacity of the relief device required in cubic feet per minute of free air.

$F$  = Correction factor, = 1.0 because relief valve is connected to the relieving volume with piping shorter than 2 feet.

$G_u$  = Gas factor for an uninsulated container, = 59.0 at 100 psig (conservative, it would be lower at 80 psig).

$A$  = Outside surface area of relief volume, =  $2\pi \frac{0.84 \text{ in}}{2} \frac{ft}{12 \text{ in}} 1.17 \text{ ft} = 0.257 \text{ ft}^2$ .

The required relief capacity is then

$$Q_a = (1.0)(59)0.257^{0.82} = 19.4 \frac{ft^3}{min}$$

SV-96-N is a 1/2" Circle Seal series M5120 relief valve with a maximum flow rate of 51 SCFM at 80 PSIG with 10% overpressure, thus the trapped volume is adequately relieved with this relief valve.

### **SV-97-N**

SV-97-N relieves a potential trapped volume between RV-036-N and MV-088-N. These valves are located outside PAB on the liquid nitrogen dewar pressure building loop. This section of piping is 14 inches of ½" SCH 10 SS pipe.

CGA Standard 1.3 paragraph 5.3.2 gives an equation for the minimum required total capacity of the pressure relief devices at a flow rating pressure of 121 percent of the MAWP of an uninsulated cryogenic container exposed to fire:

$$Q_a = FG_u A^{0.82}$$

where

$Q_a$  = Flow capacity of the relief device required in cubic feet per minute of free air.

$F$  = Correction factor, = 1.0 because relief valve is connected to the relieving volume with piping shorter than 2 feet.

$G_u$  = Gas factor for an uninsulated container, = 59.0 at 100 psig (conservative, it would be lower at 80 psig).

$A$  = Outside surface area of relief volume, =  $2\pi \frac{0.84in}{2} \frac{ft}{12in} 1.17 ft = 0.257 ft^2$ .

The required relief capacity is then

$$Q_a = (1.0)(59)0.257^{0.82} = 19.4 \frac{ft^3}{min}$$

SV-97-N is a 1/2" Circle Seal series M5120 relief valve with a maximum flow rate of 51 SCFM at 80 PSIG with 10% overpressure, thus the trapped volume is adequately relieved with this relief valve.

#### **SV-98-N**

SV-98-N relieves a potential trapped volume between MV-95-N, MV-088-N, and MV-089-N. These valves are located outside PAB on the liquid nitrogen dewar pressure building loop. This section of piping is 17.8 feet of 1/2" SCH 10 SS pipe. Although SV-98-N is set to crack at 80 psig, all of the components it protects are rated for at least 250 psig.

CGA Standard 1.3 paragraph 5.3.2 gives an equation for the minimum required total capacity of the pressure relief devices at a flow rating pressure of 121 percent of the MAWP of an uninsulated cryogenic container exposed to fire:

$$Q_a = FG_u A^{0.82}$$

where

$Q_a$  = Flow capacity of the relief device required in cubic feet per minute of free air.

$F$  = Correction factor, = 1.0 because relief valve is connected to the relieving volume with piping shorter than 2 feet.

$G_u$  = Gas factor for an uninsulated container, = 75.5 at 250 psig.

$A$  = Outside surface area of relief volume, =  $2\pi \frac{0.84in}{2} \frac{ft}{12in} 17.8 ft = 3.91 ft^2$ .

The required relief capacity is then

$$Q_a = (1.0)(75.5)3.91^{0.82} = 231 \frac{ft^3}{min}$$

SV-98-N is a 1/2" Circle Seal series M5120 relief valve with a maximum flow rate of 250 SCFM at 200 PSIG with 25% overpressure, thus the trapped volume is adequately relieved with this relief valve.

### **SV-90-N**

SV-90-N relieves a potential trapped volume between PCV-70-N and MV-092-N. This section of piping is 5 feet of 1 1/2" SCH 10 SS pipe. Although SV-90-N is set to crack at 200 psig, all of the components it protects are rated for at least 250 psig.

CGA Standard 1.3 paragraph 5.3.2 gives an equation for the minimum required total capacity of the pressure relief devices at a flow rating pressure of 121 percent of the MAWP of an uninsulated cryogenic container exposed to fire:

$$Q_a = FG_u A^{0.82}$$

where

$Q_a$  = Flow capacity of the relief device required in cubic feet per minute of free air.

$F$  = Correction factor, = 1.0 because relief valve is connected to the relieving volume with piping shorter than 2 feet.

$G_u$  = Gas factor for an uninsulated container, = 75.5 at 250 psig.

$A$  = Outside surface area of relief volume, =  $2\pi \frac{1.90in}{2} \frac{ft}{12in} 5ft = 2.49 ft^2$ .

The required relief capacity is then

$$Q_a = (1.0)(75.5)2.49^{0.82} = 160 \frac{ft^3}{min}$$

SV-90-N is a 1/2" Circle Seal series M5120 relief valve with a maximum flow rate of 250 SCFM at 200 PSIG with 25% overpressure, thus the trapped volume is adequately relieved with this relief valve.

### **CVI-220-V**

This vacuum pumpout provides the vacuum relief for the "P-bar Molecular Sieve Filtering Dewar." Its spring has been removed to lower the relief pressure. The groove for the retaining clip has been filled with epoxy to prevent a spring from being re-installed. Thus it is basically a small parallel plate relief held shut by the vacuum pressure differential. This CVI model V-1046-31 vacuum pumpout port has a throat area of 1.23 in<sup>2</sup>. According to the CGA, the area of a vacuum relief in sq. in. should be 0.00024 x wc where wc is the water capacity in pounds of the vessel. The water capacity of the vessel is about 32 gallons based on its 120 liter volume. The density of water is about 8.34 lb/gal. Thus the required relief area is 0.00024 x 32 x 8.34 = 0.064 in<sup>2</sup>. Since the CVI throat area is much larger than the required relief area, the dewar is adequately relieved.

### **PSV-313-Ar**

This relief valve is a 1 inch Circle Seal 500 series set at 10 psig. It has two purposes. First it is a trapped volume relief for the material lock. Secondly, if MV-254-V is open, PSV-313-Ar will vent the cryostat vapor space before the main relief PSV-210-Ar opens. PSV-210-Ar is an ASME coded relief. It is desirable to avoid opening PSV-210-Ar because if it does not reseal, it will have to be sent off site for repair.

Interpolation from the air flow rate table provided by Circle Seal indicates that the capacity of this valve is 40 SCFM air at 50% over pressure beyond its 10 psig crack pressure. This is about 15 psig. The mass flow rate of air is calculated as

$$W_{air} = 40 \frac{ft^3}{min} \times \frac{60 min}{hr} \times \frac{0.07491 lb}{ft^3} = 179.78 \frac{lb}{hr}$$

This can then be converted to an equivalent flow rate of cold argon gas using the method outlined in ASME Section VIII Appendix 11.

$$\text{Solving for KAP yields } (KAP) = \frac{W_{Air}}{C_{Air} \sqrt{\frac{M_{Air}}{T_{Air}}}} = \frac{179.78}{356 \sqrt{\frac{28.9}{520}}} = 2.14. \text{ The equivalent mass flow rate of saturated argon}$$

$$\text{vapor is then computed as } W_{Ar} = 378(2.14) \sqrt{\frac{39.9}{170.2}} = 391.7 \frac{lb}{hr} \text{ where the temperature used is that of saturated argon}$$

vapor at 15 psig. To convert the argon mass flow rate into a volumetric flowrate, the mass flow rate is divided by the density of the saturated argon vapor at 15 psig

$$\text{Argon } \frac{ft^3}{min} = 391.7 \frac{lb}{hr} \times \frac{1 hr}{60 min} \frac{1}{0.688 lb} \frac{ft^3}{lb} = 9.5 \frac{ft^3}{min}$$

Another measure of the capacity of this relief valve is how much heat input into the liquid it can relieve, which is calculated by multiplying the saturated vapor mass flow rate by the heat of vaporization which is found to be

$$396.8 \frac{lb}{hr} \times \frac{67.67 Btu}{lb} \times \frac{1055.06 J}{1 Btu} \times \frac{1 hr}{3600 sec} = 7869 \frac{J}{sec} = 7869 W$$

### **PSV-378-Ar**

This relief valve is a 1 inch Circle Seal 5200 series set at 10 psig. Its purpose is to vent Bo at 10 psig so that the ASME coded relief valve PSV-377-Ar does not open at 35 psig. It is undesirable to open the coded relief because if it does not re-seal it must be sent out to a certified shop to be fixed.

#### **4.1c - Relief Valve Sizing for the PAB LN2 Dewar**

The pressure relief devices for the PAB LN2 dewar (formally PS1) were sized according to the Compressed Gas Association's CGA S-1.3—1995 document. This document is entitled, "Pressure Relief Device Standards Part 3—Stationary Storage Containers for Compressed Gases." In section 4.1.1 it states, "...each container shall be provided with a primary system of one or more pressure relief devices and a secondary system of one or more pressure relief valves or rupture disks or buckling pin devices." The relief valve sizing and installation described in this document also complies with the ASME PVB Div 1 UG-125 to UG-137 guidelines.

This vessel (Fermilab ID# RD0079) is equipped with two sets of pressure relief devices. Each set consists of an Anderson Greenwood relief valve paired with a Fike Corporation rupture disk in parallel. Both relief valves are set for 75 psig while the rupture discs are set to open at 105 psig. Either set can handle all conditions. Vessel dimensions and other characteristics are based upon Bruce Squire's Aug. 31<sup>st</sup> 1992 engineering note.

#### **Relief Valve Sizing for Fire Condition**

First the fire condition is considered as it is the most difficult to relieve. To begin the calculation, an estimate of the relief capacity required is computed. This number is then corrected for pressure drop and temperature rise in the line that leads to the reliefs. In section 5.3.3 of the CGA standard, the following equation is used to calculate the minimum required flow capacity

$$Q_a = FG_iUA^{0.82}$$

where:

$$U = \text{Overall heat transfer coefficient to the liquid, } \frac{\text{Btu}}{\text{hr} \cdot \text{ft}^2 \cdot ^\circ\text{F}}$$

The dewar is encased in perlite insulation 8.75 inches in thickness. The thermal conductivity for perlite is based upon Figure 7.13 in R. Barron's text Cryogenic Systems. At 10<sup>3</sup> torr, indicating the vacuum has been spoiled, the apparent thermal conductivity of the perlite is 43.3 mW m<sup>-1</sup> K<sup>-1</sup> which converts to 0.0250 Btu ft<sup>-1</sup> hr<sup>-1</sup> °F<sup>-1</sup>. The over heat transfer coefficient is then the thermal conductivity of the insulation divided by its thickness or

$$\frac{0.0250 \text{ Btu}}{\text{ft} \cdot \text{hr} \cdot ^\circ\text{F}} \frac{1}{0.73 \text{ ft}} = 0.034 \frac{\text{Btu}}{\text{hr} \cdot \text{ft}^2 \cdot ^\circ\text{F}}$$

$F =$  Correction factor for pressure drop and temperature rise in line to relief valve.

$A =$  Arithmetic mean of the inner and outer surface areas. The inner vessel is 66 inches in diameter ( $D_i$ ) and 128 in. long ( $OL_i$ ) while the outer vessel is 84 inches in diameter ( $D_o$ ) and 168 inches long ( $OL_o$ ).

$$A = \frac{(OL_i + 0.3D_i) \times D_i \times 3.1416 + (OL_o + 0.3D_o) \times D_o \times 3.1416}{2} = \frac{(128 + 0.3(66)) \times 66 \times 3.1416 + (168 + 0.3(84)) \times 84 \times 3.1416}{2} = 40815 \text{ in}^2 = 283 \text{ ft}^2$$

$G_i =$  Gas factor for insulated containers.

$Q_a =$  Flow capacity required at applicable flow rating pressure and 60 °F in cubic feet per minute of free air.

To calculate the initial estimate of the relief capacity needed, a gas factor,  $G_i$ , must be found. From Table 1 in CGA S-1.3 finds  $G_i$  to be 10.2 at 100 psig. This  $G_i$  value is conservative for the 75 psig reliefs.

The uncorrected volumetric flow rate was found to be

$$Q_{ae} = 1.0 \cdot 10.2 \cdot 0.034 \cdot 283^{0.82} = 35.5 \frac{ft^3}{min} \text{ of free air.}$$

The mass flow rate is computed using

$$W = \frac{Q_{ae} C}{18.35} \sqrt{\frac{M}{ZT}}$$

where

$Q_{ae}$  = calculated flow capacity with  $F=1.0$  in  $\frac{ft^3}{min}$  of free air.

$W$  = Required mass flow rate of lading thru the pressure relief device in  $\frac{lb_m}{hr}$ .

$C$  = Constant for vapor related to ratio of specific heats ( $k=C_p/C_v$ ) at standard conditions.  $k = 1.410$  for Nitrogen at 60 °F and 14.696 psia which corresponds to  $C = 356$ .

$M$  = Molecular weight of gas, 28.097.

$T$  = Flow rating temperature, 176.6 °R. (This is the saturation temperature at the flow rating pressure. The flow rating pressure is 110% of the relief valve set pressure. It is  $1.1 \times (75 + 14.7) = 98.67$  psia.)

$Z$  = Compressibility factor for saturated vapor at 98.67 psia.

$$Z = \frac{Pv}{RT}, \quad Z = \frac{98.67(0.5724)144}{\frac{1545}{28.097}(176.6)} = 0.8375.$$

$T$  = Flow rating temperature, 176.6 °R.

$M$  = Molecular weight of gas, 28.097.

$R$  = Ideal Gas constant

$v$  = specific volume, saturated vapor at flow rating pressure of 98.67 psia,  $0.5724 \frac{ft^3}{lb_m}$ .

The mass flow rate was found to be,  $W = \frac{35.5 \cdot 356}{18.35} \sqrt{\frac{28.097}{0.8375 \cdot 176.6}} = 300.2 \frac{lb_m}{hr}$ .

To calculate the temperature at the inlet of the relief device,

$$T_i = 2145 - \frac{2145 - T_s}{e^{\frac{5.24dL}{WC_p}}} \quad (\text{CGA S-1.3 Section 5.1.4})$$

was used where

$T_i$  = Temperature at the inlet to the pressure relief device during full flow conditions, °R.

$T_s$  = Saturation temperature at flow rating pressure, 176.6 °R.

$d$  = Line diameter. 2.375 in. is the outside diameter of the 2 inch SCH 10 pipe that leads to the relief valves.

$L$  = Length of piping between pressure relief device and container, 6.5 feet internal and 3.5 feet external for a total of 10 ft.

$W$  = Required mass flow rate of lading thru the pressure relief device,  $300.2 \frac{lb_m}{hr}$ .

$C_p$  = Average specific heat at constant pressure of lading between  $T_s$  and 590 °R,  
 $0.26 \frac{Btu}{lb_m \cdot ^\circ F}$ .

The inlet temperature to the relief device is then

$$T_i = 2145 - \frac{2145 - 176.6}{e^{\frac{5.24(2.375)10}{300.2(0.26)}}} = 1745^\circ R.$$

The pressure at the inlet of the relief device is calculated using

$$P_i = P - 3.36 \times 10^{-6} \frac{f \ell W^2 v}{d^5} \quad (\text{CGA S-1.3 Section 5.1.4})$$

where

$P_i$  = Pressure at the inlet of the pressure relief device.

$P$  = Flow rating pressure, 98.67 psia.

$f$  = Friction factor based on Crane Technical Paper No. 410,  $f = 0.019$ .

$\ell$  = Equivalent length of pipe based on Bruce Squire's calculations

$$\frac{K}{d^4} = 0.394 \Rightarrow K = 0.394d^4, L = \frac{Kd}{f} \Rightarrow L = \frac{0.394d^5}{f} \Rightarrow L = \frac{0.394(2.157^5)}{0.019} = 968in = 81ft$$

$W$  = Required mass flow rate,  $300.2 \frac{lb_m}{hr}$ .

$v =$  Specific volume of the fluid being relieved, at the flow rating pressure (98.67 psia) and the average temperature between  $T_i$  (1745 °R) and  $T_s$  (176.6 °R),  $3.741 \frac{ft^3}{lb_m}$ .

$d =$  Pipe diameter, 2.157 inches.

The inlet pressure to the relief valve is then

$$P_i = 98.67 - 3.36 \times 10^{-6} \frac{0.019(81)300.2^2 3.741}{2.157^5} = 98.63 \text{ psia.}$$

The correction factor that accounts for line pressure drop and temperature rise is

$$F = \sqrt{\frac{P_i V_i}{P v}}$$

where

$F =$  The correction factor.

$P_i =$  Pressure at the inlet of the pressure relief device, 98.63 psia.

$P =$  Flow rating pressure, 98.67 psia.

$v_i =$  Specific volume of the fluid being relieved at the inlet of the pressure relief device,  $6.794 \frac{ft^3}{lb_m}$ .

$v =$  Specific volume of the fluid being relieved at the flow rating pressure and temperature,  $0.5724 \frac{ft^3}{lb_m}$ .

The correction factor  $F$  was found to be

$$F = \sqrt{\frac{(98.63)6.794}{(98.67)0.5724}} = 3.44.$$

**Referring back to the beginning of this document, the corrected relief capacity required is**

$Q_a = 3.44(10.2) \cdot 0.034(283)^{0.82} = 122 \frac{ft^3}{min}$  **of free air for the fire condition. Each relief valve can deliver 731 SCFM, thus the vessel is adequately.**

The relief valves vent thru an elbow and 22 inches of vertical pipe. The pressure drop thru this vent is found from

$$\Delta P = 3.36 \times 10^{-6} \frac{f \ell W^2 v}{d^5}$$

where

$P_i$  = Pressure at the inlet of the pressure relief device, 14.7 psia for the assumption that the relief valve discharges to atmosphere.

$\Delta P$  = Pressure drop across relief valve, psi.

$f$  = Friction factor based on Crane Technical Paper No. 410,  $f = 0.019$ .

$\ell$  = Equivalent length of pipe for one elbow and 22 inches of straight pipe

$$f \frac{L}{D} = 30f_T \Rightarrow L_{elbow} = 30D, L_{total} = 30D + 22 = 30(2.157) + 22 = 87in = 7.25 ft.$$

$W$  = Required mass flow rate,  $300.2 \frac{lb_m}{hr}$ .

$v$  = Specific volume of the fluid being relieved, at the flow rating pressure (14.7 psia) and the fire temperature of  $T_i$  (1745 °R),  $45.49 \frac{ft^3}{lb_m}$ .

$d$  = Pipe diameter, 2.157 inches.

$$3.36 \times 10^{-6} \frac{0.019(7.25)300.2^2(45.49)}{2.157^5} = 0.04 psi$$

**Thus the pressure drop thru the relief valve exhaust stack is insignificant.**

### API Relief Valve Sizing Recommendations

The sizing of the relief valve must also be checked against the API recommendations. For Gas flow under sonic conditions the API recommends:

$$A = \frac{V\sqrt{ZTM}}{6.32CKP_1K_b}$$

Where:

$A$  = Required effective discharge area, in<sup>2</sup>.

$V$  = Required flow thru valve, 122 SCFM (for fire relief).

$T$  = Temperature, 1745 °R at flowing conditions (for fire relief).

$Z$  = Compressibility factor at flowing conditions (for fire relief),

$$Z = \frac{Pv}{RT}, \quad Z = \frac{98.67(6.791)144}{\frac{1545}{28.097}(1745)} = 1.0.$$

$C$  = Coefficient based on specific heats,  $C = 356$ .

$K$  = Effective coefficient of discharge,  $K = 0.816$  for the Anderson Greenwood reliefs.

$K_b$  = Capacity correction factor due to back pressure,  $K_b = 1.0$  as it was previously shown that the exhaust back pressure is minimal.

$P_1$  = Upstream pressure, 98.67 psia.

$$A = \frac{122\sqrt{1.0(1745)28}}{6.32(356)0.816(98.67)1.0} = 0.149in^2$$

The relief valves have an effective flow area of 0.503 in<sup>2</sup> which is >> 0.036 in<sup>2</sup>, thus they are adequately sized.

### **Relief Valve Reaction Forces**

Another concern is the force resulting from the discharge of the gas from the relief. The API standard RP 520 in Part II section 2.4 suggests the following equation to calculate the reactive force

$$F = W \frac{\sqrt{\frac{kT}{(k+1)M}}}{366}$$

where

$F$  = horizontal reactive force at center line of valve outlet when any gas or vapor is flowing, in pounds.

$W$  = flow of any gas or vapor, in pounds per hour. This value is 300.2 lbm hr<sup>-1</sup> for the fire condition.

$k$  = ratio of specific heats,  $C_p/C_v$  which is 1.41 for nitrogen.

$T$  = absolute temperature at inlet to relief valve, 1745 °R for the fire condition.

$M$  = molecular weight of any gas or vapor. The molecular weight for Nitrogen is 28.01.

$$F = 300.2 \frac{\sqrt{\frac{1.41(1745)}{(1.41+1)28.01}}}{366} = 4.95 \text{ pounds of force.}$$

**Thus the discharge force is insignificant at 4.95 pounds and no special measures need to be taken.**

### **Loss Of Vacuum Relief Valve Sizing**

The fire condition includes loss the loss of insulating vacuum. Thus the relief valve can easily handle loss of insulating vacuum without the heat input of a fire.

### **Pressure Building Loop Failure**

A failure in the pressure building loop is an additional scenario that could increase the dewar pressure and cause the relief valves to open. The  $C_v$  of the pressure building regulator (RV-036-N) is 1.3. There is about 80 inches of liquid head above the regulator which corresponds to a pressure difference of 2.33 psi. The maximum liquid nitrogen flow thru the regulator can be calculated using the following equation from Crane 410

$$Q = C_v \sqrt{\Delta P \frac{62.4}{\rho}} \text{ where}$$

$Q$  = liquid flow rate in gallons per minute.

$C_v$  = flow coefficient for pressure building regulator, = 1.3.

$\Delta P$  = pressure difference across the regulator, = 2.33 psi.

$\rho$  = density of liquid nitrogen at 75 psig, = 44.17 lb/ft<sup>3</sup>.

$$Q = 1.3 \sqrt{2.33 \frac{62.4}{44.7}} = 2.36 \frac{\text{gal}}{\text{min}}. \text{ This converts to SCFM nitrogen as}$$

$$2.36 \frac{\text{gal}}{\text{min}} \times \frac{1 \text{ft}^3}{7.48 \text{gal}} \times \frac{44.17 \text{lb}}{\text{ft}^3} \times \frac{\text{ft}^3}{0.07247 \text{lb}} = 192 \frac{\text{ft}^3}{\text{min}}. \text{ This is less than the relief valve}$$

capacity of 731 SCFM. This is a very conservative calculation because there are other restrictions in the pressure building loop and there is not enough vaporizer surface area to provide such a flowrate.

### **Vacuum Shell Relief**

The vacuum relief is sized according to the CGA standard that states the minimum discharge area of the vacuum jacket relief will be:

$$\text{Discharge Area (in}^2\text{)} = 0.00024 \times (\text{water capacity of the lading vessel (lb. H}_2\text{O)})$$

The volume of the lab 6 dewar is 1850 gallons. The density of water is 62.38 lb ft<sup>3</sup>. Thus the required vacuum relief area is

$$0.00024 \cdot 1850 \text{gal} \cdot \frac{1 \text{ft}^3}{7.481 \text{gal}} \cdot \frac{62.38 \text{lb}}{\text{ft}^3} = 3.70 \text{in}^2$$

The vacuum relief is supplied by a flat flange on top front of the vessel. The ID of the relief plate is 3 inches. The relief area available is then

$$= \frac{\pi}{4} (3.0)^2 = 7.1 \text{in}^2$$

which is more than adequate.

### **References**

Barrons, R. "Cryogenic System," Oxford University Press.

Hands, BA. "Cryogenic Engineering," Academic Press, pages 89-121.

Incropera, I. and DeWitt, D., "Fundamentals of Heat and Mass Transfer," John Wiley & Sons, pages 482-516.

## 4.2 – Material Stress Levels

### Luke and Bo Top Flanges

The flange that mates with both Luke and Bo is shown in Figure 4.2.1. The flange is 1.5 inch thick 304 stainless steel and is populated by several conflat flanges and VCR fittings. Both the conflat flanges and VCR fittings are welded to stainless steel tubes which are then welded to the flange.




Figure 4.2.1: Luke flange.

Ignoring the numerous penetrations for the moment, the stress in the flat head can be calculated from elastic plate theory as

$$\sigma = 0.3P \left( \frac{d}{t} \right)^2 \text{ where}$$

$P$  = maximum pressure differential across the head, 35 psi.

$d$  = diameter of the head, 23.035 inches according to Figure UG-34 (j).

$t$  = thickness of flange, 1.5 inches.

The maximum stress in the flat head is then

$$\sigma = 0.3P\left(\frac{d}{t}\right)^2 = 0.3(35)\left(\frac{23.035}{1.5}\right)^2 = 2476 \text{ psi which is far less than the 18,800 psi allowed by}$$

the ASME code for 304 SS.

Dave Pushka performed an FEA analysis of the head that includes all the penetrations. The model is conservative in two key ways. The penetration diameters match the mating tube ODs all the way thru the flange. In reality, there is a step that reduces the diameter of the penetration to that of the tube ID part way thru the flange. Secondly, the flange is fixed outside the bolt holes in the FEA model for modeling simplicity.

Figure 4.2.2 shows the Von Mises stress contours. The maximum stress is 7,600 psi which is less than half of the ASME allowable stress of 18,800 psi.

@ 35 PSID  $\sigma = 7.6 \text{ ksi}$ ,  $\delta_{\text{max}} = 0.0128''$  - Dave




Figure 4.2.2: Luke flange stress contours at 35 psid.

Figure 4.2.3 shows the deflection contours. The maximum deflection is  $1.28 \times 10^{-2}$  inches.




Figure 4.2.3: Luke flange displacement contours at 35 psid.

Sixteen bolts hold the top flange to the mating cryostat flange. These  $\frac{3}{4}$  - 10 bolts are stainless steel with a minimum strength of 70,000 psi. Brass nuts with a minimum strength of 55,000 psi are installed to prevent stainless on stainless galling.

The o-ring that provides the seal between the flanges has a diameter of 23.035 inches. The force  $F$  applied to the top flange at 110% of MAWP is then

$$F = A \times P = \frac{\pi}{4} (23.035^2) \text{in}^2 \times 1.1 \times 35 \frac{\text{lb}}{\text{in}^2} = 16,044.5 \text{ lbs.}$$

Each bolt has a tensile stress area  $A_t$  of  $0.3345 \text{ in}^2$ . The stress in each bolt is then

$$\sigma_{\text{bolt}} = \frac{F}{A_t} = \frac{16,044.5 \text{ lbs}}{0.3345 \text{ in}^2} = 2998 \frac{\text{lb}}{\text{in}^2}. \text{ The bolt stress due to the maximum pressure difference}$$

the flange will see is only 4 percent of the minimum bolt strength.

For the brass nuts stripping at their major diameter, the shear area  $A_s$  for one screw thread is

$$A_s = \pi d w_o p.$$

The area factor  $w_o$  for thread stripping shear area is 0.88 for UNS threads and the pitch  $p$  is 0.1 for 10 threads per inch.

$$A_s = \pi \times 0.75 \text{ in} \times 0.88 \times 0.1 \text{ in} = 0.2073 \text{ in}^2$$

The shear stress  $\tau_s$  for thread stripping in the brass nut is then

$$\tau_s = \frac{F}{A_s} = \frac{16,044.5 \text{ lbs}}{0.2073 \text{ in}^2} = 4837 \frac{\text{lb}}{\text{in}^2}. \text{ Thus the brass nut is only at 9\% of its minimum strength.}$$

Three large 8 inch conflat flanges that populate the flange. The conflat flanges are not rated for positive pressure, however they are quite substantial. A blank 8 inch conflat flange has a thickness of 0.880 inches, a bolt circle diameter of 7.128 inches, and is constructed from 304L SS. If modeled as an elastic plate, the ASME stress at 35 psid can be calculated as

$$\sigma = 0.3P \left( \frac{d}{t} \right)^2 = 0.3(35) \left( \frac{7.128}{0.88} \right)^2 = 689 \text{ psi} \text{ which is far less than the ASME allowable stress}$$

of 16,700 psi for 304L SS. The smaller conflats used on the system are just as substantial.

#### Argon piping

The argon piping that takes liquid thru the filters and into Luke is 3/8 inch OD 0.035 inch wall 304 type stainless steel tube and 3/8 inch OD 0.032 inch wall Cu tubing. The piping run that brings liquid to Bo is 1/2 inch OD 0.035 inch wall 304 type stainless steel tube.

The MAWP of this tubing can be calculated from ANSI/B31.1.

$$P = \frac{2SEt_m}{D_o - 2yt_m} \text{ where}$$

$SE =$  allowable stress, 18,800 psi for SS304, 6,000 psi for Cu.

$t_m =$  Minimum wall thickness allowed, = 92.5%  $t_n$  for tubing.

$t_n =$  Nominal wall thickness, inches.

$D_o =$  Outside diameter of pipe, = 0.375 inches.

$Y =$  Coefficient equal to 0.4.

For the 3/8 inch OD stainless steel tubing, the maximum allowable working pressure is

$$P = \frac{2(18800)0.925(0.035)}{0.375 - 2(0.4)0.925(0.035)} = 3487 \text{ psi.}$$

For the 1/2 inch OD stainless steel tubing, the maximum allowable working pressure is

$$P = \frac{2(18800)0.925(0.035)}{0.500 - 2(0.4)0.925(0.035)} = 2568 \text{ psi.}$$

For the copper tubing, the maximum allowable working pressure is

$$P = \frac{2(6000)0.925(0.035)}{0.375 - 2(0.4)0.925(0.035)} = 1113 \text{ psi.}$$

All three tubing types are adequate for this application because the highest relief valve set point on the argon circuit is 400 psig.

### Radiography

Neither the argon piping nor the nitrogen piping was radiographed. During fabrication, it was learned that the cryogenic safety subcommittee was discussing the issue of radiographing vacuum jacketed piping and that a welding procedure was under development to use in lieu of radiography. All welding on the system was supervised by Cary Kendziora who is very experienced with the fabrication of welded stainless steel parts used in high vacuum applications.

### Argon Filters

The argon circuit contains two identical filter assemblies which are constructed from stainless steel tube and with conflat end flanges. The conflat flanges are blanks with a hole drilled thru the center for fluid flow. The stainless steel tube has an OD of 2.375 inches with a wall thickness of 0.09375 inches. The MAWP for the tube is then

$$P = \frac{2(18800)0.925(0.09375)}{2.375 - 2(0.4)0.925(0.09375)} = 1414 \text{ psi which is greater than the 400 psig relief}$$

valve set points.

If the conflat is modeled as a simply supported circular plate under uniform pressure, the stress in the conflat can be calculated from

$$\sigma = 0.300P\left(\frac{d}{t}\right)^2 \text{ where the 0.300 factor comes from ASME Fig. UG-34 Figure K and}$$

$P =$  the uniform applied pressure, 400 psig.

$d =$  diameter of conflat exposed to pressure, 3.05 inches.

$t =$  thickness of the conflat, 0.68 inches.

$$\text{The stress in the conflat is then } \sigma = 0.300(400)\left(\frac{3.05}{0.68}\right)^2 = 2414 \text{ psi which is far less}$$

than the allowable 18,800 psi for stainless steel.

The eight 5/16 inch diameter 24 thread per inch bolts used in the conflat flange are made from SS-302 HQ with a 70,000 psi yield strength. Their tensile stress area,  $A_t$ , is 0.0581 in<sup>2</sup>.

The force applied to the 8 bolts is the pressure multiplied by the area which is

$$400 \frac{lb}{in^2} \times \frac{\pi}{4} 3.05^2 in^2 = 2922 lb.$$

The tensile stress in the bolt,  $\sigma_t$ , is the force  $F$  divided by the tensile stress area  $A_t$ .


$$\sigma_t = \frac{F}{A_t} = \frac{2922 lb}{8 \times 0.0581 in^2} = 6286 \frac{lb}{in^2}.$$

Thus the bolt stress due to the pressure applied to the flange

is less than 10% of the bolt's minimum yield strength.

### Argon Fill Manifold

The argon manifold that ties four stock room dewars together was analyzed using the piping features built into ANSYS. A 400 psi internal pressure was applied and the internal tubing was fixed at each point where it is welded to the vacuum jacket. Figure 4.2.4 shows the model result which indicates the maximum stress is 8,543 psi which is less than half of the allowable 18,800 psi for 304 stainless steel.



### Liquid Nitrogen Piping

The liquid nitrogen piping consists of 304 stainless steel tube that is 0.5 inch OD with a 0.035 inch wall. The maximum allow working pressure for this tube is

$$P = \frac{2(18800)0.925(0.035)}{0.500 - 2(0.4)0.925(0.035)} = 2568 \text{ psi which is far more than the 100 psig}$$

trapped volume relief valve set points.

Thermal contraction in the liquid nitrogen transfer line is taken care of by numerous braided stainless steel flex hoses which are all rated for at least 100 psig.

### Argon transfer line

The argon transfer line is designed in a manner such that the stresses due to thermal contraction are insignificant. In Figure 1.1.1, the large amount of flexibility in the argon transfer line is apparent.

### MV-254-V

MV-254-V is a Norcal manually operated viton seal vacuum gate valve constructed from 304 stainless steel. The valve attaches to the cryostat using 8 inch conflat flanges. The valve was chosen to create a large aperture for passing materials thru that can be sealed. The valve is not rated by Norcal for positive internal pressure.

The structurally weakest part of the valve appears to be large flat rectangular panel between the conflat flange and the thick end flange that holds the actuating mechanism. To investigate the stress in this part, the section was analyzed as an unstayed flat head per section UG-34 of the ASME code.

The maximum pressure for this valve can be calculated from

$$t = d\sqrt{\frac{ZCP}{SE}} \Rightarrow P = \left(\frac{t}{d}\right)^2 \frac{SE}{ZC} \text{ and } Z = 3.4 - \frac{2.4d}{D} \text{ where}$$

$t$  = minimum required thickness of the flat heat.

$d$  = length of short span, = 6 inches.

$D$  = long span of noncircular heads measured perpendicular to short span, = 7 9/16 inches.

$Z$  = factor of noncircular heads and covers that depends on the ratio of the short span to the long span

$C$  = a factor depending upon the method of attachment of head, = 0.33 from Figure UG-34.

$P$  = internal design pressure, 35 psi.

$S$  = maximum allowable stress value in tension, = 18,800 psi for 304 SS.

$E$  = joint efficiency from Table UW-12, taken as 0.5 to be conservative.

$$Z = 3.4 - \frac{2.4(6)}{\left(7 + \frac{9}{16}\right)} = 1.496, P = \left(\frac{0.125}{6.0}\right)^2 \frac{(18800)0.5}{1.496(0.33)} = 8.3 \text{ psi.}$$

The maximum pressure this valve housing should see is 8.3 psid internal based on the large flat section.

The side of the valve consists of a strip of 1/8 inch thick stainless steel that measures 1.125" (d) x 13" (D). Applying the above equations gives an estimate of the strength of the maximum pressure this part of the valve body can withstand.

$$Z = 3.4 - \frac{2.4(1.125)}{(13)} = 3.19, P = \left(\frac{0.125}{1.125}\right)^2 \frac{(18800)0.5}{3.19(0.33)} = 110 \text{ psi}$$

The valve body is only pressurized if the valve is open. Otherwise the valve body is sealed off from the vapor space of Luke. When the valve is open, excess pressure is vented thru PSV-313-Ar which is set at 6 psig. However, PSV-313-Ar has less capacity than PSV-210-Ar. To ensure the valve body does not rupture if the gate valve is open when warm material is submerged into the liquid argon, it is strengthened by encasing the housing in 1/2 inch thick 6061-T6 Aluminum which has an ASME allowable stress of 10,500 psi. Applying the above equation again, an estimate is made for the strength of this housing

$$P = \left(\frac{0.5}{6.0}\right)^2 \frac{(10500)0.5}{1.496(0.33)} = 73.9 \text{ psi. This exceeds the 35 psig relief valve set point. MV-254-V}$$

has been successfully pressure tested to 110% of the 35 psig MAWP of Luke.

### Condenser

The pressure in the nitrogen space of the condenser is controlled by a pressure relieving regulator (PCV-388-N2). If the regulator fails to vent the excess pressure, a trapped volume relief (PSV-389-N2) set at 61 psig protects the condenser nitrogen space. The maximum pressure the condenser nitrogen space could see is the nitrogen dewar MAWP of 75 psig. The maximum pressure differential that can be applied to the 6 inch tube calculated from

$$P = \frac{2SEt_m}{D_o - 2yt_m} \text{ where}$$

SE = allowable stress, 18,800 psi for SS304.

$t_m$  = Minimum wall thickness allowed, = 92.5%  $t_n$  for tubing.

$t_n$  = Nominal wall thickness, 0.109 inches.

$D_o$  = Outside diameter of pipe, = 6.0 inches.

Y = Coefficient equal to 0.4.

For the stainless steel tubing, the maximum allowable working pressure is

$$P = \frac{2(18800)0.925(0.109)}{6.0 - 2(0.4)0.925(0.109)} = 640 \text{ psi which is far above the maximum 90 psid to vacuum}$$

the nitrogen space could see (90 psid = 75 psig in LN2 supply + 15 psid to vacuum).

From elastic plate theory, the stress in the top and bottom fixed welded plates that cap the nitrogen space can be calculated as

$$\sigma = 0.188P \left( \frac{d}{t} \right)^2 = 0.188(90) \left( \frac{6}{0.375} \right)^2 = 4331 \text{ psi which is far less than the 18,800 psi}$$

maximum allowable stress in 304 stainless steel.

The argon space of the condenser will see the maximum dewar pressure of 35 psig.

The argon space is fabricated from 2 inch SCH 10 SS pipe with a 0.109 inch wall and 3/8 inch SCH 10 SS pipe with a 0.065 inch wall.

The maximum pressure that may be applied to the 2 inch section is calculated in the following manner.

$$P = \frac{2SEt_m}{D_o - 2yt_m} \text{ where}$$

$SE$  = allowable stress, 18,000 psi for 304 SS.

$t_m$  = Minimum wall thickness allowed, = 92.5%  $t_n$  for tubing.

$t_n$  = Nominal wall thickness, 0.109 inches.

$D_o$  = Outside diameter of pipe, = 2.375 inches.

$Y$  = Coefficient equal to 0.4.

For the SS tubing, the maximum allowable working pressure is

$$P = \frac{2(18800)0.925(0.109)}{2.375 - 2(0.4)0.925(0.109)} = 1652 \text{ psi which is far above the 35 psid maximum from the}$$

argon to the nitrogen space.

The maximum pressure that may be applied to the 3/8 inch section is calculated in the following manner.

$$P = \frac{2SEt_m}{D_o - 2yt_m} \text{ where}$$

$SE$  = allowable stress, 18,000 psi for SS 304.

$t_m$  = Minimum wall thickness allowed, = 92.5%  $t_n$  for tubing.

$t_n$  = Nominal wall thickness, 0.065 nches.

$D_o$  = Outside diameter of pipe, = 0.675 inches.

$Y$  = Coefficient equal to 0.4.

For the smaller SS tubing, the maximum allowable working pressure is

$$P = \frac{2(18000)0.925(0.065)}{0.675 - 2(0.4)0.925(0.065)} = 3606 \text{ psi}$$

which is far above the 35 psid maximum from the

argon to the nitrogen space.

From elastic plate theory, the stress in the top fixed welded plate that caps the argon space can be calculated as

$$\sigma = 0.188P \left( \frac{d}{t} \right)^2 = 0.188(35) \left( \frac{2.375}{0.125} \right)^2 = 2375 \text{ psi}$$

which is far less than the 18,000 psi

maximum allowable stress in the stainless steel.

The argon space of the condenser can be externally pressurized by nitrogen. If the nitrogen supply dewar is at its 75 psig MAWP and the argon space is evacuated, the tubing could see an equivalent of 90 psi external pressure. Using the method prescribed in part UG-28 of the ASME Section VIII Division 1 code, the maximum allowable external pressure is calculated.

First  $D_o / t$  is calculated where  $D_o$  is the pipe outside diameter of 2.375 inches and  $t$  is the wall thickness of 0.109 inches.  $D_o / t = 2.375 / 0.109 = 21.8$ .

Because  $D_o / t$  is greater than 4, calculate  $L / D_o$  where  $L$  is the length of the cylinder which is 13 inches.  $L / D_o = 13 / 2.375 = 5.5$ .

Because  $L$  is greater than 0.05 and less than 50, enter Figure G in ASME Section II Part D and locate the value for Factor A. With a  $L / D_o = 5.5$  and  $D_o / t = 21.8$ , Factor A = 0.003.

From Figure HA-1 in Section II Part D, Factor B is 12,500 based on Factor A equal to 0.003 and the 100 °F modulus curve.

Because  $D_o / t$  is greater than 10, the maximum allowable external pressure is calculated using

$$P = \frac{4B}{3 \frac{D_o}{t}} = \frac{4 \times 12,500}{3 \frac{2.375}{0.109}} = 765 \text{ psi}$$

The condenser argon space can handle the external

pressure because 765 psi >> 90 psi. The smaller diameter 3/8 inch pipe with its smaller  $D_o / t$  ratio and shorter length will be able to withstand more external pressure than the 2 inch pipe.

### Materials Lock Sightglass

The 8 inch conflat flange that allows access to the materials lock contains a sight glass. The sightglass assembly is welded into a conflat flange. The sightglass is shown in Figure 4.2.5.



Figure 4.2.5: Material lock sightglass.

The smaller photo in Figure 4.2.5 shows a piece of Lexan bulletproof glass that has been mounted on standoffs above the glass window. The Lexan will provide operator protection in the unlikely event of window failure. The Lexan will also protect the window from scratching which is one of the most common modes of window failure.

The sightglass was purchased from L.J. Star Incorporated. The glass is borosilicate and conforms to DIN 7080. DIN 7080 governs dimensional tolerances for disc sight glasses as well as provides the formula to calculate glass thickness. This DIN 7080 thickness formula is shown at the end of this section in the Schott North America Maxos brochure. The working pressure values given for DIN-glasses guarantee 5-fold safety. That is, they are subjected to a test pressure that is least 5 times higher than the working pressure.

The dimensions of the glass and its fitting are provided in the brochure at the end of this document. The size purchased is the DIN 150 size. The diameter of the glass itself is 6.535 inches and the thickness is 0.590 inches.

For a simply supported flat plate the stress is calculated using the following equation found on page 5-47 of the 10<sup>th</sup> edition of Mark's Standard Handbook for Mechanical Engineers

$$S_M = k \frac{wR^2}{t^2}$$

where

$S_M$  = maximum stress, psi

$k$  = factor from Table 5.2.19 on page 5-48, 1.24 for simply supported case

$w$  = uniformly distributed load, 90 psi for window maximum pressure rating

$R$  = window radius, 3.268 inches

$t$  = plate thickness, 0.59 inches for the window.

The stress in the window at its 90 psid rating is

$$S_M = k \frac{wR^2}{t^2} = 1.24 \frac{90 \times 3.268^2}{0.59^2} = 3,424 \text{ psi.}$$

The Schott North America Maxos brochure quotes a bending strength of 23,000 psi for borosilicate glass that conforms to DIN 7080 so this calculated value of 3,424 psi seems reasonable.

Pyrex thermal expansion is very similar to that of Invar, which is one of the most dimensionally stable cryogenic materials. Table 7.18 from Cryogenic Systems 2<sup>nd</sup> Edition by Randall F. Barron provides the unit thermal expansion for Pyrex from 0 to 300 K and is included after this discussion. Pyrex is one of the commercial names for borosilicate glass. If a length of borosilicate is fixed at both ends and then thermally shocked from 300 K to 90 K the thermal stress is simply Young's modulus multiplied by the change in length. The Schott North America Maxos brochure quotes a modulus of elasticity of  $67 \times 10^3 \text{ N/mm}^2$  which converts to  $9.73 \times 10^6$  psi.


The thermal shock stress is then  $(57 - 2.8) \times 10^{-5} \times 9.73 \times 10^6 \text{ psi} = 5,274 \text{ psi}$ . Table 10.2 on page 327 of Cryogenic Engineering by Russell B. Scott tabulates the breaking stress of borosilicate glass from 296 K down to 20 K, indicating that the glass becomes stronger at cryogenic temperatures. The lowest value at 296 K is 5000 psi and the lowest value at 76 K is 10,400 psi. Based on this extreme case, it seems reasonable that the window could withstand the sudden cooling that would occur with liquid argon contact.

The worst case for window cooling would occur during the filling of the cryostat. The large vacuum gate valve MV-254-V should be closed during the fill process. If the procedures are ignored and MV-254-V is open while the intended vapor vent valve MV-255-Ar is closed, a significant amount of vapor could flow thru the material lock and out the 6 psig relief valve PSV-313-Ar. The maximum liquid argon accumulation rate during a fill is at most 1.5 liters per minute based on operational experience. The vapor generated by the pressure reduction from the 350 psig argon source dewars to the cryostat is about 30% of the mass flow. Including some heat input, we could assume that 50% of the mass flow originating from the source dewars is vented as cold vapor. So the cold vapor vent rate is estimated as  $12.8 \text{ ft}^3 / \text{min}$  based on the 1.5 LPM liquid accumulation rate. This vapor flow rate would certainly cool down the window, but it is gas cooling so it will happen relatively slowly. Figure 4.2.6 shows the flow path of the vapor past the window.

If liquid were to reach the window, that could provide a high rate of uneven cooling. Fills of the cryostat are attended because there is no way to automatically shut off the flow of liquid argon. If liquid argon did reach the 1.5" thick top flange and the operator ignored it or was not present, there would be substantial vapor generation. The top flange contains the thermal capacity of more than 250 pounds of stainless steel. If liquid did reach the window after cooling the top flange, the window would already be very cold due to all the cold vapor that would have vented past it prior to liquid reaching it.

In the material lock procedures it is stated that test samples should not be in a shape that could retain liquid argon when the sample is removed from the system.

Figure 4.2.6: Material lock



22 psig relief - PSV-313-Ar

Bellows with internal support rod.

Location of sight glass  
Glass temperature rating is -200 to +280 C  
Lexan window not shown

Air lock chamber. This is where material basket resides when it is withdrawn from cryostat.

3.5 inches

Where sight glass flange mates to 8 inch conflat cross

Large gate valve  
MV-254-V

**Weld Neck Sightglass Fittings Series MV**

ISO 9001

DATA SHEET 02-0040 12/03

**Application:**


Butt-weld sightglass fitting with screwed cover flange. Sightport for viewing into process vessels, silos, mixers, separators, pipelines, and other usually closed containers. Particularly suitable for pharmaceuticals, food and beverage processing, e.g. breweries, dairies etc.

**General:**

Sightglass fittings specific to DIN 11851 (dairy standard fittings) with see-through circular glasses. Threaded nozzles have weld necks.

**Operating Conditions**

Pressure: 90 psi (higher pressure ratings on request), vacuum  
 Temperature: max. 200°C (see temperature diagram) based on seal ring



Complete screwed sightglass fitting series MV

**Combinations:**


This sightglass unit can be combined with the Lumiglas luminaires for use in non hazardous areas. Window wipers, type SW1 can be fitted to sizes DN 65 and larger. Combination of luminaire plus wiper can be fitted to size DN 125.

**Parts & materials:** (drawing on the right)

Items	Parts name	Material options
1	slotted cover nut	stainless steel type 304
2	cushion gasket	Non-Asbestos
3	sightglass disc	soda lime glass, tempered for max temp 150°C; or borosilicate glass, tempered for max. temp 280°C
4	D-ring seal	Viton, PTFE, Buna, silicone
5	weld neck nozzle	stainless steel type: 316 L, 304; ASME material only available upon request
6	vessel wall	


**Assembly**

After welding nozzle 5 into the vessel wall 6, fit O-ring seal 4, glass disc 3 and gasket 2 as shown in the drawing on the right. Tighten all these parts down against the nozzle by cover nut 1. Always use the special "C-Spanner".



Exploded view of an MV series screwed sightglass fitting

## Dimensions of Screwed Sightglass Fittings



All dimensions in mm unless stated otherwise. Subject to change without prior notice

Size		DN 50	DN 65	DN 80	DN 100	DN 125	DN 150
Nominal bore	DN	50	65	80	100	125	150
Viewing diameter	d1*	50 (1.97")	65 (2.56")	80 (3.15")	100 (3.94")	125 (4.92")	150 (5.91")
Sightglass discs	d2	63	80	94	113	142	166
	s	10	12	12	15	15	15
Fittings	D*	92 (3.62")	112 (4.41")	127 (5.00")	148 (5.83")	178 (7.01")	210 (8.27")
	d*	61 (2.40")	79 (3.11")	93 (3.66")	114 (4.49")	136 (5.35")	163 (6.42")
	A*	44 (1.73")	52 (2.05")	57 (2.24")	69 (2.72")	59 (2.32")	62 (2.44")
	a	21	24	25	34	22	22

### Ordering Information:

Please specify the selected items as follows:

e.g. Series MV, DN 80, nominal pressure 90 psi

Preferred material for: weld flange, glass discs, seals. Cover nut always 304

\* Use mm dimensions for accuracy

ISO 9001 QA CERTIFICATE  
 GERMAN MANUFACTURER:  
 F.H. PAPANMEIER AWARDED QA APPROVAL CERTIFICATE



# LJSTAR

INCORPORATED

PO Box 1116 • Twinsburg, OH 44087 • (330) 405-3040 • Fax 405-3070


E-mail: [view@ljstar.com](mailto:view@ljstar.com) • Website: [www.ljstar.com](http://www.ljstar.com)

Page 265 of 300 ver. 6/3/2008

# MAXOS®



Safety Sight and Level Gauge  
Glasses Special-tempered




## The complete borosilicate safety sight and level gauge glass program

MAXOS® safety sight and level gauge glasses have proved themselves universally where visual process control is essential. This includes pressure vessels subjected to thermal and chemical stresses and liquid level gauge application.

A high safety level is secured through the use of special borosilicate glass of high chemical durability, exceptional purity and homogeneity. The low thermal expansion of our SUPRAX® 8488 borosilicate glass, combined with thermal prestressing (tempering) creates a high resistance to sudden temperature changes.

The material properties values and small dimensional tolerances are guaranteed by production and quality controls. With these exceptional safety characteristics, MAXOS® safety sight and level gauge glasses can be used under extreme operational conditions. It is therefore mainly these safety aspects which influence responsible technicians again and again to choose MAXOS®.



# Long form level gauge glasses, reflex and transparent

## Technical characteristics

### MAXOS® Product Range

Special tempered reflex and transparent level gauge glasses and disc sight glasses can be supplied in accordance to:

- DIN 7080/7081
- BS 3463
- JIS B 8211
- MIL - G - 16356 D
- SCHOTT USA Specification

### Bending strength (typical values)

Standard level gauge glasses	
≥ 150 N/mm <sup>2</sup>	21,000 psi
Average	
170 N/mm <sup>2</sup>	25,000 psi
High pressure level gauge glasses	
≥ 180 N/mm <sup>2</sup>	26,000 psi
Average	
200 N/mm <sup>2</sup>	29,000 psi

### Surface compressive stress

Standard level gauge glasses	
≥ 90 N/mm <sup>2</sup>	13,000 psi
Average	
100 N/mm <sup>2</sup>	14,500 psi
High pressure level gauge glasses	
≥ 100 N/mm <sup>2</sup>	14,500 psi
Average	
110 N/mm <sup>2</sup>	16,000 psi

### Parallelism

Standard level gauge glasses	
≤ 0.08 mm	0.003 inches
High pressure level gauge glasses	
≤ 0.05 mm	0.002 inches



All leading OEM's are using MAXOS®.




Long form level gauge glasses, reflex and transparent.



MAXOS® – a registered trademark of SCHOTT Glas

# Long form level gauge glasses, reflex and transparent


## Technical characteristics



Special tempered MAXOS® glasses under polarized light.

Bending strength is determined by the surface compressive stress and the inherent resistance of the glass. The inherent resistance is heavily dependent upon the surface quality.

For safety reasons, the stress to the glasses caused by internal forces, thermal stress and vessel pressure have to be totally absorbed by the surface compressive stress so that a tensile stress of the glass surface is prevented.




Pressure temperature graph for MAXOS® glasses. Range of application with no technically significant glass attack.

Application conditions	Maximum permissible pressure		Maximum permissible temperature	
	bar	psi	°C	°F
Saturated steam or hot water in direct contact with reflex or transparent sight glasses	35	500	243	470
Saturated steam or hot water in contact with transparent sight glasses protected with mica	103	1,500	320	608
Non-corrosive, non-steam service and no technically significant glass attack, with reflex or transparent glasses	280	4,000	38	100
Transparent sight glasses in contact with medias with no technically significant glass attack	345	5,000	38	100
High pressure transparent sight glasses in special armatures (gauges)	414	6,000	38	100

## Available sizes

Special design for REFLEX and TRANSPARENT on request:  
e.g. 21 mm thickness.



Reflex type glass  
(R form)

Transparent type glass  
(T form)

Size	Dimensions						max. flatness tolerance				
	Length		Width		Thickness		Standard		High pressure		
	mm	inch*)	mm	inch*)	mm	inch*)	mm	inch*)	mm	inch*)	
0	95	3.740	34	1.339	17.5	0.689	0.05	0.002	-	-	
1	115	4.500	34	1.339	17.5	0.689	0.05	0.002	0.05	0.002	
2	140	5.500	34	1.339	17.5	0.689	0.05	0.002	0.05	0.002	
3	165	6.500	34	1.339	17.5	0.689	0.05	0.002	0.05	0.002	
4	190	7.500	34	1.339	17.5	0.689	0.08	0.003	0.05	0.002	
5	220	8.625	34	1.339	17.5	0.689	0.08	0.003	0.05	0.002	
6	250	9.874	34	1.339	17.5	0.689	0.13	0.005	0.05	0.002	
7	280	11.000	34	1.339	17.5	0.689	0.13	0.005	0.05	0.002	
8	320	12.625	34	1.339	17.5	0.689	0.13	0.005	0.05	0.002	
9	340	13.374	34	1.339	17.5	0.689	0.13	0.005	0.05	0.002	
10	370	-	34	-	17.5	-	0.13	-	-	-	
11	400	-	34	-	17.5	-	0.13	-	-	-	
Tolerances*)	+ 0 - 1.5	+ 0 - 0.039	+ 0.2 - 0.8	+ 0.008 - 0.039	+ 0 - 1.0	+ 0 - 0.028					High pressure is effective only for transparent glasses.

\*) Inch dimensions are only valid for SCHOTT USA Specification.

### Flatness (max.)

Size 1-3 ≤ 0.05 mm ≤ 0.002 inches

Size 4-5 ≤ 0.08 mm ≤ 0.003 inches

Size 6-9 ≤ 0.13 mm ≤ 0.005 inches

High pressure ≤ 0.05 mm ≤ 0.002 inches  
(only transparent)

### Temperature

Thermal shock resistance  $\Delta T$  265 K

Max. permissible temperature 300 °C 572 °F


Protected with mica 320 °C 608 °F

Size	Dimensions			max. flatness tolerance
	Length	Width	Thickness	
	mm	mm	mm	mm
1	115	30	17.5	0.05
2	140	30	17.5	0.05
3	165	30	17.5	0.05
4	190	30	17.5	0.05
5	220	30	17.5	0.08
6	250	30	17.5	0.08
7	280	30	17.5	0.13
8	320	30	17.5	0.13
9	340	30	17.5	0.13
Tolerances	up to 250 ± 0.8 above 250 ± 1.0	+ 0.5 - 0.8	+ 0 - 1.0	

# Physical and chemical characteristics

<b>Glass Type SUPRAX® 8488</b>		Modulus of elasticity	67 x 10 <sup>3</sup> N/mm <sup>2</sup>
Coefficient of expansion $\alpha$ 20 °C/300 °C		Poisson's ratio $\mu$	0.20
	4.3 x 10 <sup>-6</sup> K <sup>-1</sup>	Thermal conductivity	
Transformation temperature 540 °C		$\lambda$ at 90 °C	1.2 $\frac{W}{m \cdot K}$
Glass temperature for the		Refractive index nd	1.484
viscosities dPas (Poise)	10 <sup>13.0</sup> 553 °C	( $\lambda = 587.6$ nm)	
	10 <sup>7.6</sup> 808 °C	Photoelastic	
	10 <sup>4.0</sup> 1200 °C	parameter K	3.2 x 10 <sup>-6</sup> mm <sup>2</sup> /N
Density at 25 °C			
	2.31g/cm <sup>3</sup>		

Chemical characteristics	Hydrolytic resistance	Acid resistance	Alkali resistance
Test acc. to	DIN ISO 719	DIN ISO 1776	DIN ISO 695
max. abrasion acc. to DIN ISO	0.1	< 100 $\mu$ g Na <sub>2</sub> O each 100 cm <sup>2</sup>	> 75–175 mg each 100 cm <sup>2</sup>
MAXOS® max. abrasion	0.050	< 40 $\mu$ g Na <sub>2</sub> O each 100 cm <sup>2</sup>	< 100 mg each 100 cm <sup>2</sup>
MAXOS®	HGB 1	–	class A2



The abrasion of MAXOS® glass in watery phase for several temperatures as a function of the pH-value.

## Disc sight glasses

### Technical characteristics

#### Dimensional tolerances (DIN 7080)

Diameter	
up to 135 mm	± 0.5 mm
150 to 200 mm	± 0.8 mm
above 200 mm	± 1.0 mm
Thickness	
up to 20 mm	+ 0.50 mm / - 0.25 mm
above 20 mm	+ 0.80 mm / - 0.40 mm

Bending strength	≥ 160 N/mm <sup>2</sup>	23,000 psi
Surface compressive stress	≥ 100–140 N/mm <sup>2</sup>	14,500–20,000 psi
Parallelism	≤ 0.20 mm	0.008 inches
Flatness	Diameter: up to 100 mm ≤ 0.05 above 100 up to 150 mm ≤ 0.08 above 150 up to 200 ≤ 0.12 above 200 mm ≤ 0.15	
Thermal shock resistance $\Delta T$	265 K	
Max. permissible temperature	300 °C	572 °F
Protected with mica	320 °C	608 °F


## Available size

Special dimensional design on request, e.g. Ø min. 30 – max. 265 mm and thickness min. 10 – max. 30 mm.



All MAXOS® glasses are marked with a production code number.

### Calculation of the glass thickness (acc. to DIN 7080)



$$s \geq 0.55 \cdot d_m \sqrt{\frac{p \cdot S}{10 \cdot \sigma_{DV} \text{ zul.}}}$$

s Theoretical minimum glass thickness in mm

$d_m$   $\frac{d_1 + d_2}{2}$  Mean sealing diameter in mm

$d_1$  Glass and sealing outside diameter in mm

$d_2$  Sealing inside diameter in mm

p Permissible pressure in bar

$\sigma_{DV} \text{ zul.}$  Min. value of surface compressive stress in N/mm<sup>2</sup>

S Safety factor = 5

Dimensions $d_1 \times s$ (mm)	Inspection aperture $d_2$ (mm)	Permissible pressure in bar	Dimensions $d_1 \times s$ (inch)	Inspection aperture $d_2$ (inch)	Permissible pressure in psi
30 x 15	20	200	1.181 x 0.591	0.787	2900
31.6 x 12.75	20	150	1.244 x 0.502	0.787	2175
34 x 17	24	200	1.339 x 0.669	0.945	2900
35 x 7	25	25	1.378 x 0.276	0.984	363
40 x 10	30	40	1.575 x 0.394	1.181	580
40 x 12	30	50	1.575 x 0.472	1.181	725
45 x 10	32	40	1.772 x 0.394	1.260	580
45 x 12	32	50	1.772 x 0.472	1.260	725
50 x 10	35	25	1.969 x 0.394	1.378	363
50 x 12	35	40	1.969 x 0.472	1.378	580
55 x 10	40	25	2.165 x 0.394	1.575	363
60 x 10	45	16	2.362 x 0.394	1.772	232
60 x 12	45	25	2.362 x 0.472	1.772	363
60 x 15	45	40	2.362 x 0.591	1.772	580
60 x 20	45	95	2.362 x 0.787	1.772	1377
63 x 8	48	8	2.480 x 0.315	1.890	116
63 x 10	48	16	2.480 x 0.394	1.890	232
63 x 12	48	25	2.480 x 0.472	1.890	363
63 x 15	48	40	2.480 x 0.591	1.890	580
65 x 10	50	12	2.559 x 0.394	1.969	174
65 x 15	50	40	2.559 x 0.591	1.969	580
70 x 12	55	16	2.756 x 0.472	2.165	232
70 x 15	55	25	2.756 x 0.591	2.165	363
75 x 12	60	16	2.953 x 0.472	2.362	232
80 x 10	65	10	3.150 x 0.394	2.559	145
80 x 12	65	16	3.150 x 0.472	2.559	232
80 x 15	65	25	3.150 x 0.591	2.559	363
80 x 20	65	40	3.150 x 0.787	2.559	580
90 x 10	70	8	3.543 x 0.394	2.756	116
92 x 10	72	8	3.622 x 0.394	2.835	116
95 x 10	75	6	3.740 x 0.394	2.953	87
95 x 15	75	16	3.740 x 0.591	2.953	232
100 x 10	80	7	3.937 x 0.394	3.150	101
100 x 12	80	10	3.937 x 0.472	3.150	145
100 x 15	80	16	3.937 x 0.591	3.150	232
100 x 20	80	25	3.937 x 0.787	3.150	363
100 x 25	80	40	3.937 x 0.984	3.150	580
113 x 15	88	10	4.449 x 0.591	3.465	145
115 x 15	90	10	4.528 x 0.591	3.543	145
120 x 15	95	10	4.724 x 0.591	3.740	145
125 x 15	100	10	4.921 x 0.591	3.937	145
125 x 20	100	16	4.921 x 0.787	3.937	232
125 x 25	100	25	4.921 x 0.984	3.937	363
125 x 30	100	40	4.921 x 1.181	3.937	580
130 x 15	105	10	5.118 x 0.591	4.134	145
135 x 25	110	25	5.315 x 0.984	4.331	363
150 x 10	125	2	5.906 x 0.394	4.921	29
150 x 15	125	8	5.906 x 0.591	4.921	116
150 x 20	125	10	5.906 x 0.787	4.921	145
150 x 25	125	16	5.906 x 0.984	4.921	232
150 x 30	125	25	5.906 x 1.181	4.921	363
175 x 20	150	10	6.890 x 0.787	5.906	145
175 x 25	150	16	6.890 x 0.984	5.906	232
175 x 30	150	25	6.890 x 1.181	5.906	363
200 x 20	175	8	7.874 x 0.787	6.890	116
200 x 25	175	10	7.874 x 0.984	6.890	145
200 x 30	175	16	7.874 x 1.181	6.890	232
250 x 20	225	4	9.843 x 0.787	8.858	58
250 x 25	225	8	9.843 x 0.984	8.858	116
250 x 30	225	10	9.843 x 1.181	8.858	145
265 x 30	240	8	10.433 x 1.181	9.449	116

Advanced Materials  
**SCHOTT North America, Inc.**  
555 Taxter Road  
Elmsford, NY 10523  
USA  
Phone: +1 (914) 831-2200  
Fax: +1 (914) 831-2346  
E-mail: [info@us.schott.com](mailto:info@us.schott.com)  
[www.us.schott.com](http://www.us.schott.com)

**SCHOTT**  
glass made of ideas

# CRYOGENIC SYSTEMS

*Second Edition*

**RANDALL F. BARRON**

*Department of Mechanical Engineering  
Louisiana Tech University*

**OXFORD UNIVERSITY PRESS, NEW YORK  
CLARENDON PRESS, OXFORD**

1985

Table 7.18. Unit thermal expansion for several solids (Corruccini and Gniewek 1961).

$$e_t = \Delta L/L = \int_0^T \lambda_t dT; \text{ multiply the numbers in the table by } 10^{-5}$$

= Borosilicate

Temperature (K)	Beryllium Copper	Aluminum	1020 Steel	304 Stainless	Monel	Invar	Yellow Brass	Plexiglass	Teflon	Pyrex Glass	Nylon	Polystyrene
0	0	0	0	0	0	0	0	0	0	0	0	0
20	0	0	0	0	0	0	1	15	30	-1.0	10	28
40	1	2	1	0	1	0	4	60	80	-2.0	37	84
50	3	5	2	2	3	0	9	83	109	-1.9	58	118
60	7	10	4	5	6	0	16	110	140	-1.5	81	156
70	12	16	7	11	10	1	24	136	176	-0.6	110	196
80	20	24	10	17	15	2	34	170	210	+1.0	142	242
90	29	34	15	25	21	3	45	196	250	2.8	177	286
100	39	45	20	35	28	5	58	230	290	4.5	217	339
120	61	72	32	55	45	9	85	290	380	8.5	301	445
140	85	103	47	78	64	13	115	360	480	13.0	393	558
160	110	138	64	103	84	18	147	440	600	17.5	493	676
180	137	175	82	129	107	23	180	530	740	22.5	600	798
200	165	214	101	157	130	29	215	630	900	27.5	716	924
250	242	318	155	229	193	41	304	915	1390	41.7	1050	1250
300	329	431	210	307	261	54	397	1275	1600	57.0	1450	1601

# CRYOGENIC ENGINEERING

*by*

RUSSELL B. SCOTT

*Chief, National Bureau of Standards  
Cryogenic Engineering Laboratory*



PREPARED FOR THE ATOMIC ENERGY COMMISSION

TABLE 10.1. MECHANICAL PROPERTIES OF PLASTICS

Plastic	Temp., °K	Ultimate Tensile Strength, psi × 10 <sup>-3</sup>	Compressive Yield Strength, psi × 10 <sup>-3</sup>	Young's Modulus, psi × 10 <sup>-6</sup>
Teflon® (Polytetrafluoroethylene)	295	2.	—	.06
	195	5.5	—	.26
	153	8.	9.	.54
	77	15.	18.5	.74
	20	—	25.	—
4	—	27.	1.0*	
Kel-F® (Polytrifluoromono- chloroethylene)	293	6.3	—	.26
	198	14.0	—	.62
	77	16.2	—	.84
	4	—	44.	—
Polyethylene	300	1.3	—	.02
	4	—	25.	—
Polyvinylchloride	293	7.7	—	.52
	198	17.4	—	.55
	77	19.7	—	1.11
Nylon	293	9.5	—	.43
	198	20.1	—	.56
	153	24.3	—	.75
	77	27.9	—	1.10
Mylar® (Polyethyleneterephthalate)	300	21.0	—	1.01
	195	27.	—	1.16
	77	31.	—	1.85

\* Compression data by Swenson [9]. All other values were measured in tension and are from [10] and [11].

Plastics reinforced with Fibreglas® show very good low-temperature properties. The ultimate strength parallel to the fibers increases at low temperatures and the modulus is approximately constant. Reinforcement also improves resistance to temperature shock.

**10.5. Glass.** At room temperature glass exhibits a peculiar kind of fatigue; that is, when subjected to a sufficiently severe load it will endure for a time (sometimes for hours or days) and then it will fail. It has been found also that the fatigue strength is reduced by the presence of atmospheric water vapor and microscopic surface defects [12] [13]. Another aspect of this same phenomenon is the dependence of strength upon the rate of application of the load. Kropschot and Mikesell [14] have made measurements on a

borosilicate glass down to 20°K with various constant rates of loading. Table 10.2 is a summary of their results.

TABLE 10.2. BREAKING STRESS OF A BOROSILICATE GLASS (BSC-2, CORNING 8370)

Condition	Rate of Stress Increase, lb in <sup>-2</sup> sec <sup>-1</sup>	Breaking Stress, lb in <sup>-2</sup>			
		296°K	194°K	76°K	20°K
Abraded	800	7500	9500	10,400	10,400
Abraded	10	5500	7500	10,400	10,600
Abraded	1	5000	6400	10,400	10,200
Unabraded	800	10,400		18,000	

The average strength of unabraded specimens is considerably higher than that of the abraded specimens. However, it was found that the statistical scatter of the values for the unabraded specimens was much greater. It appears that an accidental (and often invisible) surface defect can greatly reduce strength. Consequently for design purposes one should use values for abraded specimens.

## II. SPECIFIC HEAT

10.6. The design problems of the cryogenic engineer seldom call for extremely precise data on specific heats of structural materials. Nearly all the needs can be met with a general knowledge of the temperature dependence of specific heat and approximate estimates of the specific heats of those materials most likely to be of use. The specific heats of simple crystalline solids are well represented by the Debye relation. Actually the Debye equation is a general relationship, applicable to many elements and compounds, being expressed as the heat capacity per gram mole of the solid. Figure 10.2 shows a graph of the Debye equation,

$$C_v = 9R(T/\theta)^3 \int_0^{(\theta/T)} \frac{x^4 e^x}{(e^x - 1)^2} dx = 3RD(\theta/T)$$

$C_v$  is the heat capacity per gram mole,  $R$  is the universal gas constant,  $\theta$  is a constant of the material having the dimensions of temperature and called the Debye characteristic temperature, or simply the Debye theta.  $D(\theta/T)$  is the Debye function. Tables of Debye values of  $C_v$  and the corresponding internal energy function,  $E - E_0$  are given by Beattie [15]. The graphs of these functions as shown in Figure 10.2 are suitable for approximate computations, when the value of  $\theta$  for the material is known. The principal shortcoming of this approach is that only rather simple isotropic crystalline solids are well represented. However, Corruccini [1] has studied the problem carefully with the objective of making estimates of the specific heats of alloys and



Borosilicate glass is a particular type of glass, better known under the brand names Pyrex and Kimax. It was first developed by German glassmaker Otto Schott in the late 19th century and sold under the brand name "Duran" in 1893. After Corning Glass Works developed Pyrex in 1924, it became a synonym for borosilicate glass in the English-speaking world.

Borosilicate glass is the oldest type of glass to have appreciable resistance to thermal impact and higher temperatures, also has excellent resistance to chemical attack. In this glass structure, the first to carry the Pyrex trademark, some of the  $\text{SiO}_2$  is replaced by boric oxide.

Borosilicate glass has a low coefficient of thermal expansion and is, thus, suited for telescope mirrors and other precision parts. Also, because this glass can withstand thermal shock, it is used for oven and laboratory ware, headlamp lenses, and boiler gage glasses. Most borosilicate glasses have better resistance to acids than do soda-lime glasses, but poor resistance to alkalis. Glass fibers used in reinforcing plastic compounds are a modified borosilicate glass.

### ***Chemical Composition***

$\text{SiO}_2 = 80.6\%$   
 $\text{B}_2\text{O}_3 = 13.0\%$   
 $\text{Na}_2\text{O} = 4.0\%$   
 $\text{Al}_2\text{O}_3 = 2.3\%$

### ***Physical Properties***

Coefficient of expansion (20°C–300°C)  $3.3 \times 10^{-6} \text{ K}^{-1}$   
Density  $2.23 \text{ g/cm}^3$   
Refractive index (Sodium D line) 1.474  
Dielectric constant (1MHz, 20°C) 4.6  
Specific heat (20°C)  $750 \text{ J/kg}^\circ\text{C}$   
Thermal conductivity (20°C)  $1.14 \text{ W/m}^\circ\text{C}$   
Poisson's Ratio (25°C – 400°C) 0.2  
Young's Modulus (25°C)  $6400 \text{ kg/mm}^2$

## ***Optical Information***

Refractive index (Sodium D line) = 1.474

Visible light transmission, 2mm thick glass = 92%

Visible light transmission, 5mm thick glass = 91%

## ***Critical Temperatures***

150°C - When working above this temperature care should be taken to heat and cool Borosilicate glass in a slow and uniform manner.

500°C - The maximum temperature that Borosilicate glass should be subjected to and then only for short period of no longer than a few minutes.

510°C - Temperature at which thermal stress can be introduced to Borosilicate glassware.

565°C - Annealing temperature. When uniformly heated in controlled conditions, such as a kiln or oven thermal stress's can be removed.

820°C - Softening point at which Borosilicate may deform.

1252°C - Working point, the temperature that glassblowers need to attain in order to work Borosilicate glass.

## ***Working Temperatures***

Borosilicate glass retains its mechanical strength and will deform only at temperatures which approach its strain point. The practical upper limit for operating temperatures is much lower and is controlled by the temperature differentials in the glass, which depend on the relative temperatures of the contents of the equipment and the external surroundings.

Provided borosilicate glass is not subjected to rapid change in temperature, creating undue thermal shock, it can be operated safely at temperatures up to 450°F (232°C). The normal limiting factor is actually the gasket material. The degree of thermal shock (usually defined as sudden chilling) which it can withstand depends on many factors, for example: stresses due to operating conditions; stresses imposed in supporting the equipment; the wall thickness of the glass, etc. It is therefore

undesirable to give an overall figure but, as a general guide, sudden temperature changes of up to about 216°F (120°C) can be accommodated .

At sub-zero temperatures, the tensile strength of borosilicate glass tends to increase and equipment can be used with safety at cryogenic temperatures.

Further development in glassmaking continues to create new glass-ceramics that outperform borosilicate glass in various ways.

## **4.2 – Material Stress Levels Continued – Bo Feedthrus and Piping**

### “Bo” High Voltage Feed Thru

The electrical feed thru that provides high voltage (> 25 KV) to the TPC chamber was fabricated by Fermilab. Figure 4.2.7 shows the HV feed thru installed on the cryostat. The electrical conductor is a solid stainless steel rod which is 5/8 inch in diameter. The conductor is surrounded by a high density polyethylene (HDPE) cylinder. The conductor is press fit into the HDPE cylinder. The conductor and HDPE cylinder assembly is then cooled in liquid nitrogen and shrunk fit into the outer 1 3/8 inch diameter tube. The tight fit between the HDPE cylinder and both stainless steel components provides the pressure seal with respect to cryostat vapor. Figure 4.2.8 details this assembly. The assembly has passed a helium mass spec leak check. The feed thru's outside tube is welded to a 2 3/4 inch conflat flange which mates to the cryostat.

Since this HV feed thru is not a commercial component and does not easily lend itself to analysis, the ASME B31.3 Process Piping code is consulted. For unlisted components, B31.3 section 304.7.2(b) suggests a proof test in accordance with ASME B16.9, MSS SP-97, or Section VIII DIV I, UG101. ASME Section 8 Division 1 UG-101(p) requires the unlisted component to survive a hydrostatic test of not less than three times the desired MAWP without excessive deformation.


A hydrostatic pressure test was performed on a sample feed thru that is identical to the actual feed thru except that it is shorter in length. Figure 4.2.9 shows the sample that was pressure tested. The pressure test documentation is available in Section 3.5i.

First, the feed thru was tested to 105 psig, which is three times the 35 psig MAWP of Bo. No deformation occurred at this pressure. Next the pressure was slowly increased to 1000 psig in 50 psi increments. At about 550 psig a very small leak was observed. This leakage continued up to 1000 psig. After the 1000 psig pressure was removed, the point at which the water leakage occurred could not be located. Nor was any measurable deformation found.

Based on this pressure test, the HV feed thru is adequate for operation at “Bo's” 35 psig MAWP.



Figure 4.2.7: "Bo" high voltage feed thru installed.



5/8 inch diameter stainless steel rod high voltage conductor

High density polyethylene cylinder

1.375 inch OD, 0.035 inch wall, stainless steel tube

High voltage Feed thru is welded to a 2 3/4 inch conflat

High density polyethylene provides pressure seal

Bottom End of HV lead

Figure 4.2.8: “Bo” high voltage feed thru details.




Figure 4.2.9: “Bo” high voltage feed thru pressure test sample piece.

### “Bo” Signal Feed Thru

The TPC signal wires pass thru a Fermilab designed and fabricated feed thru. The feed thru is shown in Figure 4.2.10. Four slots were machined into a 6 inch OD conflat to accommodate D shaped electrical connectors. A short cylinder was welded to the conflat to provide containment for epoxy. The ribbon cables were connected to the D connectors and then the cylinder was filled with Stycast 2850 FT epoxy (cured with #9 catalyst). The epoxy provides a helium leak tight seal between the cables and the flange. The insulation is stripped from a portion of the cables so that the epoxy can make a seal with the bare conductors.

From the Lakeshore Cryotronics website, the following statement is quoted to document the appropriateness of the epoxy for cryogenic use.

“Stycast® is the most commonly used, highly versatile, nonconductive epoxy resin system for cryogenic use. The primary use for Stycast® is for vacuum feedthroughs or permanent thermal anchors. Lake Shore uses this product in vacuum tight lead-throughs with excellent thermal cycle reliability.”

[http://www.lakeshore.com/temp/acc/am\\_epoxypo.html](http://www.lakeshore.com/temp/acc/am_epoxypo.html)

A 4 inch OD tube is welded to an eight inch OD conflat on Bo. The tube then makes a right angle and enters a shielded electrical box. The signal feed thru flange is welded to this tube in the electrical box. This arrangement is shown in Figure 4.2.11.

Since this signal feed thru is not a commercial component and does not easily lend itself to analysis, the ASME B31.3 Process Piping code is consulted. For unlisted components, B31.3 section 304.7.2(b) suggests a proof test in accordance with ASME B16.9, MSS SP-97, or Section VIII DIV I, UG101. ASME Section 8 Division 1 UG-101(p) requires the unlisted component to survive a hydrostatic test of not less than three times the desired MAWP without excessive deformation.

A second feed thru flange was fabricated for proof testing. The flange, prior to being filled with epoxy, is shown in Figure 4.2.12. The pressure test documentation can be found in section 3.5j. The test flange showed no signs of leakage at 105 psig which is 3x the MAWP of “Bo.” The flange developed a pin hole sized leak at 400 psig. At 700 psig, 4 pin hole sized leaks developed. At 1000 psig, water was leaking thru the epoxy faster than the hydraulic pump could build pressure. The test flange did not have the ribbon cable insulation removed and the leakage occurred thru the insulation.





Figure 4.2.10: “Bo” signal feed thru.



Figure 4.2.11: Electronics box on “Bo”



Figure 4.2.12: Feed thru flange for pressure testing prior to being filled with epoxy

### LAr Supply Piping

Figure 4.2.13 shows the results from a FEA model of the LAr supply piping from the outlet of the oxygen filter used during the filling process to both “Luke” and “Bo.” The model considers the stress that results from the shrinkage from 300 K to 80 K and a 400 psig internal pressure.

The thermal shrinkage was taken to be  $290 \times 10^{-5} \Delta L/L$  for 304 Stainless and  $314 \times 10^{-5} \Delta L/L$  for Cu tube. The modulus of elasticity of 304 Stainless was input as 2.07E11 Pa along with a Poisson’s Ratio of 0.28. The modulus of elasticity of Cu was input as 1.207E11 Pa along with a Poisson’s Ratio of 0.35. The model also considers the density of the contained fluid, which was input as 1400 kg/m<sup>3</sup> for argon.

The model is comprised of ANSYS PIPE 16 (straight), PIPE 17 (tee), and PIPE 18 (elbow) elements in which ANSYS calculates flexibility and stress intensification per ANSI B31.1

The model shows a peak stress of 2,161 psi where the ½ inch OD stainless steel tube discharges into Bo. This is far below the 20,000 psi limit for seamless 304 SS or the 6,000 psi limit for seamless copper.

Section 3.5k documents the pneumatic pressure testing of this section of piping to 1.10x MAWP (440 psig).




Figure 4.2.13: LAr supply piping Von Mises Stresses due to cooldown shrinkage and internal 400 psig pressure.

Note: Bo\_LAr\_piping\_works.db is the ANSYS model file used.

### LAr Vent Piping

Figure 4.2.14 shows the results from a FEA model of the LAr vent piping that connects “Bo” and “Luke” to the LAr vaporizer. The model considers the stress that results from the shrinkage from 300 K to 80 K.

The thermal shrinkage was taken to be  $290 \times 10^{-5} \Delta L/L$  for 304 Stainless and  $314 \times 10^{-5} \Delta L/L$  for Cu tube. The modulus of elasticity of 304 Stainless was input as 2.07E11 Pa along with a Poisson's Ratio of 0.28. The modulus of elasticity of Cu was input as 1.207E11 Pa along with a Poisson's Ratio of 0.35. The model also considers the density of the contained fluid, which was input as 1400 kg/m<sup>3</sup> for argon.

The model is comprised of ANSYS PIPE 16 (straight), PIPE 17 (tee), and PIPE 18 (elbow) elements in which ANSYS calculates flexibility and stress intensification per ANSI B31.1

The model shows a peak stress of 3,844 psi where the ½ inch OD stainless steel vent tube connects to Luke. This is far below the 20,000 psi limit for seamless 304 SS or the 6,000 psi limit for seamless copper.




Figure 4.2.14: LAr vent piping Von Mises Stresses due to cooldown shrinkage

Note: Bo\_LAr\_piping\_vent\_works.db is the ANSYS model file used.

### Weld Examination for the LAr Transfer Line

336.5.1(b) of ANSI/ASME B31.3 states: “In-process examination as provided in 336.4.7 may be substituted for all or part of the radiographic or ultrasonic examination on a weld-for-weld basis if specified in the engineering design, regardless of temperature or pressure.”

Cary Kendziora performed in-process weld inspection for two of the welds in the piping that provides LAr to “Bo.” There are less than 40 welds in this line such that two in-process inspections satisfy the 5% examination requirement. The documentation is included on the next two pages.

## PPD Vacuum and Instrumentation Group In-Process Weld Inspection Form

(as per In-Process Weld Inspection Guidelines, AD Cryogenics, Nov 3, 2006)

Date April 15 Project: LAr Transfer Line  
Pipe Section: Between Luke and Bo Weld Number: 5  
Weld location: Vacuum insulated LAr transfer line  
Welder: Dan Watkins Inspector: C.Kendziora

### Before Welding:

Type of weld: (butt) X (other) \_\_\_\_\_  
(1) Pipe #1 Size, Schedule and material: \_\_\_\_\_ 1/2" OD \_\_\_\_ .035"  
wall \_\_\_\_\_  
(2) Pipe #2 Size, Schedule and material: \_\_\_\_\_ 1/2" OD \_\_\_\_ .035"  
wall \_\_\_\_\_

### (1) Joint Preparation and Cleanliness

Joint Preparation and Cleanliness acceptable? Yes

### (2) Welding Machine

(a) Remote foot pedal? Yes  
(b) DC straight machine? Yes

### (3) Joint Fit-up, and Internal Alignment.

(a) Internal alignment acceptable? Yes  
(b) Joint Clearance acceptable? Yes  
(c) End Preparation acceptable? Yes

### (4) Filler Rod

(a) AWS A5.9 stainless steel filler rod? Yes  
(b) Filler rod: Class A5.9 Diameter 0.035

### (5) Purge Gas.

(a) type of purge gas : Argon  
(b) time length of purge: 10min purge flow rate: 10  
SCFH \_\_\_\_\_  
(b) (if done) O2 reading: \_\_\_\_\_ O2 Monitor manf/model : \_\_\_\_\_

### (6) Inspection After Root Pass

(a) No visible cracks. None  
(b) No suck holes, which are small holes in middle of weld. None  
(c) No porosity or obvious imperfections. None  
(d) Filler material fused along edges of weld . Yes

(8) Repeat inspection after every pass: \_\_\_\_\_

(9) Final Inspection: Yes

## PPD Vacuum and Instrumentation Group In-Process Weld Inspection Form

(as per In-Process Weld Inspection Guidelines, AD Cryogenics, Nov 3, 2006)

Date April 15 Project: LAr Transfer Line  
Pipe Section: Between Luke and Bo Weld Number: 7  
Weld location: Vacuum insulated LAr transfer line  
Welder: Dan Watkins Inspector: C.Kendziora

### Before Welding:

Type of weld: (butt) X (other) \_\_\_\_\_  
(1) Pipe #1 Size, Schedule and material: \_\_\_\_\_ 1/2" OD .035" wall \_\_\_\_\_  
(2) Pipe #2 Size, Schedule and material: \_\_\_\_\_ 1/2" OD .035" wall \_\_\_\_\_

### (1) Joint Preparation and Cleanliness

Joint Preparation and Cleanliness acceptable? Yes

### (2) Welding Machine

(a) Remote foot pedal? Yes  
(b) DC straight machine? Yes

### (3) Joint Fit-up, and Internal Alignment.

(a) Internal alignment acceptable? Yes  
(b) Joint Clearance acceptable? Yes  
(c) End Preparation acceptable? Yes

### (4) Filler Rod

(a) AWS A5.9 stainless steel filler rod? Yes  
(b) Filler rod: Class A5.9 Diameter 0.035

### (5) Purge Gas.

(a) type of purge gas : Argon  
(b) time length of purge: 10min purge flow rate: 10  
SCFH \_\_\_\_\_  
(b) (if done) O2 reading: \_\_\_\_\_ O2 Monitor manf/model : \_\_\_\_\_

### (6) Inspection After Root Pass

(a) No visible cracks. None  
(b) No suck holes, which are small holes in middle of weld. None  
(c) No porosity or obvious imperfections. None  
(d) Filler material fused along edges of weld . Yes

(8) Repeat inspection after every pass: \_\_\_\_\_

(9) Final Inspection: Yes

### **4.3 – Correspondence Related to Operational Readiness Clearance**

To: Jim Strait  
Particle Physics Division

From: Phil Pfund  
Chair, Village & Misc. Cryogenic Safety Review Panel

Subject: PAB FLARE Safety Review

Dear Jim,

The Village & Misc. Cryogenic Safety Review Panel has completed its review of the FLARE liquid argon materials test station in the Proton Assembly Building (PAB).

Our review consisted of:

- Introduction and orientation walk-through on April 5, 2007.
- Review of safety related documentation. The documentation and updates are maintained by Terry Tope at: <http://lartpc-docdb.fnal.gov:8080/cgi-bin/ShowDocument?docid=265> login: lartpc , password: argon! The documentation consisted of:
  - System description
  - Flow schematic
  - Instrument and valve summary
  - System control loops
  - Fill procedure
  - FMEA – failure modes and effects analysis
  - “What-if” analysis
  - ODH analysis
  - “Luke” pressure vessel note
  - Liquid nitrogen pressure vessel note
  - Liquid nitrogen dewar compliance
  - Piping relief valves
  - LN2 relief valves
  - Material stresses
- Individual panel member meetings and e-mail exchanges with Terry Tope resulting in updates to the documentation listed above. In a few instances these resulted in changes to the hardware, also documented.
- Meeting to discuss final comments and walk-through with safety panel on June 15, 2007.
- Meeting with panel to review completion of “to-do” list and final walk-through on August 7, 2007. The walk-through resulted in two action items, both of which were reported complete on August 6, 2007:

- A caution tag was attached to the on/off "blade" switch on the box that provides power to the ODH fan.
- The window on the material lock was replaced by a blank 8 inch conflat flange.

Based on the above listed review activities, we are satisfied that the proposed test set-up can be operated safely. We recommend that you authorize the operation.

It should be noted that two future modifications are planned. (1) The window for the material lock will be reinstalled after sufficient work has been done to ensure its safe operation at cryogenic temperatures. (2) A second pressure vessel, referred to as "Cousin Bo", will be added to the system after the normal operational and safety related documentation has been developed. Each of these modifications is to be reviewed by this panel before this panel makes a recommendation to operate with either them in the system.

Regards,

Phil Pfund

On behalf of the Village & Misc. Cryogenic Safety Review Panel

Copy: Martha Heflin  
Terry Tope  
Panel Members (Brian DeGraff, Tom Page, Dave Pushka)

**From:** Jim Strait <strait@fnal.gov>  
**Subject:** Re: FLARE Test Station Safety Review  
**Date:** August 15, 2007 4:13:57 PM CDT  
**To:** Phil Pfund <pfund@fnal.gov>  
**Cc:** Martha Heflin <martha@fnal.gov>, Terry Tope <tope@fnal.gov>, Brian Degraff <degraff@fnal.gov>, Dave Pushka <pushka@fnal.gov>, Tom Page <tpage@fnal.gov>, Stephen Pordes <stephen@fnal.gov>, Dave Finley <finley@fnal.gov>, Hans Jostlein <jostlein@fnal.gov>, Cary Kendziora <clk@fnal.gov>, Kurt Krempetz <krempetz@fnal.gov>, Mike Crisler <mike@fnal.gov>, Greg Bock <bock@fnal.gov>, Win Baker <winbaker@fnal.gov>

---

Dear colleagues,

Based on the report of the Village & Misc. Cryogenic Safety Review Panel, I give (partial) Operational Readiness Clearance to the Liquid Argon Material Test Station cryogenic system in the Proton Assembly Building.

The word \*partial\* above is to emphasize that this is operational clearance for the \*cryogenic system\* only. I would like the Fixed Target ES&H Review Committee to be consulted on other safety aspects of the test system, which must include at least electrical safety, before granting full operational clearance for the Material Test Station. The LAr TPC group should take the lead in ensuring that such a review is done at the appropriate time.

Cheers,  
Jim

Phil Pfund wrote:

Jim, The Village & Misc. Cryogenic Safety Review Panel has completed its review of the FLARE liquid argon materials test station in the Proton Assembly Building (PAB). The attached memo documents our review and carries the recommendation to you to authorize operation of the system. We are aware that future modifications/additions are planned, as itemized in the memo, and will review them before they are integrated into the system. Phil

--

Philip A. Pfund  
Fermi National Accelerator Laboratory  
MS-316  
Direct: 630-840-4784  
FAX: 630-840-4529  
pfund@fnal.gov

**From:** Phil Pfund <pfund@fnal.gov>  
**Subject:** **FLARE Test Station Safety Review**  
**Date:** December 13, 2007 11:32:44 AM CST  
**To:** Jim Strait <strait@fnal.gov>  
**Cc:** Martha Heflin <martha@fnal.gov>, Brian Degraff <degraff@fnal.gov>, Dave Pushka <pushka@fnal.gov>, Tom Page <tpage@fnal.gov>, Terry Tope <tope@fnal.gov>  
 1 Attachment, 40.5 KB

---

Jim,

The Village & Misc. Cryogenic Safety Review Panel has completed its review of the addition of a window to the FLARE liquid argon materials test station in the Proton Assembly Building (PAB). The attached memo documents our review and carries the recommendation to you to authorize operation of the system.

We are aware that future modifications/additions are planned, as itemized in the memo, and will review them before they are integrated into the system.

Phil

--

<p><b>Philip A. Pfund</b> Fermi National Accelerator Laboratory MS-316 Direct: 630-840-4784 FAX: 630-840-4529 <a href="mailto:pfund@fnal.gov">pfund@fnal.gov</a></p>
--



[PAB FLARE R...doc \(40.5 KB\)](#)

To: Jim Strait  
Particle Physics Division

From: Phil Pfund  
Chair, Village & Misc. Cryogenic Safety Review Panel

Subject: PAB FLARE Safety Review

Dear Jim,

The Village & Misc. Cryogenic Safety Review Panel has completed its review of the addition of a window to the FLARE liquid argon materials test station in the Proton Assembly Building (PAB).

Our review consisted of:

- Review of safety related documentation for the window addition. All of the FLARE documentation and updates are maintained by Terry Tope at: <http://lartpc-docdb.fnal.gov:8080/cgi-bin/ShowDocument?docid=265> login: lartpc , password: argon! The documentation related to the window is on pp 217 – 233 and consists of:
  - Component description
  - Discussion of thermal shock scenarios
  - Glass properties
- Individual panel member e-mail exchanges with Terry Tope resulting in updates to the documentation listed above.
- 12/13/07 visit to PAB by panel members to see the window assembly.

Based on the above listed review activities, we are satisfied that the proposed test set-up can be operated safely with the window installed. We recommend that you authorize the operation.

It should be noted that another future modification is planned. A second pressure vessel, referred to as “Cousin Bo”, will be added to the system after the normal operational and safety related documentation has been developed. This modification is to be reviewed by this panel before this panel makes a recommendation to operate the test station with the second pressure vessel in the system.

Regards,

Phil Pfund

On behalf of the Village & Misc. Cryogenic Safety Review Panel

Copy: Martha Heflin  
Terry Tope  
Panel Members (Brian DeGraff, Tom Page, Dave Pushka)

**From:** Jim Strait <strait@fnal.gov>  
**Subject:** **Re: FLARE Test Station Safety Review**  
**Date:** January 2, 2008 10:58:00 AM CST  
**To:** Phil Pfund <pfund@fnal.gov>  
**Cc:** Martha Heflin <martha@fnal.gov>, Brian Degraff <degraff@fnal.gov>, Dave Pushka <pushka@fnal.gov>, Tom Page <tpage@fnal.gov>, Terry Tope <tope@fnal.gov>

---

I approve the operation of the material test station, as recommended by the Village & Misc. Cryogenic Safety Review Panel. I apologize for the delay in documenting this approval.

Cheers,  
Jim

Phil Pfund wrote:

Jim, The has completed its review of the addition of a window to the FLARE liquid argon materials test station in the Proton Assembly Building (PAB). The attached memo documents our review and carries the recommendation to you to authorize operation of the system. We are aware that future modifications/additions are planned, as itemized in the memo, and will review them before they are integrated into the system. Phil

--

Philip A. Pfund  
Fermi National Accelerator Laboratory  
MS-316  
Direct: 630-840-4784  
FAX: 630-840-4529  
pfund@fnal.gov